

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022627.01

Project(s): 022627.01

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.11 CLEARING	1.500 AC	_____	 _____	_____	 _____
0020	202.19 REMOVING EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	 _____
0030	202.202 REMOVING PAVEMENT SURFACE	330.000 SY	_____	 _____	_____	 _____
0040	203.20 COMMON EXCAVATION	2,700.000 CY	_____	 _____	_____	 _____
0050	203.24 COMMON BORROW	3,200.000 CY	_____	 _____	_____	 _____
0060	203.25 GRANULAR BORROW	12,600.000 CY	_____	 _____	_____	 _____
0070	203.4340 ELASTIC INCLUSION	130.000 SY	_____	 _____	_____	 _____
0080	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	530.000 CY	_____	 _____	_____	 _____
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	4,800.000 CY	_____	 _____	_____	 _____
0100	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	650.000 T	_____	 _____	_____	 _____
0110	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	4.000 T	_____	 _____	_____	 _____
0120	403.211 HOT MIX ASPHALT (SHIMMING)	10.000 T	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022627.01

Project(s): 022627.01

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	403.213 HOT MIX ASPHALT 12.5 MM BASE	1,050.000 T	_____	 _____	_____	 _____
0140	409.15 BITUMINOUS TACK COAT - APPLIED	250.000 G	_____	 _____	_____	 _____
0150	461.131 TEMPORARY PAVEMENT	27.000 T	_____	 _____	_____	 _____
0160	501.237 NOISE ATTENUATION AND UNDERWATER NOISE MONITORING	LUMP SUM		 LUMP SUM	_____	 _____
0170	501.239 DYNAMIC LOADING TESTS - PROVIDING FOR	3.000 EA	_____	 _____	_____	 _____
0180	501.54 STEEL H-BEAM PILES 117 LBS/FT, DELIVERED	4,610.000 LF	_____	 _____	_____	 _____
0190	501.541 STEEL H-BEAM PILES 117 LBS/FT, IN PLACE	4,610.000 LF	_____	 _____	_____	 _____
0200	501.821 TEMPORARY CASING FOR PILES	LUMP SUM		 LUMP SUM	_____	 _____
0210	501.90 PILE TIPS	36.000 EA	_____	 _____	_____	 _____
0220	501.91 PILE SPLICES	102.000 EA	_____	 _____	_____	 _____
0230	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
0240	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM		 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022627.01

Project(s): 022627.01

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	502.239 STRUCTURAL CONCRETE PIERS	LUMP SUM	LUMP	SUM	_____	_____
0260	502.24 STRUCTURAL CONCRETE PIERS (PLACED UNDER WATER)	300.000 CY	_____	_____	_____	_____
0270	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM	LUMP	SUM	_____	_____
0280	502.291 SAW CUT GROOVING	LUMP SUM	LUMP	SUM	_____	_____
0290	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP	SUM	_____	_____
0300	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP	SUM	_____	_____
0310	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE: E	2.000 EA	_____	_____	_____	_____
0320	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	83,000.000 LB	_____	_____	_____	_____
0330	503.13 REINFORCING STEEL, PLACING	83,000.000 LB	_____	_____	_____	_____
0340	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	31,000.000 LB	_____	_____	_____	_____
0350	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	31,000.000 LB	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022627.01

Project(s): 022627.01

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM	LUMP	SUM	_____	_____
0370	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM	LUMP	SUM	_____	_____
0380	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	SUM	_____	_____
0390	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	SUM	_____	_____
0400	511.07 COFFERDAM: ABUT NO.1	LUMP SUM	LUMP	SUM	_____	_____
0410	511.07 COFFERDAM: ABUT NO.2	LUMP SUM	LUMP	SUM	_____	_____
0420	511.07 COFFERDAM: PIER NO.1	LUMP SUM	LUMP	SUM	_____	_____
0430	512.081 FRENCH DRAINS	LUMP SUM	LUMP	SUM	_____	_____
0440	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0450	519.60 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	75.000 LF	_____	_____	_____	_____
0460	523.52 BEARING INSTALLATION	5.000 EA	_____	_____	_____	_____
0470	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	5.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022627.01

Project(s): 022627.01

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0480	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP SUM		_____	_____
0490	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	92,270.000 LF	_____	_____	_____	_____
0500	530.31 GFRP, REINFORCEMENT BARS, PLACING	92,270.000 LF	_____	_____	_____	_____
0510	603.16 15 INCH CULVERT PIPE OPTION I	68.000 LF	_____	_____	_____	_____
0520	603.219 36 INCH CULVERT PIPE OPTION III	76.000 LF	_____	_____	_____	_____
0530	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	350.000 LF	_____	_____	_____	_____
0540	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	13.000 LF	_____	_____	_____	_____
0550	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	50.000 LF	_____	_____	_____	_____
0560	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	6.000 EA	_____	_____	_____	_____
0570	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	_____	_____	_____
0580	606.259 ANCHORAGE ASSEMBLY	1.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022627.01

Project(s): 022627.01

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	15.000 EA	_____	 _____	_____	 _____
0600	606.78 LOW VOLUME GUARDRAIL END	1.000 EA	_____	 _____	_____	 _____
0610	610.08 PLAIN RIPRAP	23.000 CY	_____	 _____	_____	 _____
0620	610.16 HEAVY RIPRAP	2,800.000 CY	_____	 _____	_____	 _____
0630	610.18 STONE DITCH PROTECTION	36.000 CY	_____	 _____	_____	 _____
0640	613.319 EROSION CONTROL BLANKET	1,250.000 SY	_____	 _____	_____	 _____
0650	615.07 LOAM	620.000 CY	_____	 _____	_____	 _____
0660	618.14 SEEDING METHOD NUMBER 2	100.000 UN	_____	 _____	_____	 _____
0670	619.12 MULCH	100.000 UN	_____	 _____	_____	 _____
0680	619.14 EROSION CONTROL MIX	1,240.000 CY	_____	 _____	_____	 _____
0690	620.58 EROSION CONTROL GEOTEXTILE	2,290.000 SY	_____	 _____	_____	 _____
0700	620.66 DRAINAGE GEOCOMPOSITE	140.000 SY	_____	 _____	_____	 _____
0710	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	6,900.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022627.01

Project(s): 022627.01

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0720	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	 _____	_____	 _____
0730	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0740	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0750	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0760	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0770	652.33 DRUM	46.000 EA	_____	 _____	_____	 _____
0780	652.34 CONE	46.000 EA	_____	 _____	_____	 _____
0790	652.35 CONSTRUCTION SIGNS	330.000 SF	_____	 _____	_____	 _____
0800	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		 LUMP SUM	_____	 _____
0810	652.38 FLAGGER	500.000 HR	_____	 _____	_____	 _____
0820	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0830	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____

8/25/2020

Maine Department of Transportation

Proposal Schedule of Items

Page 8 of 8

---

Proposal ID: 022627.01

Project(s): 022627.01

Section: 1

Total:

\_\_\_\_\_!\_\_\_\_\_

Total Bid:

\_\_\_\_\_!\_\_\_\_\_