

11/14/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 7

Proposal ID: 022638.00

Project(s): 022638.00

SECTION: 1

Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0020	202.202 REMOVING PAVEMENT SURFACE	290.000 SY				
0030	203.20 COMMON EXCAVATION	790.000 CY				
0040	203.24 COMMON BORROW	10.000 CY				
0050	203.25 GRANULAR BORROW	390.000 CY				
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	1,000.000 CY				
0070	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	60.000 CY				
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	828.000 CY				
0090	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	99.000 T				
0100	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	22.000 T				
0110	403.211 HOT MIX ASPHALT (SHIMMING)	10.000 T				
0120	403.213 HOT MIX ASPHALT 12.5 MM BASE	170.000 T				

11/14/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 7

Proposal ID: 022638.00

Project(s): 022638.00

SECTION: 1

Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	409.15 BITUMINOUS TACK COAT - APPLIED	78.000 G	_____	 _____	_____	 _____
0140	461.131 TEMPORARY PAVEMENT	110.000 T	_____	 _____	_____	 _____
0150	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP	 SUM	_____	 _____
0160	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED UNDER WATER)	280.000 CY	_____	 _____	_____	 _____
0170	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP SUM	LUMP	 SUM	_____	 _____
0180	502.291 SAW CUT GROOVING	LUMP SUM	LUMP	 SUM	_____	 _____
0190	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP	 SUM	_____	 _____
0200	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP	 SUM	_____	 _____
0210	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	24,600.000 LB	_____	 _____	_____	 _____
0220	503.13 REINFORCING STEEL, PLACING	24,600.000 LB	_____	 _____	_____	 _____
0230	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	6,300.000 LB	_____	 _____	_____	 _____

11/14/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 7

Proposal ID: 022638.00

Project(s): 022638.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	6,300.000 LB	_____	_____	_____	_____
0250	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP SUM	_____	_____	_____
0260	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED	LUMP SUM	LUMP SUM	_____	_____	_____
0270	511.07 COFFERDAM: ABUT NO.1	LUMP SUM	LUMP SUM	_____	_____	_____
0280	511.07 COFFERDAM: ABUT NO.2	LUMP SUM	LUMP SUM	_____	_____	_____
0290	512.081 FRENCH DRAINS	LUMP SUM	LUMP SUM	_____	_____	_____
0300	513.22 CRUSHED STONE SLOPE PROTECTION	26.000 SY	_____	_____	_____	_____
0310	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA	_____	_____	_____	_____
0320	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP SUM	_____	_____	_____
0330	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP SUM	_____	_____	_____
0340	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA	_____	_____	_____	_____

11/14/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 7

Proposal ID: 022638.00

Project(s): 022638.00

SECTION: 1

Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN				
0360	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	14,820.000 LF				
0370	530.31 GFRP, REINFORCEMENT BARS, PLACING	14,820.000 LF				
0380	535.622 PRESTRESSED STRUCTURAL CONCRETE NEXT BEAM	LUMP SUM				
0390	603.17 18 INCH CULVERT PIPE OPTION I	37.000 LF				
0400	606.1722 BRIDGE TRANSITION - TYPE 2	2.000 EA				
0410	606.1722 BRIDGE TRANSITION - TYPE 2 Modified	2.000 EA				
0420	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	32.000 LF				
0430	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	25.000 LF				
0440	606.259 ANCHORAGE ASSEMBLY	3.000 EA				
0450	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	3.000 EA				

11/14/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 7

Proposal ID: 022638.00

Project(s): 022638.00

SECTION: 1

Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	 _____	_____	 _____
0470	606.78 LOW VOLUME GUARDRAIL END - TYPE 3	1.000 EA	_____	 _____	_____	 _____
0480	610.08 PLAIN RIPRAP	120.000 CY	_____	 _____	_____	 _____
0490	610.16 HEAVY RIPRAP	140.000 CY	_____	 _____	_____	 _____
0500	610.18 STONE DITCH PROTECTION	17.000 CY	_____	 _____	_____	 _____
0510	615.07 LOAM	4.000 CY	_____	 _____	_____	 _____
0520	618.14 SEEDING METHOD NUMBER 2	1.000 UN	_____	 _____	_____	 _____
0530	619.12 MULCH	1.000 UN	_____	 _____	_____	 _____
0540	619.14 EROSION CONTROL MIX	8.000 CY	_____	 _____	_____	 _____
0550	620.58 EROSION CONTROL GEOTEXTILE	410.000 SY	_____	 _____	_____	 _____
0560	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,350.000 LF	_____	 _____	_____	 _____
0570	627.77 REMOVING PAVEMENT MARKINGS	200.000 SF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 7

Proposal ID: 022638.00

Project(s): 022638.00

SECTION: 1

Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	800.000 LF	_____	 _____	_____	 _____
0590	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	 _____	_____	 _____
0600	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0610	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0620	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0630	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0640	637.071 DUST CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0650	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0660	643.72 TEMPORARY TRAFFIC SIGNAL Hodgdon Mills Road	LUMP SUM	LUMP SUM		_____	 _____
0670	652.312 TYPE III BARRICADE	6.000 EA	_____	 _____	_____	 _____
0680	652.33 DRUM	50.000 EA	_____	 _____	_____	 _____
0690	652.34 CONE	50.000 EA	_____	 _____	_____	 _____

11/14/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 7

Proposal ID: 022638.00

Project(s): 022638.00

SECTION: 1

Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0700	652.35 CONSTRUCTION SIGNS	270.000 SF	_____	 _____	_____	 _____
0710	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	_____	 LUMP SUM	_____	 _____
0720	652.38 FLAGGER	400.000 HR	_____	 _____	_____	 _____
0730	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0740	659.10 MOBILIZATION	LUMP SUM	_____	 LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____