

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	4.000 EA	_____	_____	_____	_____
0020	201.24 REMOVING STUMP	5.000 EA	_____	_____	_____	_____
0030	202.08 REMOVING BUILDING NO.: 1	LUMP SUM	LUMP SUM		_____	_____
0040	202.12 REMOVING EXISTING STRUCTURAL CONCRETE	46.000 CY	_____	_____	_____	_____
0050	202.15 REMOVING EXISTING MANHOLE OR CATCH BASIN	55.000 EA	_____	_____	_____	_____
0060	202.202 REMOVING PAVEMENT SURFACE	950.000 SY	_____	_____	_____	_____
0070	203.20 COMMON EXCAVATION	28,100.000 CY	_____	_____	_____	_____
0080	203.2312 HEALTH AND SAFETY PLAN	LUMP SUM	LUMP SUM		_____	_____
0090	203.2333 DISPOSAL TREATMENT OF SPECIAL EXCAVATION	1.000 T	_____	_____	_____	_____
0100	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	200.000 CY	_____	_____	_____	_____
0110	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	200.000 CY	_____	_____	_____	_____

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	23,840.000 CY	_____	 _____	_____	 _____
0130	304.14 AGGREGATE BASE COURSE - TYPE A	75.000 CY	_____	 _____	_____	 _____
0140	403.2071 19 MM POLYMER MODIFIED HOT MIX ASPHALT	5,200.000 T	_____	 _____	_____	 _____
0150	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	2,790.000 T	_____	 _____	_____	 _____
0160	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	1,160.000 T	_____	 _____	_____	 _____
0170	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	2,550.000 T	_____	 _____	_____	 _____
0180	409.15 BITUMINOUS TACK COAT - APPLIED	1,950.000 G	_____	 _____	_____	 _____
0190	502.32 STRUCTURAL CONCRETE CULVERT ENDWALLS	5.000 CY	_____	 _____	_____	 _____
0200	502.565 CONCRETE FILL (PIPE FILL)	120.000 CY	_____	 _____	_____	 _____
0210	524.301 TEMPORARY STRUCTURAL SUPPORT CATCH BASIN REPLACEMENTS STA 55+93 RT, 56+38 RT	LUMP SUM	_____	 LUMP SUM	_____	 _____

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0220	524.301 TEMPORARY STRUCTURAL SUPPORT DRAINAGE OUTLET STA 49+35 LT	LUMP SUM	LUMP	SUM	_____	_____
0230	525.329 DRY-LAID STONE WALL - REMOVE AND RESET CONCRETE BLOCK RETAINING WALL - REMOVE AND RESET	LUMP SUM	LUMP	SUM	_____	_____
0240	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0250	602.30 FLOWABLE CONCRETE FILL	55.000 CY	_____	_____	_____	_____
0260	603.001 INSPECT DRAINAGE STRUCTURE/PIPE (CAMERA)	1.000 EA	_____	_____	_____	_____
0270	603.01 CULVERT BORING/JACKING INSTALLATION 24" CULV OPTION III BORING/JACKING	LUMP SUM	LUMP	SUM	_____	_____
0280	603.05 6 INCH PVC PIPE	7.000 LF	_____	_____	_____	_____
0290	603.1311 8 " PVC PIPE	30.000 LF	_____	_____	_____	_____
0300	603.155 12 INCH REINFORCED CONCRETE PIPE CLASS III	60.000 LF	_____	_____	_____	_____
0310	603.159 12 INCH CULVERT PIPE OPTION III	440.000 LF	_____	_____	_____	_____

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0320	603.165 15 INCH REINFORCED CONCRETE PIPE CLASS III	170.000 LF	_____	_____	_____	_____
0330	603.169 15 INCH CULVERT PIPE OPTION III	320.000 LF	_____	_____	_____	_____
0340	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	430.000 LF	_____	_____	_____	_____
0350	603.179 18 INCH CULVERT PIPE OPTION III	290.000 LF	_____	_____	_____	_____
0360	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	100.000 LF	_____	_____	_____	_____
0370	603.199 24 INCH CULVERT PIPE OPTION III	680.000 LF	_____	_____	_____	_____
0380	604.072 CATCH BASIN TYPE A1-C	8.250 EA	_____	_____	_____	_____
0390	604.077 72 INCH CATCH BASIN TYPE A1-C	1.625 EA	_____	_____	_____	_____
0400	604.092 CATCH BASIN TYPE B1-C	42.375 EA	_____	_____	_____	_____
0410	604.097 72 INCH CATCH BASIN TYPE B1-C	1.000 EA	_____	_____	_____	_____
0420	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	1.000 EA	_____	_____	_____	_____
0430	604.243 CATCH BASIN TYPE F3-C	1.000 EA	_____	_____	_____	_____

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0440	604.245 CATCH BASIN TYPE F4-C	3.000 EA				
0450	604.247 CATCH BASIN TYPE F5-C	5.000 EA				
0460	604.249 CATCH BASIN TYPE F6-C	1.000 EA				
0470	604.252 CATCH BASIN TYPE A5-C	16.500 EA				
0480	604.252 CATCH BASIN TYPE A5-C 72" CATCH BASIN TYPE A5-C	1.250 EA				
0490	604.262 CATCH BASIN TYPE B5-C	27.500 EA				
0500	604.2622 72 " CATCH BASIN TYPE B5-C	1.000 EA				
0510	605.09 6 INCH UNDERDRAIN TYPE B	5,850.000 LF				
0520	605.11 12 INCH UNDERDRAIN TYPE C	2,500.000 LF				
0530	605.12 15 INCH UNDERDRAIN TYPE C	450.000 LF				
0540	605.13 18 INCH UNDERDRAIN TYPE C	1,300.000 LF				
0550	605.15 24 INCH UNDERDRAIN TYPE C	500.000 LF				
0560	606.356 UNDERDRAIN DELINEATOR POST	11.000 EA				

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0570	606.47 SINGLE WOOD POST	3.000 EA				
0580	607.24 REMOVE AND RESET FENCE	540.000 LF				
0590	608.08 REINFORCED CONCRETE SIDEWALK	1,900.000 SY				
0600	608.10 BRICK SIDEWALK, REMOVE AND REBUILD	21.000 SY				
0610	608.26 CURB RAMP DETECTABLE WARNING FIELD	300.000 SF				
0620	609.11 VERTICAL CURB TYPE 1	1,750.000 LF				
0630	609.1101 SPECIAL GRANITE CURB - 48"	390.000 LF				
0640	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	200.000 LF				
0650	609.21 CONCRETE SLIPFORM CURB	6,250.000 LF				
0660	609.219 CONCRETE SLIPFORM CURB - TERMINAL END	1,150.000 LF				
0670	609.234 TERMINAL CURB TYPE 1 - 4 FOOT	8.000 EA				
0680	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	1.000 EA				

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0690	609.238 TERMINAL CURB TYPE 1 - 8 FOOT	37.000 EA	_____	_____	_____	_____
0700	609.2381 TERMINAL CURB TYPE 1 - 8' CIRCULAR	7.000 EA	_____	_____	_____	_____
0710	609.38 RESET CURB TYPE 1	450.000 LF	_____	_____	_____	_____
0720	610.08 PLAIN RIPRAP	8.000 CY	_____	_____	_____	_____
0730	610.16 HEAVY RIPRAP	120.000 CY	_____	_____	_____	_____
0740	610.18 STONE DITCH PROTECTION	9.000 CY	_____	_____	_____	_____
0750	613.319 EROSION CONTROL BLANKET	870.000 SY	_____	_____	_____	_____
0760	615.07 LOAM	1,145.000 CY	_____	_____	_____	_____
0770	618.13 SEEDING METHOD NUMBER 1	92.000 UN	_____	_____	_____	_____
0780	619.12 MULCH	92.000 UN	_____	_____	_____	_____
0790	620.58 EROSION CONTROL GEOTEXTILE	325.000 SY	_____	_____	_____	_____
0800	626.11 PRECAST CONCRETE JUNCTION BOX	8.000 EA	_____	_____	_____	_____
0810	626.421 24 INCH DIAMETER FOUNDATION	70.000 LF	_____	_____	_____	_____

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 8 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0820	627.18 12 " SOLID WHITE PAVEMENT MARKING	10.000 LF	_____	 _____	_____	 _____
0830	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	21,770.000 LF	_____	 _____	_____	 _____
0840	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	2,700.000 SF	_____	 _____	_____	 _____
0850	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	54,000.000 LF	_____	 _____	_____	 _____
0860	629.05 HAND LABOR, STRAIGHT TIME	100.000 HR	_____	 _____	_____	 _____
0870	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0880	631.11 AIR TOOL (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0890	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0900	631.14 GRADER (INCLUDING OPERATOR)	60.000 HR	_____	 _____	_____	 _____
0910	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0920	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 9 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0930	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0940	631.21 ROAD BROOM (INCLUDING OPERATORS AND HAULER)	25.000 HR	_____	 _____	_____	 _____
0950	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0960	634.208 REMOVE AND RESET LIGHT STANDARDS	4.000 EA	_____	 _____	_____	 _____
0970	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0980	642.15 PRECAST CONCRETE STEPS	1.000 EA	_____	 _____	_____	 _____
0990	643.621 RECTANGULAR RAPID FLASHING BEACON ASSEMBLY	3.000 EA	_____	 _____	_____	 _____
1000	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	102.000 EA	_____	 _____	_____	 _____
1010	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	102.000 EA	_____	 _____	_____	 _____
1020	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	66.000 SF	_____	 _____	_____	 _____

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 10 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1030	652.312 TYPE III BARRICADE	26.000 EA				
1040	652.33 DRUM	150.000 EA				
1050	652.34 CONE	200.000 EA				
1060	652.35 CONSTRUCTION SIGNS	1,800.000 SF				
1070	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	870.000 CD				
1080	652.38 FLAGGER	8,452.000 HR				
1090	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	6.000 EA				
1100	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM				
1110	659.10 MOBILIZATION	LUMP SUM				
1120	660.21 ON-THE-JOB TRAINING (BID)	2,000.000 HR				
1130	801.03 TEST PITS	23.000 EA				
1140	801.071 TEMPORARY SEWER BY-PASS NEW SEWER INSTALLATION	LUMP SUM				

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 11 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1150	801.071 TEMPORARY SEWER BY-PASS SEWER REHAB	LUMP SUM		LUMP SUM		
1160	801.141 4" PVC SANITARY SEWER (SDR-35)	1,320.000 LF				
1170	801.16 6 INCH PVC SANITARY SEWER (SDR-35)	80.000 LF				
1180	801.17 8 INCH PVC SANITARY SEWER (SDR-35)	1,140.000 LF				
1190	802.211 RELINE EXISTING SEWER (UV CIPP LINER, 10-INCH DIAMETER)	895.000 LF				
1200	802.211 RELINE EXISTING SEWER (UV CIPP LINER, 12-INCH DIAMETER)	930.000 LF				
1210	802.211 RELINE EXISTING SEWER (UV CIPP LINER, 15-INCH DIAMETER)	885.000 LF				
1220	802.211 RELINE EXISTING SEWER (UV CIPP LINER, 18-INCH DIAMETER)	620.000 LF				
1230	802.211 RELINE EXISTING SEWER (UV CIPP LINER, 24-INCH DIAMETER)	135.000 LF				
1240	802.211 RELINE EXISTING SEWER (UV CIPP LINER, 8-INCH DIAMETER)	1,520.000 LF				
1250	803.16 4 FOOT DIAMETER PRECAST SEWER MANHOLE	5.000 EA				

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 12 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1260	803.1732 SEWER MANHOLE - 4 FOOT DIAMETER	90.000 VF	_____	 _____	_____	 _____
1270	812.161 ALTER SEWER MANHOLE	26.000 EA	_____	 _____	_____	 _____
1280	812.164 REBUILDING SEWER MANHOLE	2.000 EA	_____	 _____	_____	 _____
1290	822.33 6 INCH CLASS 52 DUCTILE IRON PIPE	210.000 LF	_____	 _____	_____	 _____
1300	822.34 8 INCH CLASS 52 DUCTILE IRON PIPE	250.000 LF	_____	 _____	_____	 _____
1310	822.36 12 INCH DUCTILE IRON PIPE	2,250.000 LF	_____	 _____	_____	 _____
1320	822.36032 CLEAN & LINE WATER MAIN UNDER RAILROAD CROSSING	200.000 LF	_____	 _____	_____	 _____
1330	823.311 12 INCH GATE VALVE WITH BOX	8.000 EA	_____	 _____	_____	 _____
1340	823.3251 8 INCH GATE VALVE WITH BOX	1.000 EA	_____	 _____	_____	 _____
1350	823.33 6 INCH GATE VALVE WITH BOX	7.000 EA	_____	 _____	_____	 _____
1360	823.3332 GATE VALVE BOX, REPLACE	27.000 EA	_____	 _____	_____	 _____
1370	824.3010 HYDRANT ASSEMBLY	4.000 EA	_____	 _____	_____	 _____
1380	824.31 REMOVE FIRE HYDRANT	4.000 EA	_____	 _____	_____	 _____

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 13 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1390	824.32 REMOVE/RESET HYDRANT	3.000 EA				
1400	825.312 3/4 INCH CURB STOP	39.000 EA				
1410	825.32 2 INCH CORPORATION	5.000 EA				
1420	825.321 1 INCH CORPORATION	15.000 EA				
1430	825.322 2" CURB STOP	5.000 EA				
1440	825.331 1" CURB STOP	15.000 EA				
1450	825.422 2" PLASTIC SERVICE	180.000 LF				
1460	825.430 1" CTS SERVICE	450.000 LF				
1470	825.4301 3/4" CTS SERVICE	920.000 LF				
1480	825.5411 TEMPORARY WATER MAIN	LUMP SUM				
1490	827.302 UNSUITABLE SOIL EXCAVATION - BELOW GRADE	300.000 CY				
1500	827.331 TRENCH INSULATION	30.000 SY				
1510	910.30 SPECIAL WORK MANHOLE-JOINT GROUTING	13.000 EA				

7/15/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 14 of 14

Proposal ID: 022643.00

Project(s): 022643.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1520	910.30 SPECIAL WORK MANHOLE-POINT REPAIR ON WALL INTERIOR	13.000 EA	_____	_____	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____