

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022665.00

Project(s): 022665.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	490.000 CY	_____	 _____	_____	 _____
0020	203.25 GRANULAR BORROW	120.000 CY	_____	 _____	_____	 _____
0030	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	10.000 CY	_____	 _____	_____	 _____
0040	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	10.000 CY	_____	 _____	_____	 _____
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	385.000 CY	_____	 _____	_____	 _____
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	50.000 T	_____	 _____	_____	 _____
0070	403.213 HOT MIX ASPHALT 12.5 MM BASE	83.000 T	_____	 _____	_____	 _____
0080	409.15 BITUMINOUS TACK COAT - APPLIED	18.000 G	_____	 _____	_____	 _____
0090	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	30.000 CY	_____	 _____	_____	 _____
0100	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	800.000 LB	_____	 _____	_____	 _____
0110	503.13 REINFORCING STEEL, PLACING	800.000 LB	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022665.00

Project(s): 022665.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0130	511.07 COFFERDAM: Downstream	LUMP SUM	LUMP	SUM	_____	_____
0140	511.07 COFFERDAM: Upstream	LUMP SUM	LUMP	SUM	_____	_____
0150	512.081 FRENCH DRAINS	LUMP SUM	LUMP	SUM	_____	_____
0160	534.71 PRECAST CONCRETE BOX CULVERT	LUMP SUM	LUMP	SUM	_____	_____
0170	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	175.000 LF	_____	_____	_____	_____
0180	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	25.000 LF	_____	_____	_____	_____
0190	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	1.000 EA	_____	_____	_____	_____
0200	610.08 PLAIN RIPRAP	10.000 CY	_____	_____	_____	_____
0210	613.319 EROSION CONTROL BLANKET	25.000 SY	_____	_____	_____	_____
0220	615.07 LOAM	48.000 CY	_____	_____	_____	_____
0230	618.14 SEEDING METHOD NUMBER 2	8.000 UN	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022665.00

Project(s): 022665.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	619.12 MULCH	8.000 UN	_____	 _____	_____	 _____
0250	619.14 EROSION CONTROL MIX	5.000 CY	_____	 _____	_____	 _____
0260	620.58 EROSION CONTROL GEOTEXTILE	12.000 SY	_____	 _____	_____	 _____
0270	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	500.000 LF	_____	 _____	_____	 _____
0280	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0290	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0300	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0310	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0320	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0330	652.33 DRUM	50.000 EA	_____	 _____	_____	 _____
0340	652.34 CONE	100.000 EA	_____	 _____	_____	 _____
0350	652.35 CONSTRUCTION SIGNS	1,000.000 SF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022665.00

Project(s): 022665.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	40.000 CD	_____	 _____	_____	 _____
0370	652.38 FLAGGER	300.000 HR	_____	 _____	_____	 _____
0380	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA	_____	 _____	_____	 _____
0390	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM	_____	 _____
0400	659.10 MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
0410	674.10 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	64.000 SF	_____	 _____	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____