

7/3/2020

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 4

Proposal ID: 022668.00

Project(s): 022668.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	455.000 CY	_____	 _____	_____	 _____
0020	203.25 GRANULAR BORROW	350.000 CY	_____	 _____	_____	 _____
0030	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	475.000 CY	_____	 _____	_____	 _____
0040	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	74.000 T	_____	 _____	_____	 _____
0050	403.213 HOT MIX ASPHALT 12.5 MM BASE	124.000 T	_____	 _____	_____	 _____
0060	409.15 BITUMINOUS TACK COAT - APPLIED	16.000 G	_____	 _____	_____	 _____
0070	511.07 COFFERDAM: Downstream	LUMP SUM		 LUMP SUM	_____	 _____
0080	511.07 COFFERDAM: Upstream	LUMP SUM		 LUMP SUM	_____	 _____
0090	602.30 FLOWABLE CONCRETE FILL	16.000 CY	_____	 _____	_____	 _____
0100	603.4073 128" X 83" POLYMER COATED CORRUGATED STEEL PIPE	96.000 LF	_____	 _____	_____	 _____
0110	606.363 GUARDRAIL REMOVE AND DISPOSE	166.000 LF	_____	 _____	_____	 _____
0120	610.08 PLAIN RIPRAP	45.000 CY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022668.00

Project(s): 022668.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	613.319 EROSION CONTROL BLANKET	10.000 SY	_____	 _____	_____	 _____
0140	615.10 DIRTY BORROW	29.000 CY	_____	 _____	_____	 _____
0150	618.14 SEEDING METHOD NUMBER 2	5.000 UN	_____	 _____	_____	 _____
0160	619.12 MULCH	5.000 UN	_____	 _____	_____	 _____
0170	619.14 EROSION CONTROL MIX	10.000 CY	_____	 _____	_____	 _____
0180	620.58 EROSION CONTROL GEOTEXTILE	39.000 SY	_____	 _____	_____	 _____
0190	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	450.000 LF	_____	 _____	_____	 _____
0200	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	 _____	_____	 _____
0210	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0220	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0230	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0240	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022668.00

Project(s): 022668.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	652.33 DRUM	50.000 EA	_____	 _____	_____	 _____
0260	652.34 CONE	100.000 EA	_____	 _____	_____	 _____
0270	652.35 CONSTRUCTION SIGNS	350.000 SF	_____	 _____	_____	 _____
0280	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	65.000 CD	_____	 _____	_____	 _____
0290	652.38 FLAGGER	790.000 HR	_____	 _____	_____	 _____
0300	652.61 STAGED CONSTRUCTION AND TRAFFIC CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0310	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0320	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
0330	803.181 REMOVE/ ABANDON MANHOLE	2.000 EA	_____	 _____	_____	 _____
0340	822.3405 8 INCH CLASS 52 DUCTILE IRON PIPE PUSH ON JOINT	140.000 LF	_____	 _____	_____	 _____
0350	822.3605 12" CLASS 52 DUCTILE IRON PIPE PUSH ON JOINT	10.000 LF	_____	 _____	_____	 _____
0360	822.3705 16" CL 52 DI PIPE WITH PUSH ON JOINT	170.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022668.00

Project(s): 022668.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	823.341 AIR RELEASE VALVE 1"	1.000 EA	_____	_____	_____	_____
0380	823.375 16" BUTTERFLY VALVE	2.000 EA	_____	_____	_____	_____
0390	824.3021 HYDRANT ASSEMBLY (TEE/GATE VALVE)	1.000 EA	_____	_____	_____	_____
0400	825.542 TEMPORARY WATER SERVICE	1.000 EA	_____	_____	_____	_____
0410	825.57 1 " WATER SERVICE - RECONNECT	1.000 EA	_____	_____	_____	_____
0420	825.62 8" HIGH DENSITY POLYETHYLENE WATER MAIN	240.000 LF	_____	_____	_____	_____
0430	825.63 16" HIGH DENSITY POLYETHELENE WATER MAIN	240.000 LF	_____	_____	_____	_____
<b>Section: 1</b>			<b>Total:</b>		_____	_____
			<b>Total Bid:</b>		_____	_____