

1/28/2021

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 4

Proposal ID: 022831.00

Project(s): 022831.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	230.000 SY	_____	 _____	_____	 _____
0020	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	25.000 CY	_____	 _____	_____	 _____
0030	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	65.000 CY	_____	 _____	_____	 _____
0040	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	80.000 T	_____	 _____	_____	 _____
0050	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	65.000 T	_____	 _____	_____	 _____
0060	403.213 HOT MIX ASPHALT 12.5 MM BASE	105.000 T	_____	 _____	_____	 _____
0070	409.15 BITUMINOUS TACK COAT - APPLIED	40.000 G	_____	 _____	_____	 _____
0080	603.165 15 INCH REINFORCED CONCRETE PIPE CLASS III	40.000 LF	_____	 _____	_____	 _____
0090	603.169 15 INCH CULVERT PIPE OPTION III	56.000 LF	_____	 _____	_____	 _____
0100	603.179 18 INCH CULVERT PIPE OPTION III	108.000 LF	_____	 _____	_____	 _____
0110	603.199 24 INCH CULVERT PIPE OPTION III	60.000 LF	_____	 _____	_____	 _____
0120	604.072 CATCH BASIN TYPE A1-C	11.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022831.00

Project(s): 022831.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	605.12 15 INCH UNDERDRAIN TYPE C	365.000 LF	_____	 _____	_____	 _____
0140	605.13 18 INCH UNDERDRAIN TYPE C	188.000 LF	_____	 _____	_____	 _____
0150	606.64 GUARDRAIL THRIE BEAM - DOUBLE RAIL	140.000 LF	_____	 _____	_____	 _____
0160	606.72 GUARDRAIL THRIE BEAM GREATER THAN 15 FOOT RADIUS	25.000 LF	_____	 _____	_____	 _____
0170	608.26 CURB RAMP DETECTABLE WARNING FIELD	24.000 SF	_____	 _____	_____	 _____
0180	608.45 CONSTRUCT SIDEWALK	285.000 SY	_____	 _____	_____	 _____
0190	609.31 CURB TYPE 3	444.000 LF	_____	 _____	_____	 _____
0200	615.07 LOAM	28.000 CY	_____	 _____	_____	 _____
0210	618.13 SEEDING METHOD NUMBER 1	2.000 UN	_____	 _____	_____	 _____
0220	619.12 MULCH	2.000 UN	_____	 _____	_____	 _____
0230	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,205.000 LF	_____	 _____	_____	 _____
0240	629.05 HAND LABOR, STRAIGHT TIME	30.000 HR	_____	 _____	_____	 _____

## Maine Department of Transportation

## Proposal Schedule of Items

Proposal ID: 022831.00

Project(s): 022831.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	60.000 HR	_____	 _____	_____	 _____
0260	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0270	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	20.000 HR	_____	 _____	_____	 _____
0280	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	60.000 HR	_____	 _____	_____	 _____
0290	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0300	642.15 PRECAST CONCRETE STEPS	1.000 EA	_____	 _____	_____	 _____
0310	652.33 DRUM	50.000 EA	_____	 _____	_____	 _____
0320	652.34 CONE	100.000 EA	_____	 _____	_____	 _____
0330	652.35 CONSTRUCTION SIGNS	250.000 SF	_____	 _____	_____	 _____
0340	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	70.000 CD	_____	 _____	_____	 _____
0350	652.38 FLAGGER	875.000 HR	_____	 _____	_____	 _____
0360	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____

1/28/2021

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 4

Proposal ID: 022831.00

Project(s): 022831.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	659.10 MOBILIZATION	LUMP SUM		LUMP SUM	_____	_____
0380	673.10 WET CAST SMALL LANDSCAPE BLOCK WALL	84.000 SF	_____	_____	_____	_____
<b>Section: 1</b>			<b>Total:</b>		_____	_____
			<b>Total Bid:</b>		_____	_____