

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022934.00

Project(s): 022934.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	2,400.000 CY	_____	 _____	_____	 _____
0020	203.24 COMMON BORROW	500.000 CY	_____	 _____	_____	 _____
0030	203.25 GRANULAR BORROW	1,230.000 CY	_____	 _____	_____	 _____
0040	203.33 SPECIAL FILL	255.000 CY	_____	 _____	_____	 _____
0050	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	50.000 CY	_____	 _____	_____	 _____
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1,500.000 CY	_____	 _____	_____	 _____
0070	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	180.000 T	_____	 _____	_____	 _____
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	300.000 T	_____	 _____	_____	 _____
0090	409.15 BITUMINOUS TACK COAT - APPLIED	65.000 G	_____	 _____	_____	 _____
0100	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	_____	 LUMP SUM	_____	 _____
0110	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM	_____	 LUMP SUM	_____	 _____
0120	511.07 COFFERDAM: UPSTREAM	LUMP SUM	_____	 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022934.00

Project(s): 022934.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	534.71 PRECAST CONCRETE BOX CULVERT	LUMP SUM				
0140	603.17 18 INCH CULVERT PIPE OPTION I	44.000 LF				
0150	603.43 36 INCH REINFORCED CONCRETE PIPE CLASS IV	76.000 LF				
0160	603.55 CONCRETE PIPE TIES	4.000 GP				
0170	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	343.750 LF				
0180	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	50.000 LF				
0190	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	2.000 EA				
0200	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA				
0210	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA				
0220	610.08 PLAIN RIPRAP	435.000 CY				
0230	610.210 STREAM CHANNEL ROCK	425.000 CY				
0240	610.212 STREAMBED ROCK FEATURES	45.000 CY				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022934.00

Project(s): 022934.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	613.319 EROSION CONTROL BLANKET	160.000 SY	_____	 _____	_____	 _____
0260	615.10 DIRTY BORROW	145.000 CY	_____	 _____	_____	 _____
0270	618.14 SEEDING METHOD NUMBER 2	24.000 UN	_____	 _____	_____	 _____
0280	619.12 MULCH	24.000 UN	_____	 _____	_____	 _____
0290	619.14 EROSION CONTROL MIX	50.000 CY	_____	 _____	_____	 _____
0300	620.58 EROSION CONTROL GEOTEXTILE	715.000 SY	_____	 _____	_____	 _____
0310	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,590.000 LF	_____	 _____	_____	 _____
0320	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0330	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0340	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0350	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0360	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	_____	 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022934.00

Project(s): 022934.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	652.33 DRUM	50.000 EA	_____	 _____	_____	 _____
0380	652.34 CONE	50.000 EA	_____	 _____	_____	 _____
0390	652.35 CONSTRUCTION SIGNS	395.000 SF	_____	 _____	_____	 _____
0400	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	62.000 CD	_____	 _____	_____	 _____
0410	652.38 FLAGGER	125.000 HR	_____	 _____	_____	 _____
0420	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	 _____	_____	 _____
0430	652.61 STAGED CONSTRUCTION AND TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____	
0440	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	
0450	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	
Section: 1			Total:		_____	
			Total Bid:		_____	