

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023118.00

Project(s): 023118.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	715.000 SY	_____	 _____	_____	 _____
0020	203.20 COMMON EXCAVATION	930.000 CY	_____	 _____	_____	 _____
0030	203.2318 DISPOSAL OF SPECIAL WASTE	50.000 T	_____	 _____	_____	 _____
0040	203.25 GRANULAR BORROW	52.000 CY	_____	 _____	_____	 _____
0050	203.33 SPECIAL FILL	55.000 CY	_____	 _____	_____	 _____
0060	203.55 CULVERT BEDDING STONE	110.000 CY	_____	 _____	_____	 _____
0070	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	11.000 CY	_____	 _____	_____	 _____
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	850.000 CY	_____	 _____	_____	 _____
0090	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	167.000 T	_____	 _____	_____	 _____
0100	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	2.000 T	_____	 _____	_____	 _____
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	187.000 T	_____	 _____	_____	 _____
0120	409.15 BITUMINOUS TACK COAT - APPLIED	90.000 G	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023118.00

Project(s): 023118.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0140	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0150	511.07 COFFERDAM: UPSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0160	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0170	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0180	534.71 PRECAST CONCRETE BOX CULVERT	LUMP SUM	LUMP	SUM	_____	_____
0190	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	405.000 LF	_____	_____	_____	_____
0200	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	25.000 LF	_____	_____	_____	_____
0210	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	3.000 EA	_____	_____	_____	_____
0220	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA	_____	_____	_____	_____
0230	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023118.00

Project(s): 023118.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	610.08 PLAIN RIPRAP	60.000 CY	_____	 _____	_____	 _____
0250	610.210 STREAM CHANNEL ROCK	60.000 CY	_____	 _____	_____	 _____
0260	613.319 EROSION CONTROL BLANKET	123.000 SY	_____	 _____	_____	 _____
0270	615.07 LOAM	53.000 CY	_____	 _____	_____	 _____
0280	618.14 SEEDING METHOD NUMBER 2	9.000 UN	_____	 _____	_____	 _____
0290	619.12 MULCH	9.000 UN	_____	 _____	_____	 _____
0300	619.14 EROSION CONTROL MIX	105.000 CY	_____	 _____	_____	 _____
0310	620.54 STABILIZATION/REINFORCEMENT GEOTEXTILE	360.000 SY	_____	 _____	_____	 _____
0320	620.58 EROSION CONTROL GEOTEXTILE	150.000 SY	_____	 _____	_____	 _____
0330	620.65 REINFORCEMENT GEOGRID	170.000 SY	_____	 _____	_____	 _____
0340	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,575.000 LF	_____	 _____	_____	 _____
0350	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023118.00

Project(s): 023118.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0370	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0380	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0390	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0400	652.33 DRUM	10.000 EA	_____	 _____	_____	 _____
0410	652.34 CONE	20.000 EA	_____	 _____	_____	 _____
0420	652.35 CONSTRUCTION SIGNS	1,130.000 SF	_____	 _____	_____	 _____
0430	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		 LUMP SUM	_____	 _____
0440	652.38 FLAGGER	200.000 HR	_____	 _____	_____	 _____
0450	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	 _____	_____	 _____
0460	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0470	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023118.00

Project(s): 023118.00

Section: 1

Total:

_____!_____

Total Bid:

_____!_____