

11/14/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 4

Proposal ID: 023133.00

Project(s): 023133.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	400.000 CY	_____	_____	_____	_____
0020	203.24 COMMON BORROW	470.000 CY	_____	_____	_____	_____
0030	203.25 GRANULAR BORROW	190.000 CY	_____	_____	_____	_____
0040	203.33 SPECIAL FILL	60.000 CY	_____	_____	_____	_____
0050	203.35 CRUSHED STONE FILL	90.000 CY	_____	_____	_____	_____
0060	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	20.000 CY	_____	_____	_____	_____
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	620.000 CY	_____	_____	_____	_____
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	100.000 T	_____	_____	_____	_____
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	10.000 T	_____	_____	_____	_____
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	160.000 T	_____	_____	_____	_____
0110	409.15 BITUMINOUS TACK COAT - APPLIED	80.000 G	_____	_____	_____	_____
0120	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM	LUMP SUM		_____	_____

11/14/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 4

Proposal ID: 023133.00

Project(s): 023133.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	511.07 COFFERDAM: UPSTREAM	LUMP SUM				
0140	603.16 15 INCH CULVERT PIPE OPTION I	50.000 LF				
0150	603.299 96" CULVERT PIPE OPTION III	110.000 LF				
0160	610.08 PLAIN RIPRAP	30.000 CY				
0170	610.210 STREAM CHANNEL ROCK	15.000 CY				
0180	613.319 EROSION CONTROL BLANKET	120.000 SY				
0190	615.10 DIRTY BORROW	160.000 CY				
0200	618.14 SEEDING METHOD NUMBER 2	26.000 UN				
0210	619.12 MULCH	26.000 UN				
0220	619.14 EROSION CONTROL MIX	50.000 CY				
0230	620.54 STABILIZATION/REINFORCEMENT GEOTEXTILE	380.000 SY				
0240	620.65 REINFORCEMENT GEOGRID	130.000 SY				
0250	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,275.000 LF				

11/14/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 4

Proposal ID: 023133.00

Project(s): 023133.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0260	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	_____	_____	_____
0270	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0280	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0290	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____
0300	643.72 TEMPORARY TRAFFIC SIGNAL Rte.106	LUMP SUM	LUMP SUM		_____	_____
0310	652.33 DRUM	20.000 EA	_____	_____	_____	_____
0320	652.34 CONE	50.000 EA	_____	_____	_____	_____
0330	652.35 CONSTRUCTION SIGNS	300.000 SF	_____	_____	_____	_____
0340	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	30.000 CD	_____	_____	_____	_____
0350	652.38 FLAGGER	625.000 HR	_____	_____	_____	_____
0360	652.61 STAGED CONSTRUCTION AND TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____	_____
0370	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____

11/14/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 4

Proposal ID: 023133.00

Project(s): 023133.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0380	659.10 MOBILIZATION	LUMP SUM		LUMP SUM		
Section: 1			Total:			
			Total Bid:			