

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.13 REMOVING EXISTING RAILINGS (RETAINED BY DEPARTMENT)	1,300.000 LF	_____	 _____	_____	 _____
0020	202.15 REMOVING EXISTING MANHOLE OR CATCH BASIN	7.000 EA	_____	 _____	_____	 _____
0030	202.19 REMOVING EXISTING BRIDGE	LUMP SUM		 LUMP SUM	_____	 _____
0040	202.19 REMOVING EXISTING BRIDGE ARCH STRUCTURE	LUMP SUM		 LUMP SUM	_____	 _____
0050	202.202 REMOVING PAVEMENT SURFACE	1,250.000 SY	_____	 _____	_____	 _____
0060	203.20 COMMON EXCAVATION	2,550.000 CY	_____	 _____	_____	 _____
0070	203.21 ROCK EXCAVATION	50.000 CY	_____	 _____	_____	 _____
0080	203.2318 DISPOSAL OF SPECIAL WASTE	40.000 T	_____	 _____	_____	 _____
0090	203.25 GRANULAR BORROW	1,200.000 CY	_____	 _____	_____	 _____
0100	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	3,700.000 CY	_____	 _____	_____	 _____
0110	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	360.000 CY	_____	 _____	_____	 _____
0120	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1,950.000 CY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	670.000 T	_____	 _____	_____	 _____
0140	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	71.000 T	_____	 _____	_____	 _____
0150	403.211 HOT MIX ASPHALT (SHIMMING)	35.000 T	_____	 _____	_____	 _____
0160	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	920.000 T	_____	 _____	_____	 _____
0170	409.15 BITUMINOUS TACK COAT - APPLIED	690.000 G	_____	 _____	_____	 _____
0180	461.131 TEMPORARY PAVEMENT	49.000 T	_____	 _____	_____	 _____
0190	501.222 MICROPILES	670.000 LF	_____	 _____	_____	 _____
0200	501.2221 ABANDONED MICROPILES	50.000 LF	_____	 _____	_____	 _____
0210	501.2331 MICROPILE VERIFICATION LOAD TEST	1.000 EA	_____	 _____	_____	 _____
0220	501.25 STEEL CASING 12 INCH GALV	42.000 LF	_____	 _____	_____	 _____
0230	501.25 STEEL CASING 24 INCH GALV	32.000 LF	_____	 _____	_____	 _____
0240	501.804 DRILLING EQUIPMENT MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	501.83 DRILLED SHAFT CONFIRMATORY BORINGS	660.000 LF	_____	 _____	_____	 _____
0260	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	560.000 CY	_____	 _____	_____	 _____
0270	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM		LUMP SUM	_____	 _____
0280	502.23 STRUCTURAL CONCRETE PIERS	16.000 CY	_____	 _____	_____	 _____
0290	502.239 STRUCTURAL CONCRETE PIERS	LUMP SUM		LUMP SUM	_____	 _____
0300	502.24 STRUCTURAL CONCRETE PIERS (PLACED UNDER WATER)	730.000 CY	_____	 _____	_____	 _____
0310	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM		LUMP SUM	_____	 _____
0320	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM		LUMP SUM	_____	 _____
0330	502.341 STRUCTURAL CONCRETE ROADWAY MEDIAN	5.000 CY	_____	 _____	_____	 _____
0340	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM		LUMP SUM	_____	 _____
0350	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE: G	8.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	108,700.000 LB	_____	 _____	_____	 _____
0370	503.13 REINFORCING STEEL, PLACING	108,700.000 LB	_____	 _____	_____	 _____
0380	503.17 MECHANICAL WELDED SPLICE	2,286.000 EA	_____	 _____	_____	 _____
0390	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	510,300.000 LB	_____	 _____	_____	 _____
0400	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	510,300.000 LB	_____	 _____	_____	 _____
0410	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM		LUMP SUM	_____	 _____
0420	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM		LUMP SUM	_____	 _____
0430	505.08 SHEAR CONNECTORS	LUMP SUM		LUMP SUM	_____	 _____
0440	506.9104 THERMAL SPRAY COATING - SHOP APPLIED	LUMP SUM		LUMP SUM	_____	 _____
0450	507.0834 WYOMING STEEL BRIDGE RAILING	LUMP SUM		LUMP SUM	_____	 _____
0460	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM		LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	511.07 COFFERDAM: ABUT NO.1	LUMP SUM	LUMP	SUM	_____	_____
0480	511.07 COFFERDAM: ABUT NO.2	LUMP SUM	LUMP	SUM	_____	_____
0490	511.07 COFFERDAM: EXIST PIER 1 REMOVAL	LUMP SUM	LUMP	SUM	_____	_____
0500	511.07 COFFERDAM: PIER	LUMP SUM	LUMP	SUM	_____	_____
0510	511.07 COFFERDAM: RIPRAP AND BR REMOVAL	LUMP SUM	LUMP	SUM	_____	_____
0520	512.081 FRENCH DRAINS	LUMP SUM	LUMP	SUM	_____	_____
0530	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0540	521.23 EXPANSION DEVICE FINGER JOINT	2.000 EA	_____	_____	_____	_____
0550	523.52 BEARING INSTALLATION	27.000 EA	_____	_____	_____	_____
0560	523.5551 POT OR DISC BEARINGS, FIXED	9.000 EA	_____	_____	_____	_____
0570	523.5552 POT OR DISC BEARINGS, EXPANSION	18.000 EA	_____	_____	_____	_____
0580	524.301 TEMPORARY STRUCTURAL SUPPORT ABUT NO.1	LUMP SUM	LUMP	SUM	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	524.301 TEMPORARY STRUCTURAL SUPPORT ABUT NO.2	LUMP SUM	LUMP	SUM	_____	_____
0600	524.301 TEMPORARY STRUCTURAL SUPPORT CLOSURE WALL	LUMP SUM	LUMP	SUM	_____	_____
0610	524.301 TEMPORARY STRUCTURAL SUPPORT CONSOLIDATED COMMUNICATIONS	LUMP SUM	LUMP	SUM	_____	_____
0620	524.304 TEMPORARY ACCESS CONSTRUCTION	LUMP SUM	LUMP	SUM	_____	_____
0630	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0640	526.304 PORTABLE CONCRETE BARRIER, ANCHORED TYPE 1	LUMP SUM	LUMP	SUM	_____	_____
0650	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA	_____	_____	_____	_____
0660	527.34 WORK ZONE CRASH CUSHIONS	3.000 UN	_____	_____	_____	_____
0670	602.30 FLOWABLE CONCRETE FILL	40.000 CY	_____	_____	_____	_____
0680	603.155 12 INCH REINFORCED CONCRETE PIPE CLASS III	70.000 LF	_____	_____	_____	_____
0690	603.159 12 INCH CULVERT PIPE OPTION III	26.000 LF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0700	603.169 15 INCH CULVERT PIPE OPTION III	44.000 LF	_____	 _____	_____	 _____
0710	603.179 18 INCH CULVERT PIPE OPTION III	64.000 LF	_____	 _____	_____	 _____
0720	603.199 24 INCH CULVERT PIPE OPTION III	52.000 LF	_____	 _____	_____	 _____
0730	604.072 CATCH BASIN TYPE A1-C	3.700 EA	_____	 _____	_____	 _____
0740	604.092 CATCH BASIN TYPE B1-C	2.000 EA	_____	 _____	_____	 _____
0750	604.16 ALTERING CATCH BASIN TO MANHOLES	2.000 EA	_____	 _____	_____	 _____
0760	604.164 REBUILDING CATCH BASIN	2.000 EA	_____	 _____	_____	 _____
0770	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	3.000 EA	_____	 _____	_____	 _____
0780	604.247 CATCH BASIN TYPE F5-C	1.000 EA	_____	 _____	_____	 _____
0790	604.249 CATCH BASIN TYPE F6-C	1.000 EA	_____	 _____	_____	 _____
0800	604.252 CATCH BASIN TYPE A5-C	4.200 EA	_____	 _____	_____	 _____
0810	605.09 6 INCH UNDERDRAIN TYPE B	350.000 LF	_____	 _____	_____	 _____
0820	605.11 12 INCH UNDERDRAIN TYPE C	60.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0830	605.12 15 INCH UNDERDRAIN TYPE C	44.000 LF	_____	_____	_____	_____
0840	605.15 24 INCH UNDERDRAIN TYPE C	48.000 LF	_____	_____	_____	_____
0850	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	79.000 LF	_____	_____	_____	_____
0860	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	25.000 LF	_____	_____	_____	_____
0870	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	3.000 EA	_____	_____	_____	_____
0880	606.1307 BRIDGE TRANSITION (ASYMMETRICAL) - TYPE 1A	2.000 EA	_____	_____	_____	_____
0890	606.1307 BRIDGE TRANSITION (ASYMMETRICAL) - TYPE 1A MODIFIED	2.000 EA	_____	_____	_____	_____
0900	606.259 ANCHORAGE ASSEMBLY	1.000 EA	_____	_____	_____	_____
0910	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	7.000 EA	_____	_____	_____	_____
0920	606.356 UNDERDRAIN DELINEATOR POST	2.000 EA	_____	_____	_____	_____
0930	606.47 SINGLE WOOD POST	1.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0940	607.17 CHAIN LINK FENCE - 6 FOOT	35.000 LF	_____	 _____	_____	 _____
0950	608.26 CURB RAMP DETECTABLE WARNING FIELD	98.000 SF	_____	 _____	_____	 _____
0960	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	4.000 LF	_____	 _____	_____	 _____
0970	609.221 TERMINAL CURB TYPE 1	31.000 LF	_____	 _____	_____	 _____
0980	609.222 TERMINAL CURB TYPE 1 - CIRCULAR	38.000 LF	_____	 _____	_____	 _____
0990	609.31 CURB TYPE 3	330.000 LF	_____	 _____	_____	 _____
1000	609.38 RESET CURB TYPE 1	520.000 LF	_____	 _____	_____	 _____
1010	609.40 RESET CURB TYPE 5	460.000 LF	_____	 _____	_____	 _____
1020	610.08 PLAIN RIPRAP	11.000 CY	_____	 _____	_____	 _____
1030	610.16 HEAVY RIPRAP	260.000 CY	_____	 _____	_____	 _____
1040	610.18 STONE DITCH PROTECTION	5.000 CY	_____	 _____	_____	 _____
1050	613.319 EROSION CONTROL BLANKET	190.000 SY	_____	 _____	_____	 _____
1060	615.07 LOAM	67.000 CY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1070	618.13 SEEDING METHOD NUMBER 1	2.000 UN	_____	_____	_____	_____
1080	618.14 SEEDING METHOD NUMBER 2	11.000 UN	_____	_____	_____	_____
1090	619.12 MULCH	13.000 UN	_____	_____	_____	_____
1100	620.58 EROSION CONTROL GEOTEXTILE	227.000 SY	_____	_____	_____	_____
1110	620.66 DRAINAGE GEOCOMPOSITE	110.000 SY	_____	_____	_____	_____
1120	623.11 REMOVE AND LOAD MONUMENT	LUMP SUM		LUMP SUM	_____	_____
1130	626.11 PRECAST CONCRETE JUNCTION BOX	4.000 EA	_____	_____	_____	_____
1140	626.21 METALLIC CONDUIT	20.000 LF	_____	_____	_____	_____
1150	626.22 NON-METALLIC CONDUIT	1,400.000 LF	_____	_____	_____	_____
1160	626.421 24 INCH DIAMETER FOUNDATION	28.000 LF	_____	_____	_____	_____
1170	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	6,400.000 LF	_____	_____	_____	_____
1180	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	1,900.000 SF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1190	627.77 REMOVING PAVEMENT MARKINGS	1,450.000 SF	_____	 _____	_____	 _____
1200	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	10,000.000 LF	_____	 _____	_____	 _____
1210	629.05 HAND LABOR, STRAIGHT TIME	140.000 HR	_____	 _____	_____	 _____
1220	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1230	631.11 AIR TOOL (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1240	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1250	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1260	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	220.000 HR	_____	 _____	_____	 _____
1270	631.22 FRONT END LOADER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1280	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1290	634.160 HIGHWAY LIGHTING	LUMP SUM		 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1300	634.70 ORNAMENTAL LIGHTING	15.000 EA	_____	 _____	_____	 _____
1310	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
1320	643.71 TRAFFIC SIGNAL MODIFICATION BRIDGE ST/ BENTON AVE/ CLINTON AVE/ BAY ST	LUMP SUM	LUMP	 SUM	_____	 _____
1330	643.71 TRAFFIC SIGNAL MODIFICATION CARTER MEMORIAL DR/ AUGUSTA RD	LUMP SUM	LUMP	 SUM	_____	 _____
1340	643.711 TRAFFIC SIGNAL MODIFICATION (TEMPORARY) BRIDGE ST/ BENTON AVE/ CLINTON AVE/ BAY ST	LUMP SUM	LUMP	 SUM	_____	 _____
1350	643.711 TRAFFIC SIGNAL MODIFICATION (TEMPORARY) SPRING ST/ MAIN ST/ WATER ST/ FRONT ST/ BRIDGE ST	LUMP SUM	LUMP	 SUM	_____	 _____
1360	643.713 TEMPORARY EMERGENCY SYSTEM PREEMPTION MODIFICATION	LUMP SUM	LUMP	 SUM	_____	 _____
1370	645.103 DEMOUNT GUIDE SIGN	15.000 EA	_____	 _____	_____	 _____
1380	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	53.000 EA	_____	 _____	_____	 _____
1390	645.108 DEMOUNT POLE	12.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1400	645.113 REINSTALL GUIDE SIGN	15.000 EA	_____	 _____	_____	 _____
1410	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	41.000 EA	_____	 _____	_____	 _____
1420	645.118 REINSTALL POLE	11.000 EA	_____	 _____	_____	 _____
1430	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	80.000 SF	_____	 _____	_____	 _____
1440	652.312 TYPE III BARRICADE	12.000 EA	_____	 _____	_____	 _____
1450	652.33 DRUM	70.000 EA	_____	 _____	_____	 _____
1460	652.34 CONE	70.000 EA	_____	 _____	_____	 _____
1470	652.35 CONSTRUCTION SIGNS	1,200.000 SF	_____	 _____	_____	 _____
1480	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		 LUMP SUM	_____	 _____
1490	652.38 FLAGGER	500.000 HR	_____	 _____	_____	 _____
1500	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA	_____	 _____	_____	 _____
1510	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1520	660.21 ON-THE-JOB TRAINING (BID)	4,000.000 HR	_____	 _____	_____	 _____
1530	801.03 TEST PITS	10.000 EA	_____	 _____	_____	 _____
1540	822.33 6 INCH CLASS 52 DUCTILE IRON PIPE	30.000 LF	_____	 _____	_____	 _____
1550	822.34 8 INCH CLASS 52 DUCTILE IRON PIPE	100.000 LF	_____	 _____	_____	 _____
1560	822.3407 8 INCH EXPANSION JOINT	2.000 EA	_____	 _____	_____	 _____
1570	822.363 12 INCH CLASS 52 DUCTILE IRON PIPE	300.000 LF	_____	 _____	_____	 _____
1580	822.50 24 INCH CLASS 52 DUCTILE IRON PIPE	8.000 LF	_____	 _____	_____	 _____
1590	823.311 12 INCH GATE VALVE WITH BOX	2.000 EA	_____	 _____	_____	 _____
1600	823.3251 8 INCH GATE VALVE WITH BOX	1.000 EA	_____	 _____	_____	 _____
1610	823.33 6 INCH GATE VALVE WITH BOX	2.000 EA	_____	 _____	_____	 _____
1620	824.30 FIRE HYDRANT	2.000 EA	_____	 _____	_____	 _____
1630	825.321 1 INCH CORPORATION	1.000 EA	_____	 _____	_____	 _____
1640	827.33 TRENCH INSULATION	40.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1650	830.104 WATER MAIN BRIDGE CROSSING	610.000 LF	_____	 _____	_____	 _____
1660	830.163 GAS MAIN BRIDGE CROSSING, OWNER FURNISHED	620.000 LF	_____	 _____	_____	 _____
1670	830.164 HANGER - ROLLER ASSEMBLIES	56.000 EACH	_____	 _____	_____	 _____
1680	845.10 STRUCTURAL STEEL UTILITY SUPPORT CHARTER COMMUNICATIONS	LUMP SUM	LUMP SUM		_____	 _____
1690	845.10 STRUCTURAL STEEL UTILITY SUPPORT CMP	LUMP SUM	LUMP SUM		_____	 _____
1700	845.10 STRUCTURAL STEEL UTILITY SUPPORT CONSOLIDATED COMMUNICATIONS	LUMP SUM	LUMP SUM		_____	 _____
1710	845.102 SINGLE STRUCTURAL STEEL UTILITY SUPPORT	56.000 EACH	_____	 _____	_____	 _____
1720	910.30 SPECIAL WORK WINTER MAINTENANCE & SNOWPLOWING	12.000 EA	_____	 _____	_____	 _____
1730	910.301 SPECIAL WORK CONDUIT - CHARTER COMMUNICATIONS	LUMP SUM	LUMP SUM		_____	 _____
1740	910.301 SPECIAL WORK CONDUIT - CONC DUCT BANK - CMP	LUMP SUM	LUMP SUM		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023138.00

Project(s): 023138.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1750	910.301 SPECIAL WORK CONDUIT - CONDUCT BANK - CONSOLIDATED COMMUNICATIONS	LUMP SUM	LUMP	SUM	_____	_____
1760	910.301 SPECIAL WORK CONDUIT & HANGERS BRIDGE - CHARTER COMMUNICATIONS	LUMP SUM	LUMP	SUM	_____	_____
1770	910.301 SPECIAL WORK CONDUIT & HANGERS BRIDGE - CMP	LUMP SUM	LUMP	SUM	_____	_____
1780	910.301 SPECIAL WORK CONDUIT & HANGERS BRIDGE - CONSOLIDATED COMMUNICATIONS	LUMP SUM	LUMP	SUM	_____	_____
1790	910.301 SPECIAL WORK PEDESTRIAN DETOUR	LUMP SUM	LUMP	SUM	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____