

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023188.00

Project(s): 023188.00, 023535.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.10 REMOVING EXISTING SUPERSTRUCTURE (PROPERTY OF CONTRACTOR)	LUMP SUM				
0020	202.12 REMOVING EXISTING STRUCTURAL CONCRETE	95.000 CY				
0030	202.202 REMOVING PAVEMENT SURFACE	1,030.000 SY				
0040	203.20 COMMON EXCAVATION	580.000 CY				
0050	203.24 COMMON BORROW	230.000 CY				
0060	203.25 GRANULAR BORROW	70.000 CY				
0070	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	200.000 CY				
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	500.000 CY				
0090	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	181.000 T				
0100	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	230.000 T				
0110	409.15 BITUMINOUS TACK COAT - APPLIED	102.000 G				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023188.00

Project(s): 023188.00, 023535.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	108.000 CY	_____	 _____	_____	 _____
0130	502.248 UNDERWATER GROUT BAGS	2.000 CY	_____	 _____	_____	 _____
0140	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP SUM		LUMP SUM	_____	 _____
0150	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM		LUMP SUM	_____	 _____
0160	502.325 STRUCTURAL CONCRETE CULVERT INVERT LINING	LUMP SUM		LUMP SUM	_____	 _____
0170	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM		LUMP SUM	_____	 _____
0180	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	43,010.000 LB	_____	 _____	_____	 _____
0190	503.13 REINFORCING STEEL, PLACING	43,010.000 LB	_____	 _____	_____	 _____
0200	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM		LUMP SUM	_____	 _____
0210	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA	_____	 _____	_____	 _____
0220	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM		LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023188.00

Project(s): 023188.00, 023535.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	511.07 COFFERDAM: DOWNSTREAM BARREL 1	LUMP SUM	LUMP	SUM	_____	_____
0240	511.07 COFFERDAM: DOWNSTREAM BARREL 2	LUMP SUM	LUMP	SUM	_____	_____
0250	511.07 COFFERDAM: UPSTREAM BARREL 1	LUMP SUM	LUMP	SUM	_____	_____
0260	511.07 COFFERDAM: UPSTREAM BARREL 2	LUMP SUM	LUMP	SUM	_____	_____
0270	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0280	518.60 REPAIR OF VERTICAL SURFACES < 8 IN.	100.000 SF	_____	_____	_____	_____
0290	518.70 REPAIR OF OVERHEAD SURFACES < 8 IN.	50.000 SF	_____	_____	_____	_____
0300	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP SUM	LUMP	SUM	_____	_____
0310	524.301 TEMPORARY STRUCTURAL SUPPORT STAGED APPROACHES	LUMP SUM	LUMP	SUM	_____	_____
0320	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0330	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023188.00

Project(s): 023188.00, 023535.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	535.60 PRESTRESSED STRUCTURAL CONCRETE SLAB	LUMP SUM				
0350	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	470.000 LF				
0360	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	1.000 EA				
0370	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	1.000 EA				
0380	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0390	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.000 EA				
0400	610.08 PLAIN RIPRAP	175.000 CY				
0410	613.319 EROSION CONTROL BLANKET	373.000 SY				
0420	615.07 LOAM	58.000 CY				
0430	618.14 SEEDING METHOD NUMBER 2	10.000 UN				
0440	619.12 MULCH	10.000 UN				
0450	619.14 EROSION CONTROL MIX	133.000 CY				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023188.00

Project(s): 023188.00, 023535.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	620.58 EROSION CONTROL GEOTEXTILE	311.000 SY	_____	 _____	_____	 _____
0470	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,700.000 LF	_____	 _____	_____	 _____
0480	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	4,000.000 LF	_____	 _____	_____	 _____
0490	629.05 HAND LABOR, STRAIGHT TIME	96.000 HR	_____	 _____	_____	 _____
0500	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	60.000 HR	_____	 _____	_____	 _____
0510	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	60.000 HR	_____	 _____	_____	 _____
0520	639.19 FIELD OFFICE TYPE B	2.000 EA	_____	 _____	_____	 _____
0530	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM		 LUMP SUM	_____	 _____
0540	652.311 TYPE II BARRICADE	4.000 EA	_____	 _____	_____	 _____
0550	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0560	652.33 DRUM	100.000 EA	_____	 _____	_____	 _____
0570	652.34 CONE	250.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023188.00

Project(s): 023188.00, 023535.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	652.35 CONSTRUCTION SIGNS	800.000 SF	_____	_____	_____	_____
0590	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM	LUMP SUM	_____	_____
0600	652.38 FLAGGER	500.000 HR	_____	_____	_____	_____
0610	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM	LUMP SUM	_____	_____
0620	659.10 MOBILIZATION	LUMP SUM	LUMP SUM	LUMP SUM	_____	_____
0630	910.301 SPECIAL WORK	LUMP SUM	LUMP SUM	LUMP SUM	_____	_____
<b>Section: 1</b>			<b>Total:</b>		_____	_____
			<b>Total Bid:</b>		_____	_____