

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023234.01

Project(s): 023234.01

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.13 REMOVING EXISTING RAILINGS (RETAINED BY DEPARTMENT)	706.000 LF	_____	 _____	_____	 _____
0020	202.15 REMOVING EXISTING MANHOLE OR CATCH BASIN	2.000 EA	_____	 _____	_____	 _____
0030	202.19 REMOVING EXISTING BRIDGE	LUMP SUM		 LUMP SUM	_____	 _____
0040	202.202 REMOVING PAVEMENT SURFACE	1,450.000 SY	_____	 _____	_____	 _____
0050	202.61 REMOVE STORM DRAIN OR SEWER PIPE, ALL DEPTHS AND SIZES	LUMP SUM		 LUMP SUM	_____	 _____
0060	203.20 COMMON EXCAVATION	2,200.000 CY	_____	 _____	_____	 _____
0070	203.2312 HEALTH AND SAFETY PLAN	LUMP SUM		 LUMP SUM	_____	 _____
0080	203.2333 DISPOSAL TREATMENT OF SPECIAL EXCAVATION	40.000 T	_____	 _____	_____	 _____
0090	203.25 GRANULAR BORROW	870.000 CY	_____	 _____	_____	 _____
0100	203.33 SPECIAL FILL	12.000 CY	_____	 _____	_____	 _____
0110	203.35 CRUSHED STONE FILL	262.000 CY	_____	 _____	_____	 _____
0120	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	2,340.000 CY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023234.01

Project(s): 023234.01

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1,150.000 CY	_____	 _____	_____	 _____
0140	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	536.000 T	_____	 _____	_____	 _____
0150	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	61.000 T	_____	 _____	_____	 _____
0160	403.211 HOT MIX ASPHALT (SHIMMING)	40.000 T	_____	 _____	_____	 _____
0170	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	370.000 T	_____	 _____	_____	 _____
0180	409.15 BITUMINOUS TACK COAT - APPLIED	346.000 G	_____	 _____	_____	 _____
0190	461.131 TEMPORARY PAVEMENT	220.000 T	_____	 _____	_____	 _____
0200	501.237 NOISE ATTENUATION AND UNDERWATER NOISE MONITORING	LUMP SUM		 LUMP SUM	_____	 _____
0210	501.239 DYNAMIC LOADING TESTS - PROVIDING FOR	2.000 EA	_____	 _____	_____	 _____
0220	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	979.000 LF	_____	 _____	_____	 _____
0230	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	979.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023234.01

Project(s): 023234.01

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	501.90 PILE TIPS	28.000 EA	_____	 _____	_____	 _____
0250	501.91 PILE SPLICES	28.000 EA	_____	 _____	_____	 _____
0260	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
0270	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM		LUMP SUM	_____	 _____
0280	502.239 STRUCTURAL CONCRETE PIERS	LUMP SUM		LUMP SUM	_____	 _____
0290	502.24 STRUCTURAL CONCRETE PIERS (PLACED UNDER WATER)	770.000 CY	_____	 _____	_____	 _____
0300	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM		LUMP SUM	_____	 _____
0310	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM		LUMP SUM	_____	 _____
0320	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM		LUMP SUM	_____	 _____
0330	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE: E	4.000 EA	_____	 _____	_____	 _____
0340	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	60,000.000 LB	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023234.01

Project(s): 023234.01

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	503.13 REINFORCING STEEL, PLACING	60,000.000 LB	_____	 _____	_____	 _____
0360	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	44,000.000 LB	_____	 _____	_____	 _____
0370	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	44,000.000 LB	_____	 _____	_____	 _____
0380	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM	LUMP	 SUM	_____	 _____
0390	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM	LUMP	 SUM	_____	 _____
0400	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	 SUM	_____	 _____
0410	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	 SUM	_____	 _____
0420	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP SUM	LUMP	 SUM	_____	 _____
0430	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	 SUM	_____	 _____
0440	510.12 SPECIAL DETOUR __FOOT ROADWAY WIDTH, VEHICULAR AND PEDESTRIAN TRAFFIC SEPARATED 12 FT	LUMP SUM	LUMP	 SUM	_____	 _____
0450	511.07 COFFERDAM: ABUT NO.1	LUMP SUM	LUMP	 SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023234.01

Project(s): 023234.01

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	511.07 COFFERDAM: ABUT NO.2	LUMP SUM	LUMP	SUM	_____	_____
0470	511.07 COFFERDAM: PIER NO.1	LUMP SUM	LUMP	SUM	_____	_____
0480	511.07 COFFERDAM: PIER NO.2	LUMP SUM	LUMP	SUM	_____	_____
0490	512.081 FRENCH DRAINS	LUMP SUM	LUMP	SUM	_____	_____
0500	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0510	520.22 EXPANSION DEVICE - COMPRESSION SEAL	1.000 EA	_____	_____	_____	_____
0520	521.23 EXPANSION DEVICE FINGER JOINT	1.000 EA	_____	_____	_____	_____
0530	523.52 BEARING INSTALLATION	24.000 EA	_____	_____	_____	_____
0540	523.5551 POT OR DISC BEARINGS, FIXED	6.000 EA	_____	_____	_____	_____
0550	523.5552 POT OR DISC BEARINGS, EXPANSION	18.000 EA	_____	_____	_____	_____
0560	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0570	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023234.01

Project(s): 023234.01

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	139,300.000 LF	_____	 _____	_____	 _____
0590	530.31 GFRP, REINFORCEMENT BARS, PLACING	139,300.000 LF	_____	 _____	_____	 _____
0600	603.179 18 INCH CULVERT PIPE OPTION III	160.000 LF	_____	 _____	_____	 _____
0610	604.072 CATCH BASIN TYPE A1-C	1.000 EA	_____	 _____	_____	 _____
0620	604.092 CATCH BASIN TYPE B1-C	1.000 EA	_____	 _____	_____	 _____
0630	604.16 ALTERING CATCH BASIN TO MANHOLES	1.000 EA	_____	 _____	_____	 _____
0640	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	5.000 EA	_____	 _____	_____	 _____
0650	604.183 MODIFY EXISTING MANHOLE OR CATCH BASIN	1.000 EA	_____	 _____	_____	 _____
0660	605.09 6 INCH UNDERDRAIN TYPE B	250.000 LF	_____	 _____	_____	 _____
0670	605.10 6 INCH UNDERDRAIN OUTLET	50.000 LF	_____	 _____	_____	 _____
0680	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	260.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023234.01

Project(s): 023234.01

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0690	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	25.000 LF	_____	 _____	_____	 _____
0700	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	3.000 EA	_____	 _____	_____	 _____
0710	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	 _____	_____	 _____
0720	606.259 ANCHORAGE ASSEMBLY	1.000 EA	_____	 _____	_____	 _____
0730	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	 _____	_____	 _____
0740	607.24 REMOVE AND RESET FENCE	25.000 LF	_____	 _____	_____	 _____
0750	608.26 CURB RAMP DETECTABLE WARNING FIELD	45.000 SF	_____	 _____	_____	 _____
0760	609.11 VERTICAL CURB TYPE 1	100.000 LF	_____	 _____	_____	 _____
0770	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	11.000 LF	_____	 _____	_____	 _____
0780	609.221 TERMINAL CURB TYPE 1	51.000 LF	_____	 _____	_____	 _____
0790	609.222 TERMINAL CURB TYPE 1 - CIRCULAR	50.000 LF	_____	 _____	_____	 _____
0800	609.31 CURB TYPE 3	100.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023234.01

Project(s): 023234.01

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0810	609.38 RESET CURB TYPE 1	200.000 LF	_____	 _____	_____	 _____
0820	610.08 PLAIN RIPRAP	1,348.000 CY	_____	 _____	_____	 _____
0830	610.18 STONE DITCH PROTECTION	17.000 CY	_____	 _____	_____	 _____
0840	610.212 STREAMBED ROCK FEATURES	6.000 CY	_____	 _____	_____	 _____
0850	613.319 EROSION CONTROL BLANKET	64.000 SY	_____	 _____	_____	 _____
0860	615.07 LOAM	110.000 CY	_____	 _____	_____	 _____
0870	618.13 SEEDING METHOD NUMBER 1	6.000 UN	_____	 _____	_____	 _____
0880	618.14 SEEDING METHOD NUMBER 2	7.000 UN	_____	 _____	_____	 _____
0890	619.12 MULCH	12.000 UN	_____	 _____	_____	 _____
0900	620.58 EROSION CONTROL GEOTEXTILE	1,470.000 SY	_____	 _____	_____	 _____
0910	620.60 SEPARATION GEOTEXTILE	400.000 SY	_____	 _____	_____	 _____
0920	623.10 REMOVE AND RESET MEMORIAL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0930	626.21 METALLIC CONDUIT	20.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023234.01

Project(s): 023234.01

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0940	626.22 NON-METALLIC CONDUIT	420.000 LF	_____	 _____	_____	 _____
0950	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	3,050.000 LF	_____	 _____	_____	 _____
0960	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	200.000 SF	_____	 _____	_____	 _____
0970	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,600.000 LF	_____	 _____	_____	 _____
0980	629.05 HAND LABOR, STRAIGHT TIME	50.000 HR	_____	 _____	_____	 _____
0990	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1000	631.11 AIR TOOL (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1010	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1020	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1030	634.160 HIGHWAY LIGHTING	LUMP SUM		 LUMP SUM	_____	 _____
1040	634.210 CONVENTIONAL LIGHT STANDARD	4.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023234.01

Project(s): 023234.01

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1050	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
1060	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM		_____	 _____
1070	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	17.000 SF	_____	 _____	_____	 _____
1080	652.312 TYPE III BARRICADE	6.000 EA	_____	 _____	_____	 _____
1090	652.33 DRUM	40.000 EA	_____	 _____	_____	 _____
1100	652.34 CONE	40.000 EA	_____	 _____	_____	 _____
1110	652.35 CONSTRUCTION SIGNS	340.000 SF	_____	 _____	_____	 _____
1120	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
1130	652.38 FLAGGER	450.000 HR	_____	 _____	_____	 _____
1140	655.201 ELECTRICAL WORK	LUMP SUM	LUMP SUM		_____	 _____
1150	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
1160	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023234.01

Project(s): 023234.01

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1170	801.03 TEST PITS	4.000 EA	_____	 _____	_____	 _____
1180	801.071 TEMPORARY SEWER BY-PASS	LUMP SUM	LUMP SUM		_____	 _____
1190	812.163 MODIFY SEWER MH, ADJUST FRAME & COVER	3.000 EA	_____	 _____	_____	 _____
1200	822.321 4 INCH CLASS 52 DUCTILE IRON PIPE	80.000 LF	_____	 _____	_____	 _____
1210	822.321 4 INCH CLASS 52 DUCTILE IRON PIPE ON BRIDGE, INSULATED	200.000 LF	_____	 _____	_____	 _____
1220	822.33 6 INCH CLASS 52 DUCTILE IRON PIPE	50.000 LF	_____	 _____	_____	 _____
1230	822.33 6 INCH CLASS 52 DUCTILE IRON PIPE ON BRIDGE, INSULATED	230.000 LF	_____	 _____	_____	 _____
1240	822.38 SEWER FORCE MAIN RELOCATION STA 21+00	1.000 EA	_____	 _____	_____	 _____
1250	823.3411 AIR RELEASE VALVE, MANUAL SYSTEM	LUMP SUM	LUMP SUM		_____	 _____
1260	827.302 UNSUITABLE SOIL EXCAVATION - BELOW GRADE	50.000 CY	_____	 _____	_____	 _____
1270	827.331 TRENCH INSULATION 2" RIGID	300.000 SY	_____	 _____	_____	 _____
1280	832.07 OWNERS TESTING ALLOWANCE	LUMP SUM	LUMP SUM		_____	 _____

8/18/2020

Maine Department of Transportation

Proposal Schedule of Items

Page 12 of 12

Proposal ID: 023234.01

Project(s): 023234.01

Section: 1

Total:

_____!_____

Total Bid:

_____!_____