

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023292.00

Project(s): 023292.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description   | Approximate Quantity and Units | Unit Price |           | Bid Amount |           |
|----------------------|---|--------------------------------|------------|-----------|------------|-----------|
|                      |   |                                | Dollars    | Cents     | Dollars    | Cents     |
| 0010                 | 202.2023<br>REMOVING PAVEMENT SURFACE -<br>MEDIUM CUT DRUM            | 98,200.000<br>SY               | _____      | <br>_____ | _____      | <br>_____ |
| 0020                 | 202.203<br>PAVEMENT BUTT JOINTS                                       | 40.000<br>SY                   | _____      | <br>_____ | _____      | <br>_____ |
| 0030                 | 403.209<br>HOT MIX ASPHALT 9.5 MM<br>(SIDEWALKS, DRIVES, INCIDENTALS) | 20.000<br>T                    | _____      | <br>_____ | _____      | <br>_____ |
| 0040                 | 403.211<br>HOT MIX ASPHALT (SHIMMING)                                 | 500.000<br>T                   | _____      | <br>_____ | _____      | <br>_____ |
| 0050                 | 409.15<br>BITUMINOUS TACK COAT - APPLIED                              | 550.000<br>G                   | _____      | <br>_____ | _____      | <br>_____ |
| 0060                 | 410.151<br>EMULSIFIED ASPHALT SEALCOAT,<br>APPLIED                    | 126,600.000<br>SY              | _____      | <br>_____ | _____      | <br>_____ |
| 0070                 | 411.10<br>UNTREATED AGGREGATE SURFACE<br>COURSE (TRUCK MEASURE)       | 10.000<br>CY                   | _____      | <br>_____ | _____      | <br>_____ |
| 0080                 | 424.323<br>ASPHALT RUBBER CRACK SEALER,<br>APPLIED                    | 46,700.000<br>LB               | _____      | <br>_____ | _____      | <br>_____ |
| 0090                 | 462.301<br>POLYMER MODIFIED ULTRATHIN<br>BONDED WEARING COURSE        | 194,300.000<br>SY              | _____      | <br>_____ | _____      | <br>_____ |
| 0100                 | 606.178<br>GUARDRAIL BEAM   | 62.500<br>LF                   | _____      | <br>_____ | _____      | <br>_____ |
| 0110                 | 606.231<br>GUARDRAIL TYPE 3C - 15 FOOT<br>RADIUS AND LESS             | 12.500<br>LF                   | _____      | <br>_____ | _____      | <br>_____ |

## Maine Department of Transportation

## Proposal Schedule of Items

Proposal ID: 023292.00

Project(s): 023292.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description   | Approximate Quantity and Units | Unit Price |           | Bid Amount |           |
|----------------------|---|--------------------------------|------------|-----------|------------|-----------|
|                      |   |                                | Dollars    | Cents     | Dollars    | Cents     |
| 0120                 | 606.232<br>GUARDRAIL TYPE 3C - OVER 15<br>FOOT RADIUS                           | 12.500<br>LF                   | _____      | <br>_____ | _____      | <br>_____ |
| 0130                 | 606.265<br>TERMINAL END - SINGLE RAIL -<br>GALVANIZED STEEL                     | 1.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0140                 | 606.353<br>REFLECTORIZED FLEXIBLE<br>GUARDRAIL MARKER                           | 2.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0150                 | 606.367<br>REPLACE UNUSABLE EXISTING<br>GUARDRAIL POSTS                         | 20.000<br>EA                   | _____      | <br>_____ | _____      | <br>_____ |
| 0160                 | 606.79<br>GUARDRAIL 350 FLARED TERMINAL   | 1.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0170                 | 613.319<br>EROSION CONTROL BLANKET  | 900.000<br>SY                  | _____      | <br>_____ | _____      | <br>_____ |
| 0180                 | 618.14<br>SEEDING METHOD NUMBER 2   | 70.000<br>UN                   | _____      | <br>_____ | _____      | <br>_____ |
| 0190                 | 619.12<br>MULCH   | 70.000<br>UN                   | _____      | <br>_____ | _____      | <br>_____ |
| 0200                 | 627.75<br>WHITE OR YELLOW PAVEMENT &<br>CURB MARKING                            | 140.000<br>SF                  | _____      | <br>_____ | _____      | <br>_____ |
| 0210                 | 627.77<br>REMOVING PAVEMENT MARKINGS  | 35,000.000<br>SF               | _____      | <br>_____ | _____      | <br>_____ |
| 0220                 | 627.78<br>TEMPORARY 4 INCH PAINTED<br>PAVEMENT MARKING LINE, WHITE<br>OR YELLOW | 453,800.000<br>LF              | _____      | <br>_____ | _____      | <br>_____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023292.00

Project(s): 023292.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description   | Approximate Quantity and Units | Unit Price |              | Bid Amount |           |
|----------------------|---|--------------------------------|------------|--------------|------------|-----------|
|                      |   |                                | Dollars    | Cents        | Dollars    | Cents     |
| 0230                 | 629.05<br>HAND LABOR, STRAIGHT TIME                             | 40.000<br>HR                   | _____      | <br>_____    | _____      | <br>_____ |
| 0240                 | 631.12<br>ALL PURPOSE EXCAVATOR<br>(INCLUDING OPERATOR)         | 80.000<br>HR                   | _____      | <br>_____    | _____      | <br>_____ |
| 0250                 | 631.172<br>TRUCK - LARGE (INCLUDING<br>OPERATOR)                | 160.000<br>HR                  | _____      | <br>_____    | _____      | <br>_____ |
| 0260                 | 639.19<br>FIELD OFFICE TYPE B                                   | 1.000<br>EA                    | _____      | <br>_____    | _____      | <br>_____ |
| 0270                 | 652.33<br>DRUM  | 10.000<br>EA                   | _____      | <br>_____    | _____      | <br>_____ |
| 0280                 | 652.34<br>CONE  | 200.000<br>EA                  | _____      | <br>_____    | _____      | <br>_____ |
| 0290                 | 652.35<br>CONSTRUCTION SIGNS                                    | 2,800.000<br>SF                | _____      | <br>_____    | _____      | <br>_____ |
| 0300                 | 652.36<br>MAINTENANCE OF TRAFFIC<br>CONTROL DEVICES             | 60.000<br>CD                   | _____      | <br>_____    | _____      | <br>_____ |
| 0310                 | 652.38<br>FLAGGER   | 1,700.000<br>HR                | _____      | <br>_____    | _____      | <br>_____ |
| 0320                 | 656.75<br>TEMPORARY SOIL EROSION AND<br>WATER POLLUTION CONTROL | LUMP SUM                       | _____      | <br>LUMP SUM | _____      | <br>_____ |
| 0330                 | 659.10<br>MOBILIZATION  | LUMP SUM                       | _____      | <br>LUMP SUM | _____      | <br>_____ |
| Section: 1           |   |                                | Total:     | _____        | _____      | <br>_____ |
|                      |   |                                | Total Bid: | _____        | _____      | <br>_____ |