

7/12/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 3

Proposal ID: 023486.00

Project(s): 023486.00

SECTION: 1

Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM		LUMP SUM		
0020	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	2,550.000 LB				
0030	503.13 REINFORCING STEEL, PLACING	2,550.000 LB				
0040	504.70 STRUCTURAL STEEL FABRICATED AND DELIVERED	LUMP SUM		LUMP SUM		
0050	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM		LUMP SUM		
0060	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM		LUMP SUM		
0070	504.7111 HEAT STRAIGHTENING	4.000 EA				
0080	504.7211 FLOOR BEAM REPAIR	1.000 EA				
0090	504.723 FLOORBEAM STRENGTHENING	14.000 EA				
0100	504.791 GIRDER STRENGTHENING	16.000 EA				
0110	504.81 REMOVAL OF RIVETS AND REPLACEMENT WITH HIGH- STRENGTH BOLTS	55.000 EA				
0120	504.8110 STRUCTURAL STEEL REPAIR	1.000 EA				

7/12/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 3

Proposal ID: 023486.00

Project(s): 023486.00

SECTION: 1

Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	158.000 SY	_____	 _____	_____	 _____
0140	518.211 REHABILITATION OF STRUCTURAL CONCRETE SUBSTRUCTURE	20.000 CY	_____	 _____	_____	 _____
0150	518.60 REPAIR OF VERTICAL SURFACES < 8 IN.	850.000 SF	_____	 _____	_____	 _____
0160	518.80 CRACK REPAIR	22.000 LF	_____	 _____	_____	 _____
0170	523.26 EXPANSION BEARING - MODIFICATION (FABRIC PAD W/ PTFE SLIDING SURFACE)	10.000 EA	_____	 _____	_____	 _____
0180	523.301 REFURBISH & RESET FIXED BEARING	14.000 EA	_____	 _____	_____	 _____
0190	523.311 REFURBISH & RESET EXPANSION BEARING	10.000 EA	_____	 _____	_____	 _____
0200	523.52 BEARING INSTALLATION	10.000 EA	_____	 _____	_____	 _____
0210	524.30 TEMPORARY STRUCTURAL SUPPORT	6.000 EA	_____	 _____	_____	 _____
0220	525.26 REPOINTING GRANITE MASONRY	1,140.000 SF	_____	 _____	_____	 _____
0230	534.30 PRECAST STRUCTURAL CONCRETE	LUMP SUM	LUMP SUM		_____	 _____

7/12/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 3

Proposal ID: 023486.00

Project(s): 023486.00

SECTION: 1

Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	610.08 PLAIN RIPRAP	40.000 CY	_____	 _____	_____	 _____
0250	620.58 EROSION CONTROL GEOTEXTILE	70.000 SY	_____	 _____	_____	 _____
0260	648.511 REMOVE AND RELAY EXISTING TRACK	1,110.000 TF	_____	 _____	_____	 _____
0270	652.38 FLAGGER	350.000 HR	_____	 _____	_____	 _____
0280	652.39 WORK ZONE TRAFFIC CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0290	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0300	659.10 MOBILIZATION	LUMP SUM	_____	 LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____