

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023639.00

Project(s): 023639.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.10 REMOVING EXISTING SUPERSTRUCTURE (PROPERTY OF CONTRACTOR)	LUMP SUM				
0020	202.12 REMOVING EXISTING STRUCTURAL CONCRETE	8.000 CY				
0030	202.13 REMOVING EXISTING RAILINGS (RETAINED BY DEPARTMENT)	88.000 LF				
0040	202.202 REMOVING PAVEMENT SURFACE	900.000 SY				
0050	203.20 COMMON EXCAVATION	430.000 CY				
0060	203.25 GRANULAR BORROW	53.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	310.000 CY				
0080	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	139.000 T				
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	22.000 T				
0100	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	159.000 T				
0110	409.15 BITUMINOUS TACK COAT - APPLIED	88.000 G				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023639.00

Project(s): 023639.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	8.000 CY	_____	 _____	_____	 _____
0130	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM	LUMP SUM		_____	 _____
0140	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP SUM		_____	 _____
0150	503.17 MECHANICAL WELDED SPLICE	194.000 EA	_____	 _____	_____	 _____
0160	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	28,100.000 LB	_____	 _____	_____	 _____
0170	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	28,100.000 LB	_____	 _____	_____	 _____
0180	504.514 BEARING STIFFENER	2.000 EA	_____	 _____	_____	 _____
0190	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP SUM		_____	 _____
0200	507.08161 STEEL APPROACH RAILING, 4 BAR	2.000 EA	_____	 _____	_____	 _____
0210	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP SUM		_____	 _____
0220	507.0822 STEEL APPROACH RAILING, 3-BAR	2.000 EA	_____	 _____	_____	 _____
0230	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP SUM	LUMP SUM		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023639.00

Project(s): 023639.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0250	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0260	518.60 REPAIR OF VERTICAL SURFACES < 8 IN.	40.000 SF	_____	_____	_____	_____
0270	523.52 BEARING INSTALLATION	8.000 EA	_____	_____	_____	_____
0280	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	8.000 EA	_____	_____	_____	_____
0290	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP SUM	LUMP	SUM	_____	_____
0300	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0310	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN	_____	_____	_____	_____
0320	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	125.000 LF	_____	_____	_____	_____
0330	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	25.000 LF	_____	_____	_____	_____
0340	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	25.000 LF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023639.00

Project(s): 023639.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	 _____	_____	 _____
0360	606.259 ANCHORAGE ASSEMBLY	3.000 EA	_____	 _____	_____	 _____
0370	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	3.000 EA	_____	 _____	_____	 _____
0380	608.26 CURB RAMP DETECTABLE WARNING FIELD	26.000 SF	_____	 _____	_____	 _____
0390	609.13 VERTICAL BRIDGE CURB TYPE 1	50.000 LF	_____	 _____	_____	 _____
0400	609.222 TERMINAL CURB TYPE 1 - CIRCULAR	35.000 LF	_____	 _____	_____	 _____
0410	609.38 RESET CURB TYPE 1	140.000 LF	_____	 _____	_____	 _____
0420	610.08 PLAIN RIPRAP	110.000 CY	_____	 _____	_____	 _____
0430	613.319 EROSION CONTROL BLANKET	32.000 SY	_____	 _____	_____	 _____
0440	615.07 LOAM	8.000 CY	_____	 _____	_____	 _____
0450	618.14 SEEDING METHOD NUMBER 2	2.000 UN	_____	 _____	_____	 _____
0460	619.12 MULCH	2.000 UN	_____	 _____	_____	 _____
0470	619.13 BARK MULCH	2.000 CY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023639.00

Project(s): 023639.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0480	619.14 EROSION CONTROL MIX	16.000 CY	_____	 _____	_____	 _____
0490	620.58 EROSION CONTROL GEOTEXTILE	180.000 SY	_____	 _____	_____	 _____
0500	627.51 6" TEMPORARY PAVEMENT TAPE, YELLOW OR WHITE	1,950.000 LF	_____	 _____	_____	 _____
0510	627.57 12" REMOVABLE BLACK LINE MASKING TAPE	1,300.000 LF	_____	 _____	_____	 _____
0520	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2,400.000 LF	_____	 _____	_____	 _____
0530	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	350.000 SF	_____	 _____	_____	 _____
0540	627.77 REMOVING PAVEMENT MARKINGS	710.000 SF	_____	 _____	_____	 _____
0550	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,800.000 LF	_____	 _____	_____	 _____
0560	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0570	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0580	631.11 AIR TOOL (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023639.00

Project(s): 023639.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0600	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0610	631.21 ROAD BROOM (INCLUDING OPERATORS AND HAULER)	10.000 HR	_____	 _____	_____	 _____
0620	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0630	652.312 TYPE III BARRICADE	8.000 EA	_____	 _____	_____	 _____
0640	652.33 DRUM	45.000 EA	_____	 _____	_____	 _____
0650	652.34 CONE	45.000 EA	_____	 _____	_____	 _____
0660	652.35 CONSTRUCTION SIGNS	510.000 SF	_____	 _____	_____	 _____
0670	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		 LUMP SUM	_____	 _____
0680	652.38 FLAGGER	350.000 HR	_____	 _____	_____	 _____
0690	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	 _____	_____	 _____
0700	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____

