

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023657.00

Project(s): 023657.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0020	202.202 REMOVING PAVEMENT SURFACE	265.000 SY				
0030	203.20 COMMON EXCAVATION	5,250.000 CY				
0040	203.25 GRANULAR BORROW	1,890.000 CY				
0050	203.33 SPECIAL FILL	50.000 CY				
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	580.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2,650.000 CY				
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	250.000 T				
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	400.000 T				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	100.000 G				
0110	501.502 ROCK SOCKETED H-PILES	245.000 LF				
0120	501.52 STEEL H-BEAM PILES 102 LBS/FT, DELIVERED	245.000 LF				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023657.00

Project(s): 023657.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	501.804 DRILLING EQUIPMENT MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
0140	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP	SUM	_____	_____
0150	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP SUM	LUMP	SUM	_____	_____
0160	502.291 SAW CUT GROOVING	LUMP SUM	LUMP	SUM	_____	_____
0170	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP	SUM	_____	_____
0180	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP	SUM	_____	_____
0190	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	21,100.000 LB	_____	_____	_____	_____
0200	503.13 REINFORCING STEEL, PLACING	21,100.000 LB	_____	_____	_____	_____
0210	503.17 MECHANICAL WELDED SPLICE	382.000 EA	_____	_____	_____	_____
0220	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	33,600.000 LB	_____	_____	_____	_____
0230	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	33,600.000 LB	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023657.00

Project(s): 023657.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	SUM	_____	_____
0250	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA	_____	_____	_____	_____
0260	511.07 COFFERDAM: ALL COFFERDAMS	LUMP SUM	LUMP	SUM	_____	_____
0270	513.12 SLOPE PROTECTION - WIRE MESH	668.000 SY	_____	_____	_____	_____
0280	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0290	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0300	526.305 PORTABLE CONCRETE BARRIER, BRACED TYPE 1	LUMP SUM	LUMP	SUM	_____	_____
0310	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN	_____	_____	_____	_____
0320	535.622 PRESTRESSED STRUCTURAL CONCRETE NEXT BEAM	LUMP SUM	LUMP	SUM	_____	_____
0330	603.169 15 INCH CULVERT PIPE OPTION III	90.000 LF	_____	_____	_____	_____
0340	604.092 CATCH BASIN TYPE B1-C	1.000 EA	_____	_____	_____	_____
0350	604.246 CATCH BASIN TYPE F5	1.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023657.00

Project(s): 023657.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	605.09 6 INCH UNDERDRAIN TYPE B	280.000 LF	_____	 _____	_____	 _____
0370	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	1,000.000 LF	_____	 _____	_____	 _____
0380	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	25.000 LF	_____	 _____	_____	 _____
0390	606.1308 BURIED-IN-SLOPE GUARDRAIL END, MID-WAY SPLICE	2.000 EA	_____	 _____	_____	 _____
0400	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	 _____	_____	 _____
0410	606.259 ANCHORAGE ASSEMBLY	1.000 EA	_____	 _____	_____	 _____
0420	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	5.000 EA	_____	 _____	_____	 _____
0430	610.08 PLAIN RIPRAP	2,100.000 CY	_____	 _____	_____	 _____
0440	610.18 STONE DITCH PROTECTION	24.000 CY	_____	 _____	_____	 _____
0450	610.213 VOID FILLED RIPRAP	430.000 CY	_____	 _____	_____	 _____
0460	613.319 EROSION CONTROL BLANKET	1,745.000 SY	_____	 _____	_____	 _____
0470	615.07 LOAM	150.000 CY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023657.00

Project(s): 023657.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0480	618.14 SEEDING METHOD NUMBER 2	27.000 UN	_____	_____	_____	_____
0490	619.12 MULCH	27.000 UN	_____	_____	_____	_____
0500	619.14 EROSION CONTROL MIX	300.000 CY	_____	_____	_____	_____
0510	620.58 EROSION CONTROL GEOTEXTILE	3,600.000 SY	_____	_____	_____	_____
0520	620.66 DRAINAGE GEOCOMPOSITE	120.000 SY	_____	_____	_____	_____
0530	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2,650.000 LF	_____	_____	_____	_____
0540	627.77 REMOVING PAVEMENT MARKINGS	50.000 SF	_____	_____	_____	_____
0550	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	2,000.000 LF	_____	_____	_____	_____
0560	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	_____	_____	_____
0570	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR	_____	_____	_____	_____
0580	631.14 GRADER (INCLUDING OPERATOR)	40.000 HR	_____	_____	_____	_____
0590	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	40.000 HR	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023657.00

Project(s): 023657.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0600	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0610	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0620	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM		_____	 _____
0630	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0640	652.33 DRUM	50.000 EA	_____	 _____	_____	 _____
0650	652.34 CONE	50.000 EA	_____	 _____	_____	 _____
0660	652.35 CONSTRUCTION SIGNS	175.000 SF	_____	 _____	_____	 _____
0670	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
0680	652.38 FLAGGER	450.000 HR	_____	 _____	_____	 _____
0690	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	3.000 EA	_____	 _____	_____	 _____
0700	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0710	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023657.00

Project(s): 023657.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0720	675.10 SOIL NAILS	2,660.000 LF	_____	 _____	_____	 _____
0730	675.11 VERIFICATION TEST - SOIL NAILS	4.000 EA	_____	 _____	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____