

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023685.00

Project(s): 023685.00, 024467.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	14,200.000 SY	_____	 _____	_____	 _____
0020	202.2023 REMOVING PAVEMENT SURFACE - MEDIUM CUT DRUM	110,400.000 SY	_____	 _____	_____	 _____
0030	202.203 PAVEMENT BUTT JOINTS	490.000 SY	_____	 _____	_____	 _____
0040	307.331 FULL DEPTH RECYCLED PAVEMENT (UNTREATED)	80,350.000 SY	_____	 _____	_____	 _____
0050	311.35 COLD IN-PLACE RECYCLED ASPHALT PAVEMENT (TRAVELING PUGMILL) 5 INCH	205,430.000 SY	_____	 _____	_____	 _____
0060	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	200.000 T	_____	 _____	_____	 _____
0070	403.2101 9.5 MM POLYMER MODIFIED HMA	800.000 T	_____	 _____	_____	 _____
0080	403.21041 HMA 9.5 MM - POLYMER MODIFIED THIN LIFT SURFACE TREATMENT	15,550.000 T	_____	 _____	_____	 _____
0090	403.211 HOT MIX ASPHALT (SHIMMING)	10,500.000 T	_____	 _____	_____	 _____
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	100.000 T	_____	 _____	_____	 _____
0110	409.15 BITUMINOUS TACK COAT - APPLIED	22,580.000 G	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023685.00

Project(s): 023685.00, 024467.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	410.151 EMULSIFIED ASPHALT SEALCOAT, APPLIED	15,900.000 SY	_____	 _____	_____	 _____
0130	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	110.000 CY	_____	 _____	_____	 _____
0140	424.22 ASPHALT RUBBER CRACK SEALER TYPE 2, APPLIED	16,700.000 LB	_____	 _____	_____	 _____
0150	462.301 POLYMER MODIFIED ULTRATHIN BONDED WEARING COURSE	110,400.000 SY	_____	 _____	_____	 _____
0160	502.57 ANNULAR SPACE GROUTING	20.000 CY	_____	 _____	_____	 _____
0170	509.202 CULVERT SLIPLINING	LUMP SUM		 LUMP SUM	_____	 _____
0180	603.199 24 INCH CULVERT PIPE OPTION III	250.000 LF	_____	 _____	_____	 _____
0190	603.209 30 INCH CULVERT PIPE OPTION III	66.000 LF	_____	 _____	_____	 _____
0200	603.219 36 INCH CULVERT PIPE OPTION III	360.000 LF	_____	 _____	_____	 _____
0210	603.255 60 INCH REINFORCED CONCRETE PIPE CLASS III	70.000 LF	_____	 _____	_____	 _____
0220	603.55 CONCRETE PIPE TIES	4.000 GP	_____	 _____	_____	 _____
0230	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	7,500.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023685.00

Project(s): 023685.00, 024467.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	25.000 LF	_____	 _____	_____	 _____
0250	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	25.000 LF	_____	 _____	_____	 _____
0260	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	27.000 EA	_____	 _____	_____	 _____
0270	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	 _____	_____	 _____
0280	606.1722 BRIDGE TRANSITION - TYPE 2	4.000 EA	_____	 _____	_____	 _____
0290	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA	_____	 _____	_____	 _____
0300	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	45.000 EA	_____	 _____	_____	 _____
0310	606.356 UNDERDRAIN DELINEATOR POST	5.000 EA	_____	 _____	_____	 _____
0320	610.08 PLAIN RIPRAP	50.000 CY	_____	 _____	_____	 _____
0330	613.319 EROSION CONTROL BLANKET	12,320.000 SY	_____	 _____	_____	 _____
0340	615.10 DIRTY BORROW	700.000 CY	_____	 _____	_____	 _____
0350	618.14 SEEDING METHOD NUMBER 2	880.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023685.00

Project(s): 023685.00, 024467.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	619.12 MULCH	880.000 UN	_____	 _____	_____	 _____
0370	620.58 EROSION CONTROL GEOTEXTILE	250.000 SY	_____	 _____	_____	 _____
0380	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	84.000 SF	_____	 _____	_____	 _____
0390	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	522,690.000 LF	_____	 _____	_____	 _____
0400	629.05 HAND LABOR, STRAIGHT TIME	70.000 HR	_____	 _____	_____	 _____
0410	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	300.000 HR	_____	 _____	_____	 _____
0420	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	600.000 HR	_____	 _____	_____	 _____
0430	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0440	652.33 DRUM	200.000 EA	_____	 _____	_____	 _____
0450	652.34 CONE	280.000 EA	_____	 _____	_____	 _____
0460	652.35 CONSTRUCTION SIGNS	3,130.000 SF	_____	 _____	_____	 _____
0470	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	180.000 CD	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023685.00

Project(s): 023685.00, 024467.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0480	652.38 FLAGGER	5,100.000 HR				
0490	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM		
0500	659.10 MOBILIZATION	LUMP SUM		LUMP SUM		
Section: 1			Total:			

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023685.00

Project(s): 023685.00, 024467.00

SECTION: 2 UTILITY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0510	652.38 FLAGGER	70.000 HR	_____	 _____	_____	 _____
0520	812.162 ADJUSTING SEWER MANHOLE TO GRADE	2.000 EA	_____	 _____	_____	 _____
0530	812.164 REBUILDING SEWER MANHOLE	4.000 EA	_____	 _____	_____	 _____
0540	823.011 GATE VALVE BOX, INSTALL ONLY	2.000 EA	_____	 _____	_____	 _____
0550	823.332 GATE VALVE BOX, ADJUST TO GRADE	6.000 EA	_____	 _____	_____	 _____
Section: 2			Total:		_____	 _____
			Total Bid:		_____	 _____