

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023697.00

Project(s): 023697.00, 023755.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	770.000 CY	_____	 _____	_____	 _____
0020	203.25 GRANULAR BORROW	220.000 CY	_____	 _____	_____	 _____
0030	203.33 SPECIAL FILL	85.000 CY	_____	 _____	_____	 _____
0040	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	60.000 CY	_____	 _____	_____	 _____
0050	304.16 AGGREGATE BASE COURSE - TYPE C	705.000 CY	_____	 _____	_____	 _____
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	75.000 T	_____	 _____	_____	 _____
0070	403.213 HOT MIX ASPHALT 12.5 MM BASE	155.000 T	_____	 _____	_____	 _____
0080	409.15 BITUMINOUS TACK COAT - APPLIED	255.000 G	_____	 _____	_____	 _____
0090	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	55.000 CY	_____	 _____	_____	 _____
0100	502.565 CONCRETE FILL	15.000 CY	_____	 _____	_____	 _____
0110	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED 023755.00	7,000.000 LB	_____	 _____	_____	 _____
0120	503.13 REINFORCING STEEL, PLACING	7,000.000 LB	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023697.00

Project(s): 023697.00, 023755.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	508.13 SHEET WATERPROOFING MEMBRANE 023697.00	LUMP SUM	LUMP	SUM	_____	_____
0140	508.13 SHEET WATERPROOFING MEMBRANE 023755.00	LUMP SUM	LUMP	SUM	_____	_____
0150	511.07 COFFERDAM: 023697.00 - DOWNSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0160	511.07 COFFERDAM: 023697.00 - UPSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0170	511.07 COFFERDAM: 023755.00 - DOWNSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0180	511.07 COFFERDAM: 023755.00 - UPSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0190	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES 023697.00	LUMP SUM	LUMP	SUM	_____	_____
0200	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES 023755.00	LUMP SUM	LUMP	SUM	_____	_____
0210	534.701 PRECAST STRUCTURAL CONCRETE ARCH, STATE SUPPLIED 023755.00	LUMP SUM	LUMP	SUM	_____	_____
0220	534.7101 PRECAST CONCRETE BOX CULVERT - STATE SUPPLIED 023697.00	LUMP SUM	LUMP	SUM	_____	_____
0230	605.09 6 INCH UNDERDRAIN TYPE B	170.000 LF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023697.00

Project(s): 023697.00, 023755.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	606.36 GUARDRAIL REMOVED AND RESET	275.000 LF	_____	 _____	_____	 _____
0250	610.203 FEATURE ROCKS	12.000 EA	_____	 _____	_____	 _____
0260	610.210 STREAM CHANNEL ROCK	50.000 CY	_____	 _____	_____	 _____
0270	610.213 VOID FILLED RIPRAP	250.000 CY	_____	 _____	_____	 _____
0280	613.319 EROSION CONTROL BLANKET	680.000 SY	_____	 _____	_____	 _____
0290	615.07 LOAM	35.000 CY	_____	 _____	_____	 _____
0300	618.14 SEEDING METHOD NUMBER 2	6.000 UN	_____	 _____	_____	 _____
0310	619.12 MULCH	6.000 UN	_____	 _____	_____	 _____
0320	620.58 EROSION CONTROL GEOTEXTILE	450.000 SY	_____	 _____	_____	 _____
0330	627.73 4 INCH YELLOW PAVEMENT MARKING LINE	380.000 LF	_____	 _____	_____	 _____
0340	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	380.000 LF	_____	 _____	_____	 _____
0350	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	760.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023697.00

Project(s): 023697.00, 023755.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	 _____	_____	 _____
0370	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0380	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	80.000 HR	_____	 _____	_____	 _____
0390	639.20 FIELD OFFICE TYPE C	1.000 EA	_____	 _____	_____	 _____
0400	652.312 TYPE III BARRICADE	8.000 EA	_____	 _____	_____	 _____
0410	652.33 DRUM	20.000 EA	_____	 _____	_____	 _____
0420	652.34 CONE	40.000 EA	_____	 _____	_____	 _____
0430	652.35 CONSTRUCTION SIGNS	960.000 SF	_____	 _____	_____	 _____
0440	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	90.000 CD	_____	 _____	_____	 _____
0450	652.38 FLAGGER	450.000 HR	_____	 _____	_____	 _____
0460	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0470	659.10 MOBILIZATION	LUMP SUM	_____	 LUMP SUM	_____	 _____

1/30/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 5

Proposal ID: 023697.00

Project(s): 023697.00, 023755.00

Section: 1

Total:

_____!

Total Bid:

_____!