

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023759.10

Project(s): 023759.10, 024197.10

SECTION: 1 REGIONAL

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	1.000 EA	_____	 _____	_____	 _____
0020	201.24 REMOVING STUMP	2.000 EA	_____	 _____	_____	 _____
0030	202.203 PAVEMENT BUTT JOINTS	940.000 SY	_____	 _____	_____	 _____
0040	204.43 REHABILITATE EXISTING SHOULDERS - TRUCK MEASURE	3,770.000 CY	_____	 _____	_____	 _____
0050	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	210.000 T	_____	 _____	_____	 _____
0060	403.2104 HOT MIX ASPHALT 9.5 MM - THIN LIFT SURFACE TREATMENT	2,900.000 T	_____	 _____	_____	 _____
0070	403.211 HOT MIX ASPHALT (SHIMMING)	3,000.000 T	_____	 _____	_____	 _____
0080	409.15 BITUMINOUS TACK COAT - APPLIED	10,400.000 G	_____	 _____	_____	 _____
0090	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	400.000 CY	_____	 _____	_____	 _____
0100	511.07 COFFERDAM: 70+25 DOWNSTREAM	LUMP SUM	LUMP SUM	 _____	_____	 _____
0110	511.07 COFFERDAM: 70+25 UPSTREAM	LUMP SUM	LUMP SUM	 _____	_____	 _____
0120	603.169 15 INCH CULVERT PIPE OPTION III	30.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023759.10

Project(s): 023759.10, 024197.10

SECTION: 1 REGIONAL

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	603.36 57 INCH SPAN 38 INCH RISE PIPE ARCH	28.000 LF	_____	 _____	_____	 _____
0140	604.242 CATCH BASIN TYPE F3	2.000 EA	_____	 _____	_____	 _____
0150	605.09 6 INCH UNDERDRAIN TYPE B	380.000 LF	_____	 _____	_____	 _____
0160	605.11 12 INCH UNDERDRAIN TYPE C	350.000 LF	_____	 _____	_____	 _____
0170	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	500.000 LF	_____	 _____	_____	 _____
0180	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	50.000 LF	_____	 _____	_____	 _____
0190	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	2.000 EA	_____	 _____	_____	 _____
0200	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	2.000 EA	_____	 _____	_____	 _____
0210	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	14.000 EA	_____	 _____	_____	 _____
0220	606.356 UNDERDRAIN DELINEATOR POST	1.000 EA	_____	 _____	_____	 _____
0230	609.31 CURB TYPE 3	1,090.000 LF	_____	 _____	_____	 _____
0240	610.08 PLAIN RIPRAP	70.000 CY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023759.10

Project(s): 023759.10, 024197.10

SECTION: 1 REGIONAL

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	613.319 EROSION CONTROL BLANKET	1,700.000 SY	_____	 _____	_____	 _____
0260	615.10 DIRTY BORROW	200.000 CY	_____	 _____	_____	 _____
0270	618.14 SEEDING METHOD NUMBER 2	226.000 UN	_____	 _____	_____	 _____
0280	619.12 MULCH	226.000 UN	_____	 _____	_____	 _____
0290	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	60,570.000 LF	_____	 _____	_____	 _____
0300	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	40.000 SF	_____	 _____	_____	 _____
0310	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	60,500.000 LF	_____	 _____	_____	 _____
0320	629.05 HAND LABOR, STRAIGHT TIME	25.000 HR	_____	 _____	_____	 _____
0330	631.111 TRACTOR MOUNTED HYDRAULIC HAMMER	90.000 HR	_____	 _____	_____	 _____
0340	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	260.000 HR	_____	 _____	_____	 _____
0350	631.14 GRADER (INCLUDING OPERATOR)	25.000 HR	_____	 _____	_____	 _____
0360	631.161 PAVING CREW	95.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023759.10

Project(s): 023759.10, 024197.10

SECTION: 1 REGIONAL

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	631.162 PAVING CREW (OVERTIME)	39.000 HR	_____	 _____	_____	 _____
0380	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	520.000 HR	_____	 _____	_____	 _____
0390	631.179 PUGMILL TRUCKING	8,600.000 T	_____	 _____	_____	 _____
0400	631.21 ROAD BROOM (INCLUDING OPERATORS AND HAULER)	22.000 HR	_____	 _____	_____	 _____
0410	631.22 FRONT END LOADER (INCLUDING OPERATOR)	12.000 HR	_____	 _____	_____	 _____
0420	652.33 DRUM	60.000 EA	_____	 _____	_____	 _____
0430	652.34 CONE	140.000 EA	_____	 _____	_____	 _____
0440	652.35 CONSTRUCTION SIGNS	1,090.000 SF	_____	 _____	_____	 _____
0450	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	123.000 CD	_____	 _____	_____	 _____
0460	652.38 FLAGGER	2,400.000 HR	_____	 _____	_____	 _____
0470	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0480	659.10 MOBILIZATION	LUMP SUM	_____	 LUMP SUM	_____	 _____

5/1/2023

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 5

Proposal ID: 023759.10

Project(s): 023759.10, 024197.10

Section: 1

Total:

\_\_\_\_\_!

Total Bid:

\_\_\_\_\_!