

11/13/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 11

Proposal ID: 023909.00

Project(s): 023909.00

SECTION: 1 MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.13 REMOVING EXISTING RAILINGS (RETAINED BY DEPARTMENT)	206.000 LF	_____	 _____	_____	 _____
0020	202.19 REMOVING EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	 _____
0030	202.20 REMOVING BITUMINOUS CONCRETE PAVEMENT	1,010.000 SY	_____	 _____	_____	 _____
0040	202.202 REMOVING PAVEMENT SURFACE	270.000 SY	_____	 _____	_____	 _____
0050	203.20 COMMON EXCAVATION	2,450.000 CY	_____	 _____	_____	 _____
0060	203.2318 DISPOSAL OF SPECIAL WASTE	680.000 T	_____	 _____	_____	 _____
0070	203.24 COMMON BORROW	50.000 CY	_____	 _____	_____	 _____
0080	203.25 GRANULAR BORROW	880.000 CY	_____	 _____	_____	 _____
0090	203.33 SPECIAL FILL	100.000 CY	_____	 _____	_____	 _____
0100	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	1,140.000 CY	_____	 _____	_____	 _____
0110	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2,400.000 CY	_____	 _____	_____	 _____
0120	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	270.000 T	_____	 _____	_____	 _____

11/13/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 11

Proposal ID: 023909.00

Project(s): 023909.00

SECTION: 1 MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	17.000 T	_____	 _____	_____	 _____
0140	403.213 HOT MIX ASPHALT 12.5 MM BASE	280.000 T	_____	 _____	_____	 _____
0150	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	260.000 T	_____	 _____	_____	 _____
0160	409.15 BITUMINOUS TACK COAT - APPLIED	200.000 G	_____	 _____	_____	 _____
0170	501.231 DYNAMIC LOADING TEST	14.000 EA	_____	 _____	_____	 _____
0180	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	1,010.000 LF	_____	 _____	_____	 _____
0190	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	920.000 LF	_____	 _____	_____	 _____
0200	501.90 PILE TIPS	11.000 EA	_____	 _____	_____	 _____
0210	501.903 PILE TIPS - ROCK INJECTOR POINT	7.000 EA	_____	 _____	_____	 _____
0220	501.91 PILE SPLICES	16.000 EA	_____	 _____	_____	 _____
0230	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM	_____	 LUMP SUM	_____	 _____
0240	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	_____	 LUMP SUM	_____	 _____

11/13/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 11

Proposal ID: 023909.00

Project(s): 023909.00

SECTION: 1 MAIN ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM	LUMP	SUM	_____	_____
0260	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP	SUM	_____	_____
0270	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP	SUM	_____	_____
0280	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	27,770.000 LB	_____	_____	_____	_____
0290	503.13 REINFORCING STEEL, PLACING	27,770.000 LB	_____	_____	_____	_____
0300	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	9,080.000 LB	_____	_____	_____	_____
0310	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	9,080.000 LB	_____	_____	_____	_____
0320	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM	LUMP	SUM	_____	_____
0330	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM	LUMP	SUM	_____	_____
0340	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	SUM	_____	_____
0350	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	SUM	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 11

Proposal ID: 023909.00

Project(s): 023909.00

SECTION: 1 MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0370	511.07 COFFERDAM: ABUTMENT 1	LUMP SUM	LUMP	SUM	_____	_____
0380	511.07 COFFERDAM: ABUTMENT 2	LUMP SUM	LUMP	SUM	_____	_____
0390	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA	_____	_____	_____	_____
0400	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0410	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	64.000 LF	_____	_____	_____	_____
0420	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA	_____	_____	_____	_____
0430	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	_____	_____	_____
0440	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	43,500.000 LF	_____	_____	_____	_____
0450	530.31 GFRP, REINFORCEMENT BARS, PLACING	43,500.000 LF	_____	_____	_____	_____
0460	603.159 12 INCH CULVERT PIPE OPTION III	12.000 LF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 11

Proposal ID: 023909.00

Project(s): 023909.00

SECTION: 1

MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	603.169 15 INCH CULVERT PIPE OPTION III	142.000 LF				
0480	604.246 CATCH BASIN TYPE F5	1.000 EA				
0490	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	425.000 LF				
0500	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	4.000 EA				
0510	606.1307 BRIDGE TRANSITION (ASYMMETRICAL) - TYPE 1A	4.000 EA				
0520	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0530	606.47 SINGLE WOOD POST	2.000 EA				
0540	609.31 CURB TYPE 3	44.000 LF				
0550	610.08 PLAIN RIPRAP	1,890.000 CY				
0560	610.18 STONE DITCH PROTECTION	100.000 CY				
0570	613.319 EROSION CONTROL BLANKET	370.000 SY				
0580	615.07 LOAM	140.000 CY				

11/13/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 11

Proposal ID: 023909.00

Project(s): 023909.00

SECTION: 1

MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	618.14 SEEDING METHOD NUMBER 2	22.000 UN	_____	_____	_____	_____
0600	619.12 MULCH	22.000 UN	_____	_____	_____	_____
0610	619.14 EROSION CONTROL MIX	270.000 CY	_____	_____	_____	_____
0620	620.58 EROSION CONTROL GEOTEXTILE	2,280.000 SY	_____	_____	_____	_____
0630	620.66 DRAINAGE GEOCOMPOSITE	110.000 SY	_____	_____	_____	_____
0640	621.267 LARGE DECIDUOUS TREE (1.75 INCH - 2 INCH CALIPER) GROUP A	3.000 EA	_____	_____	_____	_____
0650	621.52 DECIDUOUS SHRUBS (8 INCH - 15 INCH) ROOTED CUTTINGS	36.000 EA	_____	_____	_____	_____
0660	621.546 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP A	30.000 EA	_____	_____	_____	_____
0670	621.552 DECIDUOUS SHRUBS (3 FOOT - 4 FOOT) GROUP A	6.000 EA	_____	_____	_____	_____
0680	621.71 HERBACEOUS PERENNIALS GROUP A	60.000 EA	_____	_____	_____	_____
0690	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2,400.000 LF	_____	_____	_____	_____
0700	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	_____	_____	_____

11/13/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 11

Proposal ID: 023909.00

Project(s): 023909.00

SECTION: 1 MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0710	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	30.000 HR	_____	 _____	_____	 _____
0720	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0730	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0740	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	30.000 HR	_____	 _____	_____	 _____
0750	631.22 FRONT END LOADER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0760	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0770	645.103 DEMOUNT GUIDE SIGN	1.000 EA	_____	 _____	_____	 _____
0780	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	6.000 EA	_____	 _____	_____	 _____
0790	645.113 REINSTALL GUIDE SIGN	1.000 EA	_____	 _____	_____	 _____
0800	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	3.000 EA	_____	 _____	_____	 _____
0810	652.31 TYPE I BARRICADE	10.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023909.00

Project(s): 023909.00

SECTION: 1

MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0820	652.312 TYPE III BARRICADE	10.000 EA	_____	 _____	_____	 _____
0830	652.33 DRUM	20.000 EA	_____	 _____	_____	 _____
0840	652.34 CONE	40.000 EA	_____	 _____	_____	 _____
0850	652.35 CONSTRUCTION SIGNS	500.000 SF	_____	 _____	_____	 _____
0860	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES 200 CD	LUMP SUM	LUMP SUM		_____	 _____
0870	652.38 FLAGGER	850.000 HR	_____	 _____	_____	 _____
0880	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	 _____	_____	 _____
0890	653.22 2 INCH POLYSTYRENE PLASTIC INSULATION	10.000 SY	_____	 _____	_____	 _____
0900	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0910	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
0920	801.03 TEST PITS	2.000 EA	_____	 _____	_____	 _____
0930	801.071 TEMPORARY SEWER BY-PASS	LUMP SUM	LUMP SUM		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Page 9 of 11

Proposal ID: 023909.00

Project(s): 023909.00

SECTION: 1

MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0940	822.3405 8 INCH CLASS 52 DUCTILE IRON PIPE PUSH ON JOINT	140.000 LF	_____	 _____	_____	 _____
0950	822.34051 8 INCH CLASS 52 DUCTILE IRON PIPE PUSH ON JOINT - PREINSULATED	80.000 LF	_____	 _____	_____	 _____
0960	822.34052 8" CLASS 52 DUCTILE IRON PIPE RESTRAINED JOINT, PREINSUL	320.000 LF	_____	 _____	_____	 _____
0970	822.3605 12" CLASS 52 DUCTILE IRON PIPE PUSH ON JOINT	200.000 LF	_____	 _____	_____	 _____
0980	822.3632 12" CLASS 52 DUCTILE IRON PIPE RESTRAINED JOINT - PREINSULATED	320.000 LF	_____	 _____	_____	 _____
0990	823.3101 12" CUT-IN MJ GATE VALVE	2.000 EA	_____	 _____	_____	 _____
1000	823.3254 8" INSERTION VALVE	1.000 EA	_____	 _____	_____	 _____
1010	823.34 BLOW OFF VALVE ASSEMBLY	2.000 EA	_____	 _____	_____	 _____
1020	823.341 AIR RELEASE VALVE	1.000 EA	_____	 _____	_____	 _____
1030	825.431 1 1/2 INCH COPPER SERVICE	20.000 LF	_____	 _____	_____	 _____
1040	830.13 SEWER MAIN BRIDGE CROSSING 8 INCH	LUMP SUM	LUMP SUM		_____	 _____

11/13/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 10 of 11

Proposal ID: 023909.00

Project(s): 023909.00

SECTION: 1 MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1050	830.15 WATER MAIN BRIDGE CROSSING HANGER SYSTEM 12 INCH	LUMP SUM		LUMP SUM		
Section: 1			Total:			

SECTION: 2 ONE LANE TEMPORARY DETOUR

Alt Set ID: AL

Alt Mbr ID: 1

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1060	461.131 TEMPORARY PAVEMENT	250.000 T				
1070	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 18 FOOT	LUMP SUM		LUMP SUM		
1080	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM		LUMP SUM		
1090	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,740.000 LF				
1100	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM		LUMP SUM		
Section: 2			Total:			

11/13/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 11 of 11

Proposal ID: 023909.00

Project(s): 023909.00

SECTION: 3 TWO LANE TEMPORARY DETOUR

Alt Set ID: AL

Alt Mbr ID: 2

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1110	461.131 TEMPORARY PAVEMENT	530.000 T	_____	_____	_____	_____
1120	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 30 FOOT	LUMP SUM	LUMP	SUM	_____	_____
1130	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
1140	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	3,250.000 LF	_____	_____	_____	_____
Section: 3			Total:		_____	_____
			Total Bid:		_____	_____