

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 024129.00

Project(s): 024129.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	72,000.000 SY	_____	 _____	_____	 _____
0020	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	6,000.000 T	_____	 _____	_____	 _____
0030	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	20.000 T	_____	 _____	_____	 _____
0040	403.211 HOT MIX ASPHALT (SHIMMING)	2,050.000 T	_____	 _____	_____	 _____
0050	403.213 HOT MIX ASPHALT 12.5 MM BASE	20.000 T	_____	 _____	_____	 _____
0060	409.15 BITUMINOUS TACK COAT - APPLIED	5,900.000 G	_____	 _____	_____	 _____
0070	410.151 EMULSIFIED ASPHALT SEALCOAT, APPLIED	33,600.000 SY	_____	 _____	_____	 _____
0080	424.22 ASPHALT RUBBER CRACK SEALER TYPE 2, APPLIED	11,200.000 LB	_____	 _____	_____	 _____
0090	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	88.000 LF	_____	 _____	_____	 _____
0100	603.55 CONCRETE PIPE TIES	2.000 GP	_____	 _____	_____	 _____
0110	606.178 GUARDRAIL BEAM	1,000.000 LF	_____	 _____	_____	 _____
0120	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	50.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 024129.00

Project(s): 024129.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	606.356 UNDERDRAIN DELINEATOR POST	75.000 EA	_____	 _____	_____	 _____
0140	606.362 GUARDRAIL ADJUSTED	5,000.000 LF	_____	 _____	_____	 _____
0150	610.08 PLAIN RIPRAP	44.000 CY	_____	 _____	_____	 _____
0160	613.319 EROSION CONTROL BLANKET	230.000 SY	_____	 _____	_____	 _____
0170	618.14 SEEDING METHOD NUMBER 2	282.000 UN	_____	 _____	_____	 _____
0180	619.12 MULCH	282.000 UN	_____	 _____	_____	 _____
0190	620.58 EROSION CONTROL GEOTEXTILE	160.000 SY	_____	 _____	_____	 _____
0200	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	72,200.000 LF	_____	 _____	_____	 _____
0210	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	84.000 SF	_____	 _____	_____	 _____
0220	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	145,000.000 LF	_____	 _____	_____	 _____
0230	629.05 HAND LABOR, STRAIGHT TIME	60.000 HR	_____	 _____	_____	 _____
0240	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	120.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 024129.00

Project(s): 024129.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	631.133 SKID STEER (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0260	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	240.000 HR	_____	 _____	_____	 _____
0270	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	8.000 HR	_____	 _____	_____	 _____
0280	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0290	652.33 DRUM	20.000 EA	_____	 _____	_____	 _____
0300	652.34 CONE	180.000 EA	_____	 _____	_____	 _____
0310	652.35 CONSTRUCTION SIGNS	1,040.000 SF	_____	 _____	_____	 _____
0320	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	52.000 CD	_____	 _____	_____	 _____
0330	652.38 FLAGGER	950.000 HR	_____	 _____	_____	 _____
0340	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	3.000 EA	_____	 _____	_____	 _____
0350	652.47 TEMPORARY PORTABLE RUMBLE STRIP	4.000 GP	_____	 _____	_____	 _____
0360	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____

