

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 024241.00

Project(s): 024241.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	700.000 CY	_____	 _____	_____	 _____
0020	203.24 COMMON BORROW	110.000 CY	_____	 _____	_____	 _____
0030	203.25 GRANULAR BORROW	220.000 CY	_____	 _____	_____	 _____
0040	203.33 SPECIAL FILL	115.000 CY	_____	 _____	_____	 _____
0050	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	20.000 CY	_____	 _____	_____	 _____
0060	304.16 AGGREGATE BASE COURSE - TYPE C	600.000 CY	_____	 _____	_____	 _____
0070	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	60.000 T	_____	 _____	_____	 _____
0080	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	140.000 T	_____	 _____	_____	 _____
0090	409.15 BITUMINOUS TACK COAT - APPLIED	22.000 G	_____	 _____	_____	 _____
0100	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	_____	 LUMP SUM	_____	 _____
0110	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM	_____	 LUMP SUM	_____	 _____
0120	511.07 COFFERDAM: UPSTREAM	LUMP SUM	_____	 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 024241.00

Project(s): 024241.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	76.000 SY	_____	 _____	_____	 _____
0140	534.7101 PRECAST CONCRETE BOX CULVERT - STATE SUPPLIED	LUMP SUM	LUMP SUM		_____	 _____
0150	610.08 PLAIN RIPRAP	170.000 CY	_____	 _____	_____	 _____
0160	610.212 STREAMBED ROCK FEATURES	5.000 CY	_____	 _____	_____	 _____
0170	610.213 VOID FILLED RIPRAP	25.000 CY	_____	 _____	_____	 _____
0180	613.319 EROSION CONTROL BLANKET	130.000 SY	_____	 _____	_____	 _____
0190	615.10 DIRTY BORROW	60.000 CY	_____	 _____	_____	 _____
0200	618.14 SEEDING METHOD NUMBER 2	9.000 UN	_____	 _____	_____	 _____
0210	619.12 MULCH	9.000 UN	_____	 _____	_____	 _____
0220	620.58 EROSION CONTROL GEOTEXTILE	260.000 SY	_____	 _____	_____	 _____
0230	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	675.000 LF	_____	 _____	_____	 _____
0240	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 024241.00

Project(s): 024241.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0260	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0270	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0280	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM		_____	 _____
0290	652.312 TYPE III BARRICADE	2.000 EA	_____	 _____	_____	 _____
0300	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____
0310	652.34 CONE	25.000 EA	_____	 _____	_____	 _____
0320	652.35 CONSTRUCTION SIGNS	640.000 SF	_____	 _____	_____	 _____
0330	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	60.000 CD	_____	 _____	_____	 _____
0340	652.38 FLAGGER	40.000 HR	_____	 _____	_____	 _____
0350	652.61 STAGED CONSTRUCTION AND TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0360	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____

