

5/8/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 4

Proposal ID: 024281.00

Project(s): 024281.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	1,515.000 SY	_____	 _____	_____	 _____
0020	203.20 COMMON EXCAVATION	1,572.000 CY	_____	 _____	_____	 _____
0030	203.25 GRANULAR BORROW	295.000 CY	_____	 _____	_____	 _____
0040	203.33 SPECIAL FILL	75.000 CY	_____	 _____	_____	 _____
0050	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	160.000 CY	_____	 _____	_____	 _____
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1,415.000 CY	_____	 _____	_____	 _____
0070	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	310.000 T	_____	 _____	_____	 _____
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	275.000 T	_____	 _____	_____	 _____
0090	409.15 BITUMINOUS TACK COAT - APPLIED	155.000 G	_____	 _____	_____	 _____
0100	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	LUMP SUM		_____	 _____
0110	511.07 COFFERDAM: - DOWNSTREAM	LUMP SUM	LUMP SUM		_____	 _____
0120	511.07 COFFERDAM: - UPSTREAM	LUMP SUM	LUMP SUM		_____	 _____

5/8/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 4

Proposal ID: 024281.00

Project(s): 024281.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	534.71 PRECAST CONCRETE BOX CULVERT	LUMP SUM				
0140	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	460.000 LF				
0150	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	1.000 EA				
0160	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	1.000 EA				
0170	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.000 EA				
0180	610.08 PLAIN RIPRAP	65.000 CY				
0190	610.210 STREAM CHANNEL ROCK	30.000 CY				
0200	619.14 EROSION CONTROL MIX	185.000 CY				
0210	620.58 EROSION CONTROL GEOTEXTILE	85.000 SY				
0220	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2,300.000 LF				
0230	629.05 HAND LABOR, STRAIGHT TIME	15.000 HR				
0240	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				

5/8/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 4

Proposal ID: 024281.00

Project(s): 024281.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0260	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	5.000 HR	_____	_____	_____	_____
0270	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	5.000 HR	_____	_____	_____	_____
0280	631.22 FRONT END LOADER (INCLUDING OPERATOR)	5.000 HR	_____	_____	_____	_____
0290	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____
0300	652.311 TYPE II BARRICADE	5.000 EA	_____	_____	_____	_____
0310	652.312 TYPE III BARRICADE	8.000 EA	_____	_____	_____	_____
0320	652.33 DRUM	50.000 EA	_____	_____	_____	_____
0330	652.34 CONE	75.000 EA	_____	_____	_____	_____
0340	652.35 CONSTRUCTION SIGNS	475.000 SF	_____	_____	_____	_____
0350	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	50.000 CD	_____	_____	_____	_____
0360	652.38 FLAGGER	750.000 HR	_____	_____	_____	_____

5/8/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 4

Proposal ID: 024281.00

Project(s): 024281.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	_____	_____	_____
0380	652.61 STAGED CONSTRUCTION AND TRAFFIC CONTROL	LUMP SUM	LUMP SUM	_____	_____	_____
0390	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM	_____	_____	_____
0400	659.10 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
Section: 1			Total:		_____	_____

SECTION: 2 WATER DISTRICT - WATERLINE RELOCATION

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0410	801.03 TEST PITS	2.000 EA	_____	_____	_____	_____
0420	822.363 12 INCH CLASS 52 DUCTILE IRON PIPE -WATER DISTRICT SUPPLIED	290.000 LF	_____	_____	_____	_____
Section: 2			Total:		_____	_____
			Total Bid:		_____	_____