

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 024879.00

Project(s): 024879.00

SECTION: 1 Highway Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	160.000 SY	_____	 _____	_____	 _____
0020	409.15 BITUMINOUS TACK COAT - APPLIED	6,380.000 G	_____	 _____	_____	 _____
0030	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	120.000 CY	_____	 _____	_____	 _____
0040	461.210 9.5 MM HMA - CYCLICAL PAVEMENT RESURFACING	4,670.000 T	_____	 _____	_____	 _____
0050	461.216 HOT MIX ASPHALT (SHIMMING)	3,640.000 T	_____	 _____	_____	 _____
0060	618.13 SEEDING METHOD NUMBER 1	40.000 UN	_____	 _____	_____	 _____
0070	618.14 SEEDING METHOD NUMBER 2	100.000 UN	_____	 _____	_____	 _____
0080	619.12 MULCH	140.000 UN	_____	 _____	_____	 _____
0090	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	106,950.000 LF	_____	 _____	_____	 _____
0100	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	106,950.000 LF	_____	 _____	_____	 _____
0110	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0120	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	100.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 024879.00

Project(s): 024879.00

SECTION: 1 Highway Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	200.000 HR	_____	 _____	_____	 _____
0140	652.34 CONE	120.000 EA	_____	 _____	_____	 _____
0150	652.35 CONSTRUCTION SIGNS	700.000 SF	_____	 _____	_____	 _____
0160	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	56.000 CD	_____	 _____	_____	 _____
0170	652.38 FLAGGER	1,070.000 HR	_____	 _____	_____	 _____
0180	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0190	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
<b>Section: 1</b>			<b>Total:</b>		_____	 _____
			<b>Total Bid:</b>		_____	 _____