

3/12/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 4

Proposal ID: 025387.00

Project(s): 025387.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.121 REMOVING EXISTING CONCRETE	LUMP SUM				
0020	202.202 REMOVING PAVEMENT SURFACE	440.000 SY				
0030	203.20 COMMON EXCAVATION	1,300.000 CY				
0040	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1,050.000 CY				
0050	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	161.000 T				
0060	403.213 HOT MIX ASPHALT 12.5 MM BASE	220.000 T				
0070	409.15 BITUMINOUS TACK COAT - APPLIED	92.000 G				
0080	461.131 TEMPORARY PAVEMENT	150.000 T				
0090	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA				
0100	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 16 FOOT	LUMP SUM				
0110	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM				
0120	511.07 COFFERDAM: UPSTREAM	LUMP SUM				

3/12/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 4

Proposal ID: 025387.00

Project(s): 025387.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM		LUMP SUM		
0140	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN				
0150	531.51 BRIDGE STRUCTURE - DETAIL BUILD	LUMP SUM		LUMP SUM		
0160	603.17 18 INCH CULVERT PIPE OPTION I	34.000 LF				
0170	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	338.000 LF				
0180	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	4.000 EA				
0190	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0200	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0210	610.08 PLAIN RIPRAP	450.000 CY				
0220	610.18 STONE DITCH PROTECTION	5.000 CY				
0230	610.213 VOID FILLED RIPRAP	370.000 CY				
0240	613.319 EROSION CONTROL BLANKET	195.000 SY				

3/12/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 4

Proposal ID: 025387.00

Project(s): 025387.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	615.07 LOAM	45.000 CY	_____	_____	_____	_____
0260	618.14 SEEDING METHOD NUMBER 2	8.000 UN	_____	_____	_____	_____
0270	619.12 MULCH	8.000 UN	_____	_____	_____	_____
0280	619.14 EROSION CONTROL MIX	90.000 CY	_____	_____	_____	_____
0290	620.58 EROSION CONTROL GEOTEXTILE	1,044.000 SY	_____	_____	_____	_____
0300	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,725.000 LF	_____	_____	_____	_____
0310	627.77 REMOVING PAVEMENT MARKINGS	410.000 SF	_____	_____	_____	_____
0320	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,300.000 LF	_____	_____	_____	_____
0330	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	_____	_____	_____
0340	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0350	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0360	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____

3/12/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 4

Proposal ID: 025387.00

Project(s): 025387.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0380	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0390	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM		_____	 _____
0400	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0410	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____
0420	652.34 CONE	50.000 EA	_____	 _____	_____	 _____
0430	652.35 CONSTRUCTION SIGNS	400.000 SF	_____	 _____	_____	 _____
0440	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
0450	652.38 FLAGGER	400.000 HR	_____	 _____	_____	 _____
0460	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0470	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____