

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025449.00

Project(s): 025449.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description   | Approximate Quantity and Units | Unit Price |       | Bid Amount |       |
|----------------------|---|--------------------------------|------------|-------|------------|-------|
|                      |   |                                | Dollars    | Cents | Dollars    | Cents |
| 0010                 | 202.19<br>REMOVING EXISTING BRIDGE  | LUMP SUM                       | LUMP SUM   |       | _____      | _____ |
| 0020                 | 202.202<br>REMOVING PAVEMENT SURFACE  | 435.000<br>SY                  | _____      | _____ | _____      | _____ |
| 0030                 | 203.20<br>COMMON EXCAVATION   | 550.000<br>CY                  | _____      | _____ | _____      | _____ |
| 0040                 | 203.2318<br>DISPOSAL OF SPECIAL WASTE   | 420.000<br>T                   | _____      | _____ | _____      | _____ |
| 0050                 | 203.24<br>COMMON BORROW   | 50.000<br>CY                   | _____      | _____ | _____      | _____ |
| 0060                 | 203.25<br>GRANULAR BORROW   | 70.000<br>CY                   | _____      | _____ | _____      | _____ |
| 0070                 | 203.33<br>SPECIAL FILL  | 105.000<br>CY                  | _____      | _____ | _____      | _____ |
| 0080                 | 203.55<br>CULVERT BEDDING STONE   | 65.000<br>CY                   | _____      | _____ | _____      | _____ |
| 0090                 | 206.061<br>STRUCTURAL EARTH EXCAVATION -<br>DRAINAGE AND MINOR<br>STRUCTURES, BELOW GRADE | 70.000<br>CY                   | _____      | _____ | _____      | _____ |
| 0100                 | 304.10<br>AGGREGATE SUBBASE COURSE -<br>GRAVEL  | 660.000<br>CY                  | _____      | _____ | _____      | _____ |
| 0110                 | 403.208<br>HOT MIX ASPHALT 12.5 MM HMA<br>SURFACE   | 130.000<br>T                   | _____      | _____ | _____      | _____ |
| 0120                 | 403.213<br>HOT MIX ASPHALT 12.5 MM BASE   | 200.000<br>T                   | _____      | _____ | _____      | _____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025449.00

Project(s): 025449.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description                                     | Approximate Quantity and Units | Unit Price |           | Bid Amount |           |
|----------------------|---|--------------------------------|------------|-----------|------------|-----------|
|                      |   |                                | Dollars    | Cents     | Dollars    | Cents     |
| 0130                 | 409.15<br>BITUMINOUS TACK COAT - APPLIED                | 62.000<br>G                    | _____      | <br>_____ | _____      | <br>_____ |
| 0140                 | 508.13<br>SHEET WATERPROOFING MEMBRANE                  | LUMP SUM                       | LUMP SUM   |           | _____      | <br>_____ |
| 0150                 | 511.07<br>COFFERDAM: DOWNSTREAM                         | LUMP SUM                       | LUMP SUM   |           | _____      | <br>_____ |
| 0160                 | 511.07<br>COFFERDAM: UPSTREAM                           | LUMP SUM                       | LUMP SUM   |           | _____      | <br>_____ |
| 0170                 | 515.21<br>PROTECTIVE COATING FOR CONCRETE SURFACES      | LUMP SUM                       | LUMP SUM   |           | _____      | <br>_____ |
| 0180                 | 526.301<br>PORTABLE CONCRETE BARRIER TYPE I             | LUMP SUM                       | LUMP SUM   |           | _____      | <br>_____ |
| 0190                 | 534.71<br>PRECAST CONCRETE BOX CULVERT                  | LUMP SUM                       | LUMP SUM   |           | _____      | <br>_____ |
| 0200                 | 606.1301<br>31" W-BM GR, MID-WAY SPLICE-SGL FACED       | 262.500<br>LF                  | _____      | <br>_____ | _____      | <br>_____ |
| 0210                 | 606.1305<br>31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL | 4.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0220                 | 606.353<br>REFLECTORIZED FLEXIBLE GUARDRAIL MARKER      | 8.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0230                 | 610.08<br>PLAIN RIPRAP                                  | 50.000<br>CY                   | _____      | <br>_____ | _____      | <br>_____ |
| 0240                 | 610.213<br>VOID FILLED RIPRAP                           | 85.000<br>CY                   | _____      | <br>_____ | _____      | <br>_____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025449.00

Project(s): 025449.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description   | Approximate Quantity and Units | Unit Price |           | Bid Amount |           |
|----------------------|---|--------------------------------|------------|-----------|------------|-----------|
|                      |   |                                | Dollars    | Cents     | Dollars    | Cents     |
| 0250                 | 613.319<br>EROSION CONTROL BLANKET  | 128.000<br>SY                  | _____      | <br>_____ | _____      | <br>_____ |
| 0260                 | 615.07<br>LOAM  | 36.000<br>CY                   | _____      | <br>_____ | _____      | <br>_____ |
| 0270                 | 618.14<br>SEEDING METHOD NUMBER 2   | 5.000<br>UN                    | _____      | <br>_____ | _____      | <br>_____ |
| 0280                 | 619.12<br>MULCH   | 5.000<br>UN                    | _____      | <br>_____ | _____      | <br>_____ |
| 0290                 | 619.14<br>EROSION CONTROL MIX   | 36.000<br>CY                   | _____      | <br>_____ | _____      | <br>_____ |
| 0300                 | 620.54<br>STABILIZATION/REINFORCEMENT<br>GEOTEXTILE                             | 230.000<br>SY                  | _____      | <br>_____ | _____      | <br>_____ |
| 0310                 | 620.58<br>EROSION CONTROL GEOTEXTILE  | 150.000<br>SY                  | _____      | <br>_____ | _____      | <br>_____ |
| 0320                 | 627.733<br>4" WHITE OR YELLOW PAINTED<br>PAVEMENT MARKING LINE                  | 1,150.000<br>LF                | _____      | <br>_____ | _____      | <br>_____ |
| 0330                 | 627.78<br>TEMPORARY 4 INCH PAINTED<br>PAVEMENT MARKING LINE, WHITE<br>OR YELLOW | 1,150.000<br>LF                | _____      | <br>_____ | _____      | <br>_____ |
| 0340                 | 629.05<br>HAND LABOR, STRAIGHT TIME   | 10.000<br>HR                   | _____      | <br>_____ | _____      | <br>_____ |
| 0350                 | 631.12<br>ALL PURPOSE EXCAVATOR<br>(INCLUDING OPERATOR)                         | 10.000<br>HR                   | _____      | <br>_____ | _____      | <br>_____ |
| 0360                 | 631.14<br>GRADER (INCLUDING OPERATOR)   | 10.000<br>HR                   | _____      | <br>_____ | _____      | <br>_____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025449.00

Project(s): 025449.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description  | Approximate Quantity and Units | Unit Price |              | Bid Amount |           |
|----------------------|--|--------------------------------|------------|--------------|------------|-----------|
|                      |  |                                | Dollars    | Cents        | Dollars    | Cents     |
| 0370                 | 631.15<br>ROLLER, EARTH AND BASE COURSE<br>(INCLUDING OPERATOR ) | 10.000<br>HR                   | _____      | <br>_____    | _____      | <br>_____ |
| 0380                 | 631.172<br>TRUCK - LARGE (INCLUDING<br>OPERATOR)                 | 10.000<br>HR                   | _____      | <br>_____    | _____      | <br>_____ |
| 0390                 | 639.19<br>FIELD OFFICE TYPE B                                    | 1.000<br>EA                    | _____      | <br>_____    | _____      | <br>_____ |
| 0400                 | 652.312<br>TYPE III BARRICADE                                    | 4.000<br>EA                    | _____      | <br>_____    | _____      | <br>_____ |
| 0410                 | 652.33<br>DRUM   | 20.000<br>EA                   | _____      | <br>_____    | _____      | <br>_____ |
| 0420                 | 652.34<br>CONE   | 20.000<br>EA                   | _____      | <br>_____    | _____      | <br>_____ |
| 0430                 | 652.35<br>CONSTRUCTION SIGNS                                     | 400.000<br>SF                  | _____      | <br>_____    | _____      | <br>_____ |
| 0440                 | 652.361<br>MAINTENANCE OF TRAFFIC<br>CONTROL DEVICES             | LUMP SUM                       |            | <br>LUMP SUM | _____      | <br>_____ |
| 0450                 | 652.38<br>FLAGGER  | 150.000<br>HR                  | _____      | <br>_____    | _____      | <br>_____ |
| 0460                 | 652.41<br>PORTABLE CHANGEABLE MESSAGE<br>SIGN                    | 2.000<br>EA                    | _____      | <br>_____    | _____      | <br>_____ |
| 0470                 | 656.75<br>TEMPORARY SOIL EROSION AND<br>WATER POLLUTION CONTROL  | LUMP SUM                       |            | <br>LUMP SUM | _____      | <br>_____ |
| 0480                 | 659.10<br>MOBILIZATION   | LUMP SUM                       |            | <br>LUMP SUM | _____      | <br>_____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025449.00

Project(s): 025449.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description                   | Approximate Quantity and Units | Unit Price        |       | Bid Amount |       |
|----------------------|---------------------------------------|--------------------------------|-------------------|-------|------------|-------|
|                      |                                       |                                | Dollars           | Cents | Dollars    | Cents |
| 0490                 | 834.322<br>DRY HYDRANT - INSTALL ONLY | LUMP SUM                       |                   |       |            |       |
|                      |                                       | <b>Section: 1</b>              |                   |       |            |       |
|                      |                                       |                                | <b>Total:</b>     |       |            |       |
|                      |                                       |                                | <b>Total Bid:</b> |       |            |       |