

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025529.00

Project(s): 025529.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	_____
0020	202.202 REMOVING PAVEMENT SURFACE	120.000 SY	_____	_____	_____	_____
0030	203.20 COMMON EXCAVATION	770.000 CY	_____	_____	_____	_____
0040	203.25 GRANULAR BORROW	266.000 CY	_____	_____	_____	_____
0050	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	630.000 CY	_____	_____	_____	_____
0060	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	30.000 CY	_____	_____	_____	_____
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	600.000 CY	_____	_____	_____	_____
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	89.000 T	_____	_____	_____	_____
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	5.000 T	_____	_____	_____	_____
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	140.000 T	_____	_____	_____	_____
0110	409.15 BITUMINOUS TACK COAT - APPLIED	63.000 G	_____	_____	_____	_____
0120	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP SUM		_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025529.00

Project(s): 025529.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED UNDER WATER)	84.000 CY	_____	 _____	_____	 _____
0140	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP SUM	_____	 LUMP SUM	_____	 _____
0150	502.291 SAW CUT GROOVING	LUMP SUM	_____	 LUMP SUM	_____	 _____
0160	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	_____	 LUMP SUM	_____	 _____
0170	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	_____	 LUMP SUM	_____	 _____
0180	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	14,900.000 LB	_____	 _____	_____	 _____
0190	503.13 REINFORCING STEEL, PLACING	14,900.000 LB	_____	 _____	_____	 _____
0200	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	3,100.000 LB	_____	 _____	_____	 _____
0210	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	3,100.000 LB	_____	 _____	_____	 _____
0220	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	_____	 LUMP SUM	_____	 _____
0230	511.07 COFFERDAM: ABUT NO.1	LUMP SUM	_____	 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025529.00

Project(s): 025529.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	511.07 COFFERDAM: ABUT NO.2	LUMP SUM	LUMP	SUM	_____	_____
0250	512.081 FRENCH DRAINS	LUMP SUM	LUMP	SUM	_____	_____
0260	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0270	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP SUM	LUMP	SUM	_____	_____
0280	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0290	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA	_____	_____	_____	_____
0300	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	8,000.000 LF	_____	_____	_____	_____
0310	530.31 GFRP, REINFORCEMENT BARS, PLACING	8,000.000 LF	_____	_____	_____	_____
0320	535.622 PRESTRESSED STRUCTURAL CONCRETE NEXT BEAM	LUMP SUM	LUMP	SUM	_____	_____
0330	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	262.500 LF	_____	_____	_____	_____
0340	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	75.000 LF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025529.00

Project(s): 025529.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	1.000 EA	_____	 _____	_____	 _____
0360	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	 _____	_____	 _____
0370	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	3.000 EA	_____	 _____	_____	 _____
0380	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	 _____	_____	 _____
0390	610.08 PLAIN RIPRAP	150.000 CY	_____	 _____	_____	 _____
0400	610.18 STONE DITCH PROTECTION	5.000 CY	_____	 _____	_____	 _____
0410	610.213 VOID FILLED RIPRAP	90.000 CY	_____	 _____	_____	 _____
0420	613.319 EROSION CONTROL BLANKET	86.000 SY	_____	 _____	_____	 _____
0430	615.07 LOAM	22.000 CY	_____	 _____	_____	 _____
0440	618.13 SEEDING METHOD NUMBER 1	1.000 UN	_____	 _____	_____	 _____
0450	618.14 SEEDING METHOD NUMBER 2	3.000 UN	_____	 _____	_____	 _____
0460	619.12 MULCH	4.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025529.00

Project(s): 025529.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	619.14 EROSION CONTROL MIX	43.000 CY	_____	 _____	_____	 _____
0480	620.58 EROSION CONTROL GEOTEXTILE	350.000 SY	_____	 _____	_____	 _____
0490	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,050.000 LF	_____	 _____	_____	 _____
0500	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	 _____	_____	 _____
0510	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0520	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0530	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	10.000 HR	_____	 _____	_____	 _____
0540	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0550	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0560	652.312 TYPE III BARRICADE	6.000 EA	_____	 _____	_____	 _____
0570	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____
0580	652.34 CONE	50.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025529.00

Project(s): 025529.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	652.35 CONSTRUCTION SIGNS	380.000 SF	_____	 _____	_____	 _____
0600	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
0610	652.38 FLAGGER	420.000 HR	_____	 _____	_____	 _____
0620	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0630	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
<b>Section: 1</b>			<b>Total:</b>		_____	 _____
			<b>Total Bid:</b>		_____	 _____