

2/12/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 8

Proposal ID: 026019.00

Project(s): 026019.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	7.000 EA	_____	_____	_____	_____
0020	201.24 REMOVING STUMP	7.000 EA	_____	_____	_____	_____
0030	203.20 COMMON EXCAVATION	6,458.000 CY	_____	_____	_____	_____
0040	203.21 ROCK EXCAVATION	325.000 CY	_____	_____	_____	_____
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	5,500.000 CY	_____	_____	_____	_____
0060	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	690.000 T	_____	_____	_____	_____
0070	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	170.000 T	_____	_____	_____	_____
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	1,980.000 T	_____	_____	_____	_____
0090	409.15 BITUMINOUS TACK COAT - APPLIED	610.000 G	_____	_____	_____	_____
0100	502.342 STRUCTURAL CONCRETE ROADWAY TRUCK APRON	120.000 CY	_____	_____	_____	_____
0110	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	325.000 LF	_____	_____	_____	_____
0120	603.179 18 INCH CULVERT PIPE OPTION III	50.000 LF	_____	_____	_____	_____

2/12/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 8

Proposal ID: 026019.00

Project(s): 026019.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	603.55 CONCRETE PIPE TIES	8,000 GP				
0140	604.092 CATCH BASIN TYPE B1-C	9,000 EA				
0150	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	125,000 LF				
0160	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	1,000 EA				
0170	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	2,000 EA				
0180	609.21 CONCRETE SLIPFORM CURB	2,950,000 LF				
0190	609.219 CONCRETE SLIPFORM CURB - TERMINAL END	32,000 LF				
0200	609.341 CURB TYPE 5 - TRUCK APRON	365,000 LF				
0210	610.08 PLAIN RIPRAP	43,000 CY				
0220	610.18 STONE DITCH PROTECTION	165,000 CY				
0230	613.319 EROSION CONTROL BLANKET	970,000 SY				
0240	615.07 LOAM	330,000 CY				

2/12/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 8

Proposal ID: 026019.00

Project(s): 026019.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	615.081 COMPOST BLANKET	395,000 CY				
0260	615.10 DIRTY BORROW	50,000 CY				
0270	618.13 SEEDING METHOD NUMBER 1	20,000 UN				
0280	618.14 SEEDING METHOD NUMBER 2	15,000 UN				
0290	619.12 MULCH	35,000 UN				
0300	619.13 BARK MULCH	10,000 CY				
0310	620.58 EROSION CONTROL GEOTEXTILE	86,000 SY				
0320	621.031 EVERGREEN TREES (4 FOOT - 5 FOOT) GROUP A	5,000 EA				
0330	621.037 EVERGREEN TREES (5 FOOT - 6 FOOT) GROUP A	5,000 EA				
0340	621.043 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP A	3,000 EA				
0350	621.046 EVERGREEN TR (8' - 10') GP A	1,000 EA				
0360	621.101 PLUG/ STARTER PLANT	1,250,000 EA				

2/12/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 8

Proposal ID: 026019.00

Project(s): 026019.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	621.396 EVERGREENS (18 INCH - 24 INCH) GROUP B	90,000 EA	_____	 _____	_____	 _____
0380	621.402 EVERGREENS (2 FOOT - 2.50 FOOT) GROUP B	24,000 EA	_____	 _____	_____	 _____
0390	621.408 EVERGREENS (2.50 FOOT - 3 FOOT) GROUP B	12,000 EA	_____	 _____	_____	 _____
0400	621.54 DECIDUOUS SHRUBS (18 INCH - 24 INCH) GROUP A	80,000 EA	_____	 _____	_____	 _____
0410	621.546 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP A	90,000 EA	_____	 _____	_____	 _____
0420	621.552 DECIDUOUS SHRUBS (3 FOOT - 4 FOOT) GROUP A	20,000 EA	_____	 _____	_____	 _____
0430	621.558 DECIDUOUS SHRUBS (4 FOOT - 5 FOOT) GROUP A	8,000 EA	_____	 _____	_____	 _____
0440	621.71 HERBACEOUS PERENNIALS GROUP A	650,000 EA	_____	 _____	_____	 _____
0450	621.80 ESTABLISHMENT PERIOD	LUMP SUM		LUMP SUM	_____	 _____
0460	626.11 PRECAST CONCRETE JUNCTION BOX	15,000 EA	_____	 _____	_____	 _____
0470	626.22 NON-METALLIC CONDUIT	1,630,000 LF	_____	 _____	_____	 _____

2/12/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 8

Proposal ID: 026019.00

Project(s): 026019.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0480	626.43 30 INCH DIAMETER FOUNDATION	101.000 LF	_____	 _____	_____	 _____
0490	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	5,350.000 LF	_____	 _____	_____	 _____
0500	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	80.000 SF	_____	 _____	_____	 _____
0510	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	5,350.000 LF	_____	 _____	_____	 _____
0520	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	 _____	_____	 _____
0530	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0540	631.133 SKID STEER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0550	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0560	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0570	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0580	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____

2/12/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 8

Proposal ID: 026019.00

Project(s): 026019.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0600	634.160 HIGHWAY LIGHTING	LUMP SUM	_____	 LUMP SUM	_____	 _____
0610	634.2042 LED LUMINARIES	12.000 EA	_____	 _____	_____	 _____
0620	634.210 CONVENTIONAL LIGHT STANDARD	12.000 EA	_____	 _____	_____	 _____
0630	634.25 SERVICE POLE COMPLETE WITH CABINET AND CONTROLS	1.000 EA	_____	 _____	_____	 _____
0640	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0650	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0660	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	11.000 EA	_____	 _____	_____	 _____
0670	645.108 DEMOUNT POLE	11.000 EA	_____	 _____	_____	 _____
0680	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	4.000 EA	_____	 _____	_____	 _____
0690	645.118 REINSTALL POLE	4.000 EA	_____	 _____	_____	 _____
0700	645.161 BREAKAWAY DEVICES SINGLE POLE	20.000 EA	_____	 _____	_____	 _____

2/12/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 8

Proposal ID: 026019.00

Project(s): 026019.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0710	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	265,000 SF	_____	_____	_____	_____
0720	645.301 DEMOUNTABLE REFLECTORIZED DELINEATOR, SINGLE	40,000 EA	_____	_____	_____	_____
0730	652.312 TYPE III BARRICADE	20,000 EA	_____	_____	_____	_____
0740	652.33 DRUM	50,000 EA	_____	_____	_____	_____
0750	652.34 CONE	90,000 EA	_____	_____	_____	_____
0760	652.35 CONSTRUCTION SIGNS	1,020,000 SF	_____	_____	_____	_____
0770	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	300,000 CD	_____	_____	_____	_____
0780	652.38 FLAGGER	1,920,000 HR	_____	_____	_____	_____
0790	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	12,000 EA	_____	_____	_____	_____
0800	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____
0810	658.20 ACRYLIC LATEX COLOR FINISH, GREEN GREEN	810,000 SY	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Page 8 of 8

Proposal ID: 026019.00

Project(s): 026019.00

SECTION: 1 **HIGHWAY ITEMS**

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0820	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM		
Section: 1			Total:			
			Total Bid:			