

4/9/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 5

Proposal ID: 026065.10

Project(s): 026065.10

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	1.000 EA	_____	_____	_____	_____
0020	201.24 REMOVING STUMP	1.000 EA	_____	_____	_____	_____
0030	202.203 PAVEMENT BUTT JOINTS	550.000 SY	_____	_____	_____	_____
0040	203.20 COMMON EXCAVATION	4,835.000 CY	_____	_____	_____	_____
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	3,375.000 CY	_____	_____	_____	_____
0060	308.36 FULL DEPTH RECYCLED PAVEMENT WITH CEMENT	24,150.000 SY	_____	_____	_____	_____
0070	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	140.000 T	_____	_____	_____	_____
0080	403.2104 HOT MIX ASPHALT 9.5 MM - THIN LIFT SURFACE TREATMENT	1,290.000 T	_____	_____	_____	_____
0090	403.211 HOT MIX ASPHALT (SHIMMING)	50.000 T	_____	_____	_____	_____
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	2,580.000 T	_____	_____	_____	_____
0110	409.15 BITUMINOUS TACK COAT - APPLIED	1,900.000 G	_____	_____	_____	_____
0120	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	50.000 CY	_____	_____	_____	_____

4/9/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 5

Proposal ID: 026065.10

Project(s): 026065.10

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	603.16 15 INCH CULVERT PIPE OPTION I STATE SUPPLIED	644.000 LF	_____	_____	_____	_____
0140	603.17 18 INCH CULVERT PIPE OPTION I STATE SUPPLIED	574.000 LF	_____	_____	_____	_____
0150	603.19 24 INCH CULVERT PIPE OPTION I STATE SUPPLIED	88.000 LF	_____	_____	_____	_____
0160	604.161 ALTERING CATCH BASIN	1.000 EA	_____	_____	_____	_____
0170	605.09 6 INCH UNDERDRAIN TYPE B	1,000.000 LF	_____	_____	_____	_____
0180	605.10 6 INCH UNDERDRAIN OUTLET	40.000 LF	_____	_____	_____	_____
0190	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	150.000 LF	_____	_____	_____	_____
0200	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	25.000 LF	_____	_____	_____	_____
0210	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	1.000 EA	_____	_____	_____	_____
0220	606.3511 SNOW POLE	2.000 EA	_____	_____	_____	_____
0230	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.000 EA	_____	_____	_____	_____

4/9/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 5

Proposal ID: 026065.10

Project(s): 026065.10

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	606.754 WIDEN SHOULDER FOR FLARED GUARDRAIL TERMINAL	1.000 EA	_____	_____	_____	_____
0250	608.45 CONSTRUCT SIDEWALK	330.000 SY	_____	_____	_____	_____
0260	609.38 RESET CURB TYPE 1	580.000 LF	_____	_____	_____	_____
0270	610.08 PLAIN RIPRAP	100.000 CY	_____	_____	_____	_____
0280	610.18 STONE DITCH PROTECTION	510.000 CY	_____	_____	_____	_____
0290	615.07 LOAM	440.000 CY	_____	_____	_____	_____
0300	615.10 DIRTY BORROW	520.000 CY	_____	_____	_____	_____
0310	618.13 SEEDING METHOD NUMBER 1	106.000 UN	_____	_____	_____	_____
0320	618.14 SEEDING METHOD NUMBER 2	106.000 UN	_____	_____	_____	_____
0330	619.12 MULCH	212.000 UN	_____	_____	_____	_____
0340	620.54 STABILIZATION/REINFORCEMENT GEOTEXTILE	500.000 SY	_____	_____	_____	_____
0350	620.58 EROSION CONTROL GEOTEXTILE	1,600.000 SY	_____	_____	_____	_____

4/9/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 5

Proposal ID: 026065.10

Project(s): 026065.10

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	21,030.000 LF	_____	_____	_____	_____
0370	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	42,060.000 LF	_____	_____	_____	_____
0380	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	_____	_____	_____
0390	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0400	631.11 AIR TOOL (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0410	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	100.000 HR	_____	_____	_____	_____
0420	631.13 BULLDOZER (INCLUDING OPERATOR)	40.000 HR	_____	_____	_____	_____
0430	631.14 GRADER (INCLUDING OPERATOR)	40.000 HR	_____	_____	_____	_____
0440	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	240.000 HR	_____	_____	_____	_____
0450	631.22 FRONT END LOADER (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0460	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____

4/9/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 5

Proposal ID: 026065.10

Project(s): 026065.10

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	652.33 DRUM	10.000 EA	_____	_____	_____	_____
0480	652.34 CONE	100.000 EA	_____	_____	_____	_____
0490	652.35 CONSTRUCTION SIGNS	660.000 SF	_____	_____	_____	_____
0500	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	60.000 CD	_____	_____	_____	_____
0510	652.38 FLAGGER	1,510.000 HR	_____	_____	_____	_____
0520	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____
0530	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____