

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 026083.00

Project(s): 026083.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0020	202.202 REMOVING PAVEMENT SURFACE	380.000 SY				
0030	203.20 COMMON EXCAVATION	2,060.000 CY				
0040	203.2318 DISPOSAL OF SPECIAL WASTE	330.000 T				
0050	203.25 GRANULAR BORROW	370.000 CY				
0060	203.33 SPECIAL FILL	110.000 CY				
0070	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	520.000 CY				
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	890.000 CY				
0090	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	150.000 T				
0100	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	14.000 T				
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	200.000 T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	65.000 G				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 026083.00

Project(s): 026083.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	501.231 DYNAMIC LOADING TEST	2.000 EA	_____	 _____	_____	 _____
0140	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	1,375.000 LF	_____	 _____	_____	 _____
0150	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	1,375.000 LF	_____	 _____	_____	 _____
0160	501.90 PILE TIPS	10.000 EA	_____	 _____	_____	 _____
0170	501.91 PILE SPLICES	30.000 EA	_____	 _____	_____	 _____
0180	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
0190	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM		LUMP SUM	_____	 _____
0200	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP SUM		LUMP SUM	_____	 _____
0210	502.291 SAW CUT GROOVING	LUMP SUM		LUMP SUM	_____	 _____
0220	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM		LUMP SUM	_____	 _____
0230	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM		LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 026083.00

Project(s): 026083.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	17,500.000 LB	_____	 _____	_____	 _____
0250	503.13 REINFORCING STEEL, PLACING	17,500.000 LB	_____	 _____	_____	 _____
0260	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	14,700.000 LB	_____	 _____	_____	 _____
0270	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	14,700.000 LB	_____	 _____	_____	 _____
0280	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM		 LUMP SUM	_____	 _____
0290	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA	_____	 _____	_____	 _____
0300	511.07 COFFERDAM: ABUT NO.1	LUMP SUM		 LUMP SUM	_____	 _____
0310	511.07 COFFERDAM: ABUT NO.2	LUMP SUM		 LUMP SUM	_____	 _____
0320	512.081 FRENCH DRAINS	LUMP SUM		 LUMP SUM	_____	 _____
0330	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM		 LUMP SUM	_____	 _____
0340	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM		 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 026083.00

Project(s): 026083.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	16,300.000 LF	_____	 _____	_____	 _____
0360	530.31 GFRP, REINFORCEMENT BARS, PLACING	16,300.000 LF	_____	 _____	_____	 _____
0370	535.622 PRESTRESSED STRUCTURAL CONCRETE NEXT BEAM	LUMP SUM		LUMP SUM	_____	 _____
0380	603.199 24 INCH CULVERT PIPE OPTION III	56.000 LF	_____	 _____	_____	 _____
0390	603.209 30 INCH CULVERT PIPE OPTION III	56.000 LF	_____	 _____	_____	 _____
0400	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	240.000 LF	_____	 _____	_____	 _____
0410	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	88.000 LF	_____	 _____	_____	 _____
0420	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	2.000 EA	_____	 _____	_____	 _____
0430	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	 _____	_____	 _____
0440	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA	_____	 _____	_____	 _____
0450	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	7.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 026083.00

Project(s): 026083.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	606.47 SINGLE WOOD POST	1.000 EA	_____	 _____	_____	 _____
0470	610.08 PLAIN RIPRAP	750.000 CY	_____	 _____	_____	 _____
0480	610.18 STONE DITCH PROTECTION	10.000 CY	_____	 _____	_____	 _____
0490	613.319 EROSION CONTROL BLANKET	340.000 SY	_____	 _____	_____	 _____
0500	615.07 LOAM	65.000 CY	_____	 _____	_____	 _____
0510	618.13 SEEDING METHOD NUMBER 1	3.000 UN	_____	 _____	_____	 _____
0520	618.14 SEEDING METHOD NUMBER 2	5.000 UN	_____	 _____	_____	 _____
0530	619.12 MULCH	8.000 UN	_____	 _____	_____	 _____
0540	619.14 EROSION CONTROL MIX	130.000 CY	_____	 _____	_____	 _____
0550	620.58 EROSION CONTROL GEOTEXTILE	640.000 SY	_____	 _____	_____	 _____
0560	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,170.000 LF	_____	 _____	_____	 _____
0570	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	 _____	_____	 _____
0580	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 026083.00

Project(s): 026083.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	631.14 GRADER (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0600	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	40.000 HR	_____	 _____	_____	 _____
0610	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0620	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0630	652.312 TYPE III BARRICADE	6.000 EA	_____	 _____	_____	 _____
0640	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____
0650	652.34 CONE	25.000 EA	_____	 _____	_____	 _____
0660	652.35 CONSTRUCTION SIGNS	350.000 SF	_____	 _____	_____	 _____
0670	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		 LUMP SUM	_____	 _____
0680	652.38 FLAGGER	600.000 HR	_____	 _____	_____	 _____
0690	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0700	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 026083.00

Project(s): 026083.00

Section: 1

Total:

\_\_\_\_\_!

Total Bid:

\_\_\_\_\_!