

7/27/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 6

Proposal ID: 026089.00

Project(s): 026089.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0020	202.202 REMOVING PAVEMENT SURFACE	350.000 SY				
0030	203.20 COMMON EXCAVATION	690.000 CY				
0040	203.21 ROCK EXCAVATION	67.000 CY				
0050	203.24 COMMON BORROW	50.000 CY				
0060	203.25 GRANULAR BORROW	270.000 CY				
0070	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	350.000 CY				
0080	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	100.000 CY				
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	740.000 CY				
0100	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	129.000 T				
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	167.000 T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	75.000 G				

7/27/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 6

Proposal ID: 026089.00

Project(s): 026089.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	461.131 TEMPORARY PAVEMENT	120.000 T				
0140	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM		LUMP SUM		
0150	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED UNDER WATER)	199.000 CY				
0160	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	7,500.000 LB				
0170	503.13 REINFORCING STEEL, PLACING	7,500.000 LB				
0180	504.906 ROCK DOWEL	LUMP SUM		LUMP SUM		
0190	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM		LUMP SUM		
0200	510.10 SPECIAL DETOUR, VEHICULAR AND PEDESTRIAN TRAFFIC NOT SEPARATED 14FT	LUMP SUM		LUMP SUM		
0210	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM		LUMP SUM		
0220	511.07 COFFERDAM: UPSTREAM	LUMP SUM		LUMP SUM		
0230	512.081 FRENCH DRAINS	LUMP SUM		LUMP SUM		

7/27/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 6

Proposal ID: 026089.00

Project(s): 026089.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	513.50 ROCK BLOCK TOE BUTTRESS STABILIZATION	LUMP SUM	LUMP	SUM	_____	_____
0250	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0260	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0270	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	_____	_____	_____
0280	534.70 PRECAST STRUCTURAL CONCRETE ARCH	LUMP SUM	LUMP	SUM	_____	_____
0290	603.16 15 INCH CULVERT PIPE OPTION I	40.000 LF	_____	_____	_____	_____
0300	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	319.000 LF	_____	_____	_____	_____
0310	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	50.000 LF	_____	_____	_____	_____
0320	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	1.000 EA	_____	_____	_____	_____
0330	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	1.000 EA	_____	_____	_____	_____
0340	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA	_____	_____	_____	_____

7/27/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 6

Proposal ID: 026089.00

Project(s): 026089.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	 _____	_____	 _____
0360	610.08 PLAIN RIPRAP	251.000 CY	_____	 _____	_____	 _____
0370	610.213 VOID FILLED RIPRAP	92.000 CY	_____	 _____	_____	 _____
0380	613.319 EROSION CONTROL BLANKET	110.000 SY	_____	 _____	_____	 _____
0390	615.07 LOAM	33.000 CY	_____	 _____	_____	 _____
0400	618.14 SEEDING METHOD NUMBER 2	6.000 UN	_____	 _____	_____	 _____
0410	619.12 MULCH	6.000 UN	_____	 _____	_____	 _____
0420	619.14 EROSION CONTROL MIX	65.000 CY	_____	 _____	_____	 _____
0430	620.58 EROSION CONTROL GEOTEXTILE	564.000 SY	_____	 _____	_____	 _____
0440	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,350.000 LF	_____	 _____	_____	 _____
0450	627.77 REMOVING PAVEMENT MARKINGS	300.000 SF	_____	 _____	_____	 _____
0460	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	900.000 LF	_____	 _____	_____	 _____

7/27/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 6

Proposal ID: 026089.00

Project(s): 026089.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0480	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0490	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR				
0500	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	10.000 HR				
0510	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR				
0520	639.19 FIELD OFFICE TYPE B	1.000 EA				
0530	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM				
0540	652.312 TYPE III BARRICADE	4.000 EA				
0550	652.33 DRUM	25.000 EA				
0560	652.34 CONE	50.000 EA				
0570	652.35 CONSTRUCTION SIGNS	400.000 SF				
0580	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM				

7/27/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 6

Proposal ID: 026089.00

Project(s): 026089.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	652.38 FLAGGER	400.000 HR				
0600	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM				
0610	659.10 MOBILIZATION	LUMP SUM				
Section: 1			Total:			
			Total Bid:			