

6/4/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 3

Proposal ID: 026288.00

Project(s): 026288.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.11 CLEARING	1.000 AC				
0020	203.20 COMMON EXCAVATION	8,550.000 CY				
0030	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	5,920.000 CY				
0040	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	910.000 T				
0050	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	80.000 T				
0060	403.213 HOT MIX ASPHALT 12.5 MM BASE	890.000 T				
0070	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	1,035.000 T				
0080	409.15 BITUMINOUS TACK COAT - APPLIED	630.000 G				
0090	502.341 STRUCTURAL CONCRETE ROADWAY MEDIAN	25.000 CY				
0100	603.17 18 INCH CULVERT PIPE OPTION I	118.000 LF				
0110	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	176.000 LF				
0120	603.55 CONCRETE PIPE TIES	10.000 GP				

6/4/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 3

Proposal ID: 026288.00

Project(s): 026288.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	604.092 CATCH BASIN TYPE B1-C	2.000 EA				
0140	605.09 6 INCH UNDERDRAIN TYPE B	846.000 LF				
0150	609.34 CURB TYPE 5	820.000 LF				
0160	609.35 CURB TYPE 5 - CIRCULAR	36.000 LF				
0170	610.08 PLAIN RIPRAP	20.000 CY				
0180	613.319 EROSION CONTROL BLANKET	1,775.000 SY				
0190	615.07 LOAM	460.000 CY				
0200	618.14 SEEDING METHOD NUMBER 2	74.000 UN				
0210	619.12 MULCH	74.000 UN				
0220	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	5,610.000 LF				
0230	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	96.000 SF				
0240	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	16,820.000 LF				

6/4/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 3

Proposal ID: 026288.00

Project(s): 026288.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0260	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0270	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0280	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0290	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	195.000 SF	_____	 _____	_____	 _____
0300	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____
0310	652.34 CONE	50.000 EA	_____	 _____	_____	 _____
0320	652.35 CONSTRUCTION SIGNS	320.000 SF	_____	 _____	_____	 _____
0330	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	60.000 CD	_____	 _____	_____	 _____
0340	652.38 FLAGGER	2,000.000 HR	_____	 _____	_____	 _____
0350	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0360	659.10 MOBILIZATION	LUMP SUM	_____	 LUMP SUM	_____	 _____

Section: 1

Total:

Total Bid:
