

1/6/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 6

Proposal ID: 026574.00

Project(s): 026574.00

SECTION: 1 MAIN ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0020	203.20 COMMON EXCAVATION	560.000 CY				
0030	203.25 GRANULAR BORROW	460.000 CY				
0040	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	630.000 CY				
0050	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	37.000 CY				
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	650.000 CY				
0070	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	120.000 T				
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	200.000 T				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	43.000 G				
0100	461.131 TEMPORARY PAVEMENT	81.000 T				
0110	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	100.000 CY				

1/6/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 6

Proposal ID: 026574.00

Project(s): 026574.00

SECTION: 1 MAIN ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED UNDER WATER)	95.000 CY	_____	_____	_____	_____
0130	502.291 SAW CUT GROOVING	LUMP SUM	LUMP SUM	_____	_____	_____
0140	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP SUM	_____	_____	_____
0150	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	11,500.000 LB	_____	_____	_____	_____
0160	503.13 REINFORCING STEEL, PLACING	11,500.000 LB	_____	_____	_____	_____
0170	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP SUM	_____	_____	_____
0180	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA	_____	_____	_____	_____
0190	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 14 FEET	LUMP SUM	LUMP SUM	_____	_____	_____
0200	511.07 COFFERDAM: ABUT. NO. 1	LUMP SUM	LUMP SUM	_____	_____	_____
0210	511.07 COFFERDAM: ABUT. NO. 2	LUMP SUM	LUMP SUM	_____	_____	_____
0220	512.081 FRENCH DRAINS	LUMP SUM	LUMP SUM	_____	_____	_____

1/6/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 6

Proposal ID: 026574.00

Project(s): 026574.00

SECTION: 1 MAIN ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0240	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP SUM	LUMP	SUM	_____	_____
0250	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	_____	_____	_____
0260	531.511 BRIDGE SUPERSTRUCTURE - DETAIL BUILD PBFTG ALTERNATIVE	LUMP SUM	LUMP	SUM	_____	_____
0270	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	1.000 EA	_____	_____	_____	_____
0280	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	50.000 LF	_____	_____	_____	_____
0290	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	2.000 EA	_____	_____	_____	_____
0300	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	2.000 EA	_____	_____	_____	_____
0310	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	_____	_____	_____
0320	608.07 PLAIN CONCRETE SIDEWALK	140.000 SY	_____	_____	_____	_____
0330	609.11 VERTICAL CURB TYPE 1	80.000 LF	_____	_____	_____	_____
0340	609.238 TERMINAL CURB TYPE 1 - 8 FOOT	2.000 EA	_____	_____	_____	_____

1/6/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 6

Proposal ID: 026574.00

Project(s): 026574.00

SECTION: 1 MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	610.213 VOID FILLED RIPRAP	200.000 CY				
0360	613.319 EROSION CONTROL BLANKET	34.000 SY				
0370	615.07 LOAM	32.000 CY				
0380	618.14 SEEDING METHOD NUMBER 2	6.000 UN				
0390	619.12 MULCH	6.000 UN				
0400	619.14 EROSION CONTROL MIX	64.000 CY				
0410	620.58 EROSION CONTROL GEOTEXTILE	200.000 SY				
0420	627.18 12 " SOLID WHITE PAVEMENT MARKING	32.000 LF				
0430	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	450.000 LF				
0440	627.77 REMOVING PAVEMENT MARKINGS	32.000 SF				
0450	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	780.000 LF				
0460	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				

1/6/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 6

Proposal ID: 026574.00

Project(s): 026574.00

SECTION: 1 MAIN ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0480	631.131 SMALL BULLDOZER-GRADER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0490	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0500	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM		_____	 _____
0510	645.103 DEMOUNT GUIDE SIGN	2.000 EA	_____	 _____	_____	 _____
0520	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	6.000 EA	_____	 _____	_____	 _____
0530	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	3.000 EA	_____	 _____	_____	 _____
0540	645.251 ROADSIDE GUIDE SIGNS, TYPE I	8.000 SF	_____	 _____	_____	 _____
0550	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	4.000 SF	_____	 _____	_____	 _____
0560	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0570	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____

1/6/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 6

Proposal ID: 026574.00

Project(s): 026574.00

SECTION: 1 MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	652.34 CONE	25.000 EA	_____	 _____	_____	 _____
0590	652.35 CONSTRUCTION SIGNS	60.000 SF	_____	 _____	_____	 _____
0600	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
0610	652.38 FLAGGER	360.000 HR	_____	 _____	_____	 _____
0620	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	 _____	_____	 _____
0630	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0640	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____