

8/20/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 7

Proposal ID: 026630.08

Project(s): 026630.08

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0020	202.202 REMOVING PAVEMENT SURFACE	390.000 SY				
0030	203.20 COMMON EXCAVATION	7,700.000 CY				
0040	203.21 ROCK EXCAVATION	160.000 CY				
0050	203.25 GRANULAR BORROW	450.000 CY				
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	430.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1,600.000 CY				
0080	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	205.000 T				
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	5.000 T				
0100	403.211 HOT MIX ASPHALT (SHIMMING)	5.000 T				
0110	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	485.000 T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	205.000 G				

8/20/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 7

Proposal ID: 026630.08

Project(s): 026630.08

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	461.131 TEMPORARY PAVEMENT	350.000 T	_____	_____	_____	_____
0140	501.502 ROCK SOCKETED H-PILES	270.000 LF	_____	_____	_____	_____
0150	501.54 STEEL H-BEAM PILES 117 LBS/FT, DELIVERED	270.000 LF	_____	_____	_____	_____
0160	501.804 DRILLING EQUIPMENT MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0170	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP SUM	_____	_____	_____
0180	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP SUM	LUMP SUM	_____	_____	_____
0190	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP SUM	_____	_____	_____
0200	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP SUM	_____	_____	_____
0210	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	8,000.000 LB	_____	_____	_____	_____
0220	503.13 REINFORCING STEEL, PLACING	8,000.000 LB	_____	_____	_____	_____
0230	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	13,800.000 LB	_____	_____	_____	_____

8/20/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 7

Proposal ID: 026630.08

Project(s): 026630.08

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	13,800.000 LB	_____	 _____	_____	 _____
0250	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP SUM	 _____	_____	 _____
0260	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA	_____	 _____	_____	 _____
0270	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP SUM	 _____	_____	 _____
0280	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED	LUMP SUM	LUMP SUM	 _____	_____	 _____
0290	511.07 COFFERDAM: WILSON STREAM	LUMP SUM	LUMP SUM	 _____	_____	 _____
0300	512.081 FRENCH DRAINS	LUMP SUM	LUMP SUM	 _____	_____	 _____
0310	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP SUM	 _____	_____	 _____
0320	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	10.000 EA	_____	 _____	_____	 _____
0330	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP SUM	 _____	_____	 _____
0340	527.34 WORK ZONE CRASH CUSHIONS	10.000 UN	_____	 _____	_____	 _____

8/20/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 7

Proposal ID: 026630.08

Project(s): 026630.08

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	22,000.000 LF	_____	_____	_____	_____
0360	530.31 GFRP, REINFORCEMENT BARS, PLACING	22,000.000 LF	_____	_____	_____	_____
0370	535.61 PRESTRESSED STRUCTURAL CONCRETE I-GIRDERS	LUMP SUM	LUMP SUM		_____	_____
0380	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	225.000 LF	_____	_____	_____	_____
0390	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	26.000 LF	_____	_____	_____	_____
0400	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	3.000 EA	_____	_____	_____	_____
0410	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	_____	_____	_____
0420	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____
0430	610.08 PLAIN RIPRAP	22.000 CY	_____	_____	_____	_____
0440	610.16 HEAVY RIPRAP	1,900.000 CY	_____	_____	_____	_____
0450	610.18 STONE DITCH PROTECTION	8.000 CY	_____	_____	_____	_____
0460	613.319 EROSION CONTROL BLANKET	40.000 SY	_____	_____	_____	_____

8/20/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 7

Proposal ID: 026630.08

Project(s): 026630.08

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	615.07 LOAM	200.000 CY	_____	_____	_____	_____
0480	618.14 SEEDING METHOD NUMBER 2	13.000 UN	_____	_____	_____	_____
0490	619.12 MULCH	13.000 UN	_____	_____	_____	_____
0500	619.14 EROSION CONTROL MIX	20.000 CY	_____	_____	_____	_____
0510	620.58 EROSION CONTROL GEOTEXTILE	1,600.000 SY	_____	_____	_____	_____
0520	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2,400.000 LF	_____	_____	_____	_____
0530	627.77 REMOVING PAVEMENT MARKINGS	100.000 SF	_____	_____	_____	_____
0540	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	100.000 LF	_____	_____	_____	_____
0550	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	_____	_____	_____
0560	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0570	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0580	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____

8/20/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 7

Proposal ID: 026630.08

Project(s): 026630.08

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0600	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0610	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0620	631.22 FRONT END LOADER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0630	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0640	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0650	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM		_____	 _____
0660	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	36.000 SF	_____	 _____	_____	 _____
0670	652.312 TYPE III BARRICADE	10.000 EA	_____	 _____	_____	 _____
0680	652.33 DRUM	50.000 EA	_____	 _____	_____	 _____
0690	652.34 CONE	25.000 EA	_____	 _____	_____	 _____

8/20/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 7

Proposal ID: 026630.08

Project(s): 026630.08

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0700	652.35 CONSTRUCTION SIGNS	300.000 SF	_____	_____	_____	_____
0710	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM	_____	_____	_____
0720	652.38 FLAGGER	600.000 HR	_____	_____	_____	_____
0730	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	_____	_____	_____
0740	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM	_____	_____	_____
0750	659.10 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
Section: 1			Total:	_____	_____	_____
			Total Bid:	_____	_____	_____