

8/25/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 4

Proposal ID: 026630.10

Project(s): 026630.10

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	2,930.000 CY	_____	_____	_____	_____
0020	203.25 GRANULAR BORROW	810.000 CY	_____	_____	_____	_____
0030	203.33 SPECIAL FILL	380.000 CY	_____	_____	_____	_____
0040	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	100.000 CY	_____	_____	_____	_____
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1,640.000 CY	_____	_____	_____	_____
0060	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	190.000 T	_____	_____	_____	_____
0070	403.213 HOT MIX ASPHALT 12.5 MM BASE	450.000 T	_____	_____	_____	_____
0080	409.15 BITUMINOUS TACK COAT - APPLIED	40.000 G	_____	_____	_____	_____
0090	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0100	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0110	511.07 COFFERDAM: UPSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0120	534.71 PRECAST CONCRETE BOX CULVERT	LUMP SUM	LUMP	SUM	_____	_____

8/25/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 4

Proposal ID: 026630.10

Project(s): 026630.10

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	1.000 EA	_____	 _____	_____	 _____
0140	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	1.000 EA	_____	 _____	_____	 _____
0150	606.365 GUARDRAIL REMOVE, MODIFY, AND RESET	750.000 LF	_____	 _____	_____	 _____
0160	610.08 PLAIN RIPRAP	20.000 CY	_____	 _____	_____	 _____
0170	610.212 STREAMBED ROCK FEATURES	30.000 CY	_____	 _____	_____	 _____
0180	610.213 VOID FILLED RIPRAP	60.000 CY	_____	 _____	_____	 _____
0190	615.10 DIRTY BORROW	110.000 CY	_____	 _____	_____	 _____
0200	618.14 SEEDING METHOD NUMBER 2	11.000 UN	_____	 _____	_____	 _____
0210	619.12 MULCH	11.000 UN	_____	 _____	_____	 _____
0220	620.58 EROSION CONTROL GEOTEXTILE	110.000 SY	_____	 _____	_____	 _____
0230	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,200.000 LF	_____	 _____	_____	 _____
0240	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	 _____	_____	 _____

8/25/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 4

Proposal ID: 026630.10

Project(s): 026630.10

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR	_____	_____	_____	_____
0260	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR	_____	_____	_____	_____
0270	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0280	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____
0290	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM		_____	_____
0300	652.312 TYPE III BARRICADE	6.000 EA	_____	_____	_____	_____
0310	652.33 DRUM	30.000 EA	_____	_____	_____	_____
0320	652.34 CONE	100.000 EA	_____	_____	_____	_____
0330	652.35 CONSTRUCTION SIGNS	260.000 SF	_____	_____	_____	_____
0340	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	30.000 CD	_____	_____	_____	_____
0350	652.38 FLAGGER	250.000 HR	_____	_____	_____	_____
0360	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	_____	_____	_____

8/25/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 4

Proposal ID: 026630.10

Project(s): 026630.10

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	652.61 STAGED CONSTRUCTION AND TRAFFIC CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0380	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0390	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____