

8/25/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 4

Proposal ID: 026630.11

Project(s): 026630.11, 026630.12

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	1,520.000 CY	_____	_____	_____	_____
0020	203.25 GRANULAR BORROW	490.000 CY	_____	_____	_____	_____
0030	203.33 SPECIAL FILL	250.000 CY	_____	_____	_____	_____
0040	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1,470.000 CY	_____	_____	_____	_____
0050	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	160.000 T	_____	_____	_____	_____
0060	403.213 HOT MIX ASPHALT 12.5 MM BASE	430.000 T	_____	_____	_____	_____
0070	409.15 BITUMINOUS TACK COAT - APPLIED	40.000 G	_____	_____	_____	_____
0080	508.13 SHEET WATERPROOFING MEMBRANE WIN 026630.11	LUMP SUM	LUMP	SUM	_____	_____
0090	508.13 SHEET WATERPROOFING MEMBRANE WIN 026630.12	LUMP SUM	LUMP	SUM	_____	_____
0100	511.07 COFFERDAM: DOWNSTREAM - WIN 026630.11	LUMP SUM	LUMP	SUM	_____	_____
0110	511.07 COFFERDAM: DOWNSTREAM - WIN 026630.12	LUMP SUM	LUMP	SUM	_____	_____
0120	511.07 COFFERDAM: UPSTREAM - WIN 026630.11	LUMP SUM	LUMP	SUM	_____	_____

8/25/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 4

Proposal ID: 026630.11

Project(s): 026630.11, 026630.12

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	511.07 COFFERDAM: UPSTREAM - WIN 026630.12	LUMP SUM	LUMP	SUM	_____	_____
0140	534.71 PRECAST CONCRETE BOX CULVERT WIN 026630.11	LUMP SUM	LUMP	SUM	_____	_____
0150	534.71 PRECAST CONCRETE BOX CULVERT WIN 026630.12	LUMP SUM	LUMP	SUM	_____	_____
0160	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	90.000 LF	_____	_____	_____	_____
0170	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	2.000 EA	_____	_____	_____	_____
0180	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	2.000 EA	_____	_____	_____	_____
0190	610.08 PLAIN RIPRAP	50.000 CY	_____	_____	_____	_____
0200	610.212 STREAMBED ROCK FEATURES	60.000 CY	_____	_____	_____	_____
0210	610.213 VOID FILLED RIPRAP	110.000 CY	_____	_____	_____	_____
0220	615.10 DIRTY BORROW	110.000 CY	_____	_____	_____	_____
0230	618.14 SEEDING METHOD NUMBER 2	11.000 UN	_____	_____	_____	_____
0240	619.12 MULCH	11.000 UN	_____	_____	_____	_____

8/25/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 4

Proposal ID: 026630.11

Project(s): 026630.11, 026630.12

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	620.58 EROSION CONTROL GEOTEXTILE	210.000 SY				
0260	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,350.000 LF				
0270	629.05 HAND LABOR, STRAIGHT TIME	80.000 HR				
0280	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	80.000 HR				
0290	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	80.000 HR				
0300	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	20.000 HR				
0310	639.19 FIELD OFFICE TYPE B	1.000 EA				
0320	643.72 TEMPORARY TRAFFIC SIGNAL WIN 026630.12	LUMP SUM				
0330	643.72 TEMPORARY TRAFFIC SIGNAL WIN 026630.11	LUMP SUM				
0340	652.312 TYPE III BARRICADE	12.000 EA				
0350	652.33 DRUM	60.000 EA				
0360	652.34 CONE	200.000 EA				

8/25/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 4

Proposal ID: 026630.11

Project(s): 026630.11, 026630.12

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	652.35 CONSTRUCTION SIGNS	520.000 SF	_____	_____	_____	_____
0380	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	60.000 CD	_____	_____	_____	_____
0390	652.38 FLAGGER	500.000 HR	_____	_____	_____	_____
0400	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA	_____	_____	_____	_____
0410	652.61 STAGED CONSTRUCTION AND TRAFFIC CONTROL WIN 026630.11	LUMP SUM	LUMP	SUM	_____	_____
0420	652.61 STAGED CONSTRUCTION AND TRAFFIC CONTROL WIN 026630.12	LUMP SUM	LUMP	SUM	_____	_____
0430	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0440	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____