

12/3/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 11

Proposal ID: 026824.00

Project(s): 026824.00

SECTION: 1 MAIN PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	6.000 EA	_____	_____	_____	_____
0020	202.1221 REMOVE ABANDONED CONCRETE FOUNDATION	LUMP SUM	LUMP SUM	_____	_____	_____
0030	203.20 COMMON EXCAVATION	6,391.000 CY	_____	_____	_____	_____
0040	304.10 AGGREGATE SUBBASE COURSE - GRAVEL (PAVED AND STONE-SLOPE PROTECTION AREAS)	2,778.000 CY	_____	_____	_____	_____
0050	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	363.000 T	_____	_____	_____	_____
0060	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	25.000 T	_____	_____	_____	_____
0070	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	545.000 T	_____	_____	_____	_____
0080	409.15 BITUMINOUS TACK COAT - APPLIED	250.000 G	_____	_____	_____	_____
0090	411.09 UNTREATED AGGREGATE SURFACE COURSE (RUBBLE MOUND & BOAT RAMP)	1,010.000 CY	_____	_____	_____	_____
0100	419.30 SAW CUTTING BITUMINOUS PAVEMENT	100.000 LF	_____	_____	_____	_____
0110	501.235 ACOUSTIC MONITOR	365.000 CD	_____	_____	_____	_____

12/3/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 11

Proposal ID: 026824.00

Project(s): 026824.00

SECTION: 1 MAIN PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	501.236 PROTECTED SPECIES OBSERVER	5,840.000 HOUR	_____	 _____	_____	 _____
0130	501.303 STEEL SHEET PILING - DELIVERED	11,562.000 SF	_____	 _____	_____	 _____
0140	501.304 STEEL SHEET PILING - IN PLACE	11,562.000 SF	_____	 _____	_____	 _____
0150	501.543 STEEL H-BEAM SECTIONS, DELIVERED (HP16X141) (163,560 LBS)	1,160.000 LF	_____	 _____	_____	 _____
0160	501.544 STEEL H-BEAM SECTIONS, IN PLACE (HP16X141) (163,560 LBS)	LUMP SUM	LUMP SUM		_____	 _____
0170	501.545 STEEL W-BEAM SECTIONS, DELIVERED (W10X100) (42,000 LBS)	420.000 LF	_____	 _____	_____	 _____
0180	501.545 STEEL W-BEAM SECTIONS, DELIVERED (W18X311) (223,920 LBS)	720.000 LF	_____	 _____	_____	 _____
0190	501.545 STEEL W-BEAM SECTIONS, DELIVERED (W21X201) (281,400 LBS)	1,400.000 LF	_____	 _____	_____	 _____
0200	501.546 STEEL W-BEAM SECTIONS, IN PLACE (W10X100) (42,000 LBS)	LUMP SUM	LUMP SUM		_____	 _____
0210	501.546 STEEL W-BEAM SECTIONS, IN PLACE (W18X311) (223,920 LBS)	LUMP SUM	LUMP SUM		_____	 _____
0220	501.546 STEEL W-BEAM SECTIONS, IN PLACE (W21X201) (281,400 LBS)	LUMP SUM	LUMP SUM		_____	 _____

12/3/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 11

Proposal ID: 026824.00

Project(s): 026824.00

SECTION: 1 MAIN PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	501.70 STEEL PIPE PILES, DELIVERED (12" DIAMETER X 1/2" WT)	780.000 LF	_____	_____	_____	_____
0240	501.70 STEEL PIPE PILES, DELIVERED (24" DIAMETER X 1/2" WT)	1,540.000 LF	_____	_____	_____	_____
0250	501.70 STEEL PIPE PILES, DELIVERED (36" DIAMETER X 1" WT)	5,067.000 LF	_____	_____	_____	_____
0260	501.701 STEEL PIPE PILES, IN PLACE (12" DIAMETER X 1/2" WT)	780.000 LF	_____	_____	_____	_____
0270	501.701 STEEL PIPE PILES, IN PLACE (24" DIAMETER X 1/2" WT)	1,540.000 LF	_____	_____	_____	_____
0280	501.701 STEEL PIPE PILES, IN PLACE (36" DIAMETER X 1" WT)	5,067.000 LF	_____	_____	_____	_____
0290	501.72 STEEL CASINGS, DELIVERED (18" DIAMETER)	624.000 LF	_____	_____	_____	_____
0300	501.72 STEEL CASINGS, DELIVERED (30" DIAMETER)	878.000 LF	_____	_____	_____	_____
0310	501.72 STEEL CASINGS, DELIVERED (42" DIAMETER)	833.000 LF	_____	_____	_____	_____
0320	501.721 STEEL CASINGS, IN PLACE (18" DIAMETER)	624.000 LF	_____	_____	_____	_____
0330	501.721 STEEL CASINGS, IN PLACE (30" DIAMETER)	878.000 LF	_____	_____	_____	_____

12/3/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 11

Proposal ID: 026824.00

Project(s): 026824.00

SECTION: 1 MAIN PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	501.721 STEEL CASINGS, IN PLACE (42" DIAMETER)	833.000 LF	_____	 _____	_____	 _____
0350	501.802 ROCK SOCKET (15" DIAMETER)	36.000 LF	_____	 _____	_____	 _____
0360	501.802 ROCK SOCKET (18" DIAMETER)	220.000 LF	_____	 _____	_____	 _____
0370	501.802 ROCK SOCKET (30" DIAMETER)	1,600.000 LF	_____	 _____	_____	 _____
0380	501.804 DRILLING EQUIPMENT MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
0390	501.90 PILE TIPS (STEEL PILES)	115.000 EA	_____	 _____	_____	 _____
0400	501.91 PILE SPLICES	5.000 EA	_____	 _____	_____	 _____
0410	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
0420	502.2351 STRUCTURAL CONCRETE, PILE CAP	79.000 CY	_____	 _____	_____	 _____
0430	502.2354 STRUCTURAL CONCRETE, PILE FILL	1,172.000 CY	_____	 _____	_____	 _____
0440	502.263 STRUCTURAL CONCRETE ROADWAY AND END POSTS ON STEEL BRIDGES	LUMP SUM	LUMP SUM		_____	 _____
0450	502.264 STRUCTURAL CONCRETE PARAPETS	LUMP SUM	LUMP SUM		_____	 _____

12/3/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 11

Proposal ID: 026824.00

Project(s): 026824.00

SECTION: 1 MAIN PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	502.411 STRUCTURAL CONCRETE, PIER DECK SLAB	469.000 CY	_____	_____	_____	_____
0470	502.45 STRUCTURAL CONCRETE APPROACH SLABS (BOAT RAMP TRANSITION)	20.000 CY	_____	_____	_____	_____
0480	503.14 EPOXY-COATED REINFORCING STEEL, FABRICATED AND DELIVERED	633,000.000 LB	_____	_____	_____	_____
0490	503.15 EPOXY-COATED REINFORCING STEEL, PLACING	633,000.000 LB	_____	_____	_____	_____
0500	504.510 MISC. FABRICATION	LUMP SUM	LUMP	SUM	_____	_____
0510	504.60 TIMBER FENDER SYSTEM	LUMP SUM	LUMP	SUM	_____	_____
0520	504.70 STRUCTURAL STEEL FABRICATED AND DELIVERED (W24X117)	LUMP SUM	LUMP	SUM	_____	_____
0530	504.71 STRUCTURAL STEEL ERECTION (W24X117)	LUMP SUM	LUMP	SUM	_____	_____
0540	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	SUM	_____	_____
0550	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	6,370.000 SY	_____	_____	_____	_____
0560	531.90 HOIST (2 TON CAPACITY)	2.000 EA	_____	_____	_____	_____

12/3/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 11

Proposal ID: 026824.00

Project(s): 026824.00

SECTION: 1 MAIN PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0570	531.91 FLOAT (TIMBER, CONCRETE OR STEEL)	12,100.000 SF	_____	 _____	_____	 _____
0580	531.9601 ALUMINUM GANGWAY - 80 LF	1.000 EA	_____	 _____	_____	 _____
0590	534.76022 PRECAST PIER, CAP	LUMP SUM	LUMP SUM		_____	 _____
0600	535.60 PRESTRESSED STRUCTURAL CONCRETE SLAB	LUMP SUM	LUMP SUM		_____	 _____
0610	606.15 GUARDRAIL TYPE 3A - SINGLE RAIL	360.000 LF	_____	 _____	_____	 _____
0620	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	4.000 EA	_____	 _____	_____	 _____
0630	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	 _____	_____	 _____
0640	607.163 CHAIN LINK FENCE - 4 FOOT P.V.C. COATED	400.000 LF	_____	 _____	_____	 _____
0650	607.35 BRACING ASSEMBLY CHAIN LINK FENCE PVC COATED	5.000 EA	_____	 _____	_____	 _____
0660	609.21 CONCRETE SLIPFORM CURB	26.000 LF	_____	 _____	_____	 _____
0670	609.219 CONCRETE SLIPFORM CURB - TERMINAL END	60.000 LF	_____	 _____	_____	 _____
0680	610.08 PLAIN RIPRAP	68,695.000 CY	_____	 _____	_____	 _____

12/3/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 11

Proposal ID: 026824.00

Project(s): 026824.00

SECTION: 1 MAIN PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0690	610.16 HEAVY RIPRAP	16,354.000 CY				
0700	610.17 ARMOR STONE	13,855.000 T				
0710	610.18 STONE DITCH PROTECTION	7,720.000 CY				
0720	610.45 LEVEL LIP SPREADER	LUMP SUM				
0730	615.07 LOAM	137.000 CY				
0740	615.27 UNDERDRAIN SOIL FILTER	LUMP SUM				
0750	618.13 SEEDING METHOD NUMBER 1	1.000 UN				
0760	618.14 SEEDING METHOD NUMBER 2	3.000 UN				
0770	619.12 MULCH	4.000 UN				
0780	619.14 EROSION CONTROL MIX	74.000 CY				
0790	620.58 EROSION CONTROL GEOTEXTILE - (NON-WOVEN - UPLAND)	1,485.000 SY				
0800	620.60 SEPARATION GEOTEXTILE -(NON- WOVEN - RUBBLE MOUND AND BOAT RAMP)	3,785.000 SY				

12/3/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 8 of 11

Proposal ID: 026824.00

Project(s): 026824.00

SECTION: 1 MAIN PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0810	626.11 PRECAST CONCRETE JUNCTION BOX	5.000 EA	_____	 _____	_____	 _____
0820	626.221 NON-METALLIC CONDUIT CONCRETE ENCASED [2.5", 2", 1"]]	1,017.000 LF	_____	 _____	_____	 _____
0830	626.222 FRP CONDUIT (1 INCH)	20.000 LF	_____	 _____	_____	 _____
0840	626.222 FRP CONDUIT (2.5 INCH)	10.000 LF	_____	 _____	_____	 _____
0850	626.38 GROUND MOUNTED CABINET FOUNDATION	1.000 EA	_____	 _____	_____	 _____
0860	626.385 METER ENCLOSURE	1.000 EA	_____	 _____	_____	 _____
0870	626.421 24 INCH DIAMETER FOUNDATION	51.000 LF	_____	 _____	_____	 _____
0880	626.74 PANELBOARD	LUMP SUM	LUMP SUM		_____	 _____
0890	626.91 POWER DISTRIBUTION PANELBOARD AND CIRCUIT BREAKERS	LUMP SUM	LUMP SUM		_____	 _____
0900	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	4,410.000 LF	_____	 _____	_____	 _____
0910	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	85.000 SF	_____	 _____	_____	 _____
0920	634.1812 1" LIQUID-TIGHT FLEXIBLE CONDUIT	12.000 LF	_____	 _____	_____	 _____

12/3/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 9 of 11

Proposal ID: 026824.00

Project(s): 026824.00

SECTION: 1

MAIN PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0930	634.1941 1" PVC CONDUIT	2,189.000 LF				
0940	634.1944 2" SCHEDULE 40 PVC CONDUIT	1,331.000 LF				
0950	634.1949 2 1/2" SCHEDULE 40 PVC CONDUIT	1,359.000 LF				
0960	634.2042 LED LUMINARIES (TYPE D1 SOLAR DOCK LIGHT)	70.000 EA				
0970	634.2042 LED LUMINARIES (TYPE OC, P1)	1.000 EA				
0980	634.2042 LED LUMINARIES (TYPE T3, R1 AND R2)	31.000 EA				
0990	634.2101 TYPE A LIGHT STANDARD	6.000 EA				
1000	634.2102 TYPE B LIGHT STANDARD	13.000 EA				
1010	634.2311 STAINLESS STEEL EXTERIOR PULL BOX	12.000 EA				
1020	634.312 # 2 AWG COPPER WIRING	1,335.000 LF				
1030	634.313 # 4/0 AWG COPPER WIRING	5,434.000 LF				
1040	634.314 #6 AWG COPPER WIRE	8,382.000 LF				

12/3/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 10 of 11

Proposal ID: 026824.00

Project(s): 026824.00

SECTION: 1

MAIN PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1050	634.316 #10 AWG COPPER WIRE	616.000 LF				
1060	634.3161 #12 AWG COPPER WIRING	3,620.000 LF				
1070	637.071 DUST CONTROL	LUMP SUM		LUMP SUM		
1080	639.18 FIELD OFFICE TYPE A	1.000 EA				
1090	641.42 SIGN POSTS	8.000 EA				
1100	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	26.750 SF				
1110	652.31 TYPE I BARRICADE	6.000 EA				
1120	652.33 DRUM	40.000 EA				
1130	652.34 CONE	25.000 EA				
1140	652.35 CONSTRUCTION SIGNS	192.000 SF				
1150	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		LUMP SUM		
1160	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM		

12/3/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 11 of 11

Proposal ID: 026824.00

Project(s): 026824.00

SECTION: 1 MAIN PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1170	659.10 MOBILIZATION	LUMP SUM		LUMP SUM		
1180	815.50 PRIVY BUILDING	LUMP SUM		LUMP SUM		
1190	832.05 SURVEY MONITORING POINT	10.000 EA				
1200	853.15 BOAT RAMP	LUMP SUM		LUMP SUM		
1210	853.50 LIFE RING ASSEMBLY	6.000 EA				
Section: 1			Total:			
			Total Bid:			