

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 026958.00

Project(s): 026958.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.24 REMOVING STUMP	9.000 EA	_____	 _____	_____	 _____
0020	202.202 REMOVING PAVEMENT SURFACE	40,500.000 SY	_____	 _____	_____	 _____
0030	202.203 PAVEMENT BUTT JOINTS	100.000 SY	_____	 _____	_____	 _____
0040	203.25 GRANULAR BORROW	100.000 CY	_____	 _____	_____	 _____
0050	204.42 REHABILITATE EXISTING SHOULDERS	10,250.000 SY	_____	 _____	_____	 _____
0060	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	350.000 T	_____	 _____	_____	 _____
0070	403.210 HOT MIX ASPHALT 9.5 MM	3,900.000 T	_____	 _____	_____	 _____
0080	403.211 HOT MIX ASPHALT (SHIMMING)	4,500.000 T	_____	 _____	_____	 _____
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	50.000 T	_____	 _____	_____	 _____
0100	409.15 BITUMINOUS TACK COAT - APPLIED	3,750.000 G	_____	 _____	_____	 _____
0110	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	250.000 CY	_____	 _____	_____	 _____
0120	511.07 COFFERDAM: 114+44 DOWNSTREAM	LUMP SUM	_____	 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 026958.00

Project(s): 026958.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	511.07 COFFERDAM: 114+44 UPSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0140	511.07 COFFERDAM: 121+44 DOWNSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0150	511.07 COFFERDAM: 121+44 UPSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0160	603.169 15 INCH CULVERT PIPE OPTION III	40.000 LF	_____	_____	_____	_____
0170	603.179 18 INCH CULVERT PIPE OPTION III	384.000 LF	_____	_____	_____	_____
0180	603.189 21 INCH CULVERT PIPE OPTION III	210.000 LF	_____	_____	_____	_____
0190	603.209 30 INCH CULVERT PIPE OPTION III	52.000 LF	_____	_____	_____	_____
0200	603.239 48 INCH CULVERT PIPE OPTION III	60.000 LF	_____	_____	_____	_____
0210	603.249 54 INCH CULVERT PIPE OPTION III	68.000 LF	_____	_____	_____	_____
0220	606.52 MAILBOX REMOVE & RESET	50.000 EA	_____	_____	_____	_____
0230	609.31 CURB TYPE 3	100.000 LF	_____	_____	_____	_____
0240	610.08 PLAIN RIPRAP	50.000 CY	_____	_____	_____	_____
0250	610.18 STONE DITCH PROTECTION	100.000 CY	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 026958.00

Project(s): 026958.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0260	613.319 EROSION CONTROL BLANKET	500.000 SY	_____	 _____	_____	 _____
0270	615.07 LOAM	1,000.000 CY	_____	 _____	_____	 _____
0280	615.10 DIRTY BORROW	100.000 CY	_____	 _____	_____	 _____
0290	618.13 SEEDING METHOD NUMBER 1	150.000 UN	_____	 _____	_____	 _____
0300	618.14 SEEDING METHOD NUMBER 2	10.000 UN	_____	 _____	_____	 _____
0310	619.12 MULCH	160.000 UN	_____	 _____	_____	 _____
0320	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	45,150.000 LF	_____	 _____	_____	 _____
0330	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	15,050.000 LF	_____	 _____	_____	 _____
0340	629.05 HAND LABOR, STRAIGHT TIME	50.000 HR	_____	 _____	_____	 _____
0350	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	350.000 HR	_____	 _____	_____	 _____
0360	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	700.000 HR	_____	 _____	_____	 _____
0370	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 026958.00

Project(s): 026958.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0380	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0390	652.33 DRUM	150.000 EA	_____	 _____	_____	 _____
0400	652.34 CONE	400.000 EA	_____	 _____	_____	 _____
0410	652.35 CONSTRUCTION SIGNS	1,250.000 SF	_____	 _____	_____	 _____
0420	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	200.000 CD	_____	 _____	_____	 _____
0430	652.38 FLAGGER	5,000.000 HR	_____	 _____	_____	 _____
0440	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0450	659.10 MOBILIZATION	LUMP SUM	_____	 LUMP SUM	_____	 _____
<b>Section: 1</b>			<b>Total:</b>		_____	 _____
			<b>Total Bid:</b>		_____	 _____