

3/6/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 5

Proposal ID: 027008.00

Project(s): 027008.00, 027010.00, 027012.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	53,140.000 SY	_____	_____	_____	_____
0020	202.203 PAVEMENT BUTT JOINTS	1,880.000 SY	_____	_____	_____	_____
0030	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	4,500.000 T	_____	_____	_____	_____
0040	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	290.000 T	_____	_____	_____	_____
0050	403.211 HOT MIX ASPHALT (SHIMMING)	1,450.000 T	_____	_____	_____	_____
0060	403.213 HOT MIX ASPHALT 12.5 MM BASE	50.000 T	_____	_____	_____	_____
0070	409.15 BITUMINOUS TACK COAT - APPLIED	4,500.000 G	_____	_____	_____	_____
0080	424.22 ASPHALT RUBBER CRACK SEALER TYPE 2, APPLIED	21,400.000 LB	_____	_____	_____	_____
0090	424.38 CRACK REPAIR - HOT POUR MASTIC	5,330.000 LB	_____	_____	_____	_____
0100	424.385 MASTIC FOR ASPHALTIC PLUG JOINT REPLACEMENT, 0.75-1.25 INCH	160.000 LF	_____	_____	_____	_____
0110	603.159 12 INCH CULVERT PIPE OPTION III	100.000 LF	_____	_____	_____	_____
0120	603.179 18 INCH CULVERT PIPE OPTION III	260.000 LF	_____	_____	_____	_____

3/6/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 5

Proposal ID: 027008.00

Project(s): 027008.00, 027010.00, 027012.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	604.161 ALTERING CATCH BASIN	20.000 EA	_____	_____	_____	_____
0140	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	108.000 EA	_____	_____	_____	_____
0150	606.178 GUARDRAIL BEAM	13.000 LF	_____	_____	_____	_____
0160	608.08 REINFORCED CONCRETE SIDEWALK	760.000 SY	_____	_____	_____	_____
0170	608.15 BRICK SIDEWALK WITH BITUMINOUS BASE	385.000 SY	_____	_____	_____	_____
0180	608.15 BRICK SIDEWALK WITH BITUMINOUS BASE CITY/STATE SUPPLIED BRICK	165.000 SY	_____	_____	_____	_____
0190	608.26 CURB RAMP DETECTABLE WARNING FIELD	900.000 SF	_____	_____	_____	_____
0200	608.46 REGRADE SIDEWALK	1,040.000 SY	_____	_____	_____	_____
0210	609.11 VERTICAL CURB TYPE 1	50.000 LF	_____	_____	_____	_____
0220	609.31 CURB TYPE 3	100.000 LF	_____	_____	_____	_____
0230	609.38 RESET CURB TYPE 1	1,970.000 LF	_____	_____	_____	_____
0240	615.07 LOAM	50.000 CY	_____	_____	_____	_____

3/6/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 5

Proposal ID: 027008.00

Project(s): 027008.00, 027010.00, 027012.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	618.13 SEEDING METHOD NUMBER 1	6.000 UN	_____	_____	_____	_____
0260	619.12 MULCH	6.000 UN	_____	_____	_____	_____
0270	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	31,760.000 LF	_____	_____	_____	_____
0280	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	10,480.000 SF	_____	_____	_____	_____
0290	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	69,440.000 LF	_____	_____	_____	_____
0300	629.05 HAND LABOR, STRAIGHT TIME	30.000 HR	_____	_____	_____	_____
0310	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	60.000 HR	_____	_____	_____	_____
0320	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	80.000 HR	_____	_____	_____	_____
0330	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____
0340	652.33 DRUM	60.000 EA	_____	_____	_____	_____
0350	652.34 CONE	270.000 EA	_____	_____	_____	_____
0360	652.35 CONSTRUCTION SIGNS	3,650.000 SF	_____	_____	_____	_____

3/6/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 5

Proposal ID: 027008.00

Project(s): 027008.00, 027010.00, 027012.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	212.000 CD	_____	_____	_____	_____
0380	652.38 FLAGGER	5,660.000 HR	_____	_____	_____	_____
0390	652.381 TRAFFIC OFFICER	320.000 HR	_____	_____	_____	_____
0400	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	5.000 EA	_____	_____	_____	_____
0410	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0420	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
Section: 1			Total:		_____	_____

SECTION: 2 SEWER ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0430	812.162 ADJUSTING SEWER MANHOLE TO GRADE	13.000 EA	_____	_____	_____	_____
Section: 2			Total:		_____	_____

Total Bid: _____