

4/25/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 4

Proposal ID: 027070.00

Project(s): 027070.00

SECTION: 1

INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.127 REMOVE EXISTING BITUMINOUS PAVEMENT	LUMP SUM	LUMP	SUM	_____	_____
0020	202.202 REMOVING PAVEMENT SURFACE	635.000 SY	_____	_____	_____	_____
0030	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	25.000 CY	_____	_____	_____	_____
0040	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	200.000 T	_____	_____	_____	_____
0050	403.213 HOT MIX ASPHALT 12.5 MM BASE	60.000 T	_____	_____	_____	_____
0060	409.15 BITUMINOUS TACK COAT - APPLIED	90.000 G	_____	_____	_____	_____
0070	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	300.000 LB	_____	_____	_____	_____
0080	503.13 REINFORCING STEEL, PLACING	300.000 LB	_____	_____	_____	_____
0090	503.17 MECHANICAL WELDED SPLICE	20.000 EA	_____	_____	_____	_____
0100	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0110	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____

4/25/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 4

Proposal ID: 027070.00

Project(s): 027070.00

SECTION: 1

INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 8 IN.	50.000 SF	_____	_____	_____	_____
0130	518.51 REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL < 8 IN.	200.000 SF	_____	_____	_____	_____
0140	520.244 BRIDGE JOINT MODIFICATION TYPE 4	4.000 EA	_____	_____	_____	_____
0150	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0160	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	275.000 LF	_____	_____	_____	_____
0170	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	3.000 EA	_____	_____	_____	_____
0180	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	1.000 EA	_____	_____	_____	_____
0190	606.1727 BRIDGE TRANSITION - TYPE 1A	8.000 EA	_____	_____	_____	_____
0200	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____
0210	610.08 PLAIN RIPRAP	15.000 CY	_____	_____	_____	_____
0220	618.141 SEEDING METHOD NUMBER 3	3.000 UN	_____	_____	_____	_____

4/25/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 4

Proposal ID: 027070.00

Project(s): 027070.00

SECTION: 1

INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	619.12 MULCH	3.000 UN	_____	_____	_____	_____
0240	619.14 EROSION CONTROL MIX	40.000 CY	_____	_____	_____	_____
0250	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2,600.000 LF	_____	_____	_____	_____
0260	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	_____	_____	_____
0270	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0280	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0290	634.2082 REMOVE EXISTING LIGHT STANDARD	1.000 EA	_____	_____	_____	_____
0300	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____
0310	652.312 TYPE III BARRICADE	6.000 EA	_____	_____	_____	_____
0320	652.33 DRUM	40.000 EA	_____	_____	_____	_____
0330	652.34 CONE	40.000 EA	_____	_____	_____	_____
0340	652.35 CONSTRUCTION SIGNS	475.000 SF	_____	_____	_____	_____

4/25/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 4

Proposal ID: 027070.00

Project(s): 027070.00

SECTION: 1

INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP	SUM	_____	_____
0360	652.38 FLAGGER	240.000 HR	_____	_____	_____	_____
0370	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0380	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____