

5/29/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 5

Proposal ID: 027078.00

Project(s): 027078.00, 028410.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.127 REMOVE EXISTING BITUMINOUS PAVEMENT	LUMP SUM		LUMP SUM		
0020	202.202 REMOVING PAVEMENT SURFACE	425.000 SY				
0030	202.30 REMOVING EXISTING CONCRETE WEARING SURFACE	LUMP SUM		LUMP SUM		
0040	203.20 COMMON EXCAVATION	15.000 CY				
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	10.000 CY				
0060	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	94.000 T				
0070	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	106.000 T				
0080	409.15 BITUMINOUS TACK COAT - APPLIED	45.000 G				
0090	424.304 HIGH MOLECULAR WEIGHT METHACRYLATE CRACK SEALER	85.000 G				
0100	502.29 STRUCTURAL CONCRETE WEARING SURFACE ON BRIDGES	LUMP SUM		LUMP SUM		
0110	502.291 SAW CUT GROOVING	LUMP SUM		LUMP SUM		

5/29/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 5

Proposal ID: 027078.00

Project(s): 027078.00, 028410.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	502.75 PLUGGING EXISTING BRIDGE DRAINS	6.000 EA	_____	 _____	_____	 _____
0130	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	7,040.000 LB	_____	 _____	_____	 _____
0140	503.13 REINFORCING STEEL, PLACING	7,040.000 LB	_____	 _____	_____	 _____
0150	503.17 MECHANICAL WELDED SPLICE	189.000 EA	_____	 _____	_____	 _____
0160	506.144 FIELD PAINTING NEW AND EXISTING STRUCTURAL STEEL	LUMP SUM	LUMP	 SUM	_____	 _____
0170	506.17 SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	LUMP SUM	LUMP	 SUM	_____	 _____
0180	506.18 CONTAINMENT AND POLLUTION CONTROL	LUMP SUM	LUMP	 SUM	_____	 _____
0190	506.191 DISPOSAL OF SPECIAL WASTE OR HAZARDOUS WASTE MATERIAL	LUMP SUM	LUMP	 SUM	_____	 _____
0200	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	 SUM	_____	 _____
0210	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	 SUM	_____	 _____
0220	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 8 IN.	140.000 SF	_____	 _____	_____	 _____

5/29/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 5

Proposal ID: 027078.00

Project(s): 027078.00, 028410.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	518.51 REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL < 8 IN.	470.000 SF	_____	 _____	_____	 _____
0240	518.60 REPAIR OF VERTICAL SURFACES < 8 IN.	80.000 SF	_____	 _____	_____	 _____
0250	518.70 REPAIR OF OVERHEAD SURFACES < 8 IN.	200.000 SF	_____	 _____	_____	 _____
0260	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP SUM		_____	 _____
0270	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	 _____	_____	 _____
0280	608.08 REINFORCED CONCRETE SIDEWALK	30.000 SY	_____	 _____	_____	 _____
0290	608.26 CURB RAMP DETECTABLE WARNING FIELD	20.000 SF	_____	 _____	_____	 _____
0300	609.21 CONCRETE SLIPFORM CURB	43.000 LF	_____	 _____	_____	 _____
0310	627.18 12 " SOLID WHITE PAVEMENT MARKING	76.000 LF	_____	 _____	_____	 _____
0320	627.55 12" TEMPORARY PAVEMENT TAPE, WHITE	180.000 LF	_____	 _____	_____	 _____
0330	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2,330.000 LF	_____	 _____	_____	 _____

5/29/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 5

Proposal ID: 027078.00

Project(s): 027078.00, 028410.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	84.000 SF	_____	 _____	_____	 _____
0350	627.77 REMOVING PAVEMENT MARKINGS	580.000 SF	_____	 _____	_____	 _____
0360	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,570.000 LF	_____	 _____	_____	 _____
0370	629.05 HAND LABOR, STRAIGHT TIME	60.000 HR	_____	 _____	_____	 _____
0380	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	30.000 HR	_____	 _____	_____	 _____
0390	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	30.000 HR	_____	 _____	_____	 _____
0400	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0410	643.72 TEMPORARY TRAFFIC SIGNAL (BRIDGE NO. 2540)	LUMP SUM	LUMP SUM		_____	 _____
0420	643.72 TEMPORARY TRAFFIC SIGNAL (BRIDGE NO. 2977)	LUMP SUM	LUMP SUM		_____	 _____
0430	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	33.000 SF	_____	 _____	_____	 _____
0440	652.311 TYPE II BARRICADE	3.000 EA	_____	 _____	_____	 _____

5/29/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 5

Proposal ID: 027078.00

Project(s): 027078.00, 028410.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0450	652.312 TYPE III BARRICADE	11.000 EA	_____	_____	_____	_____
0460	652.33 DRUM	70.000 EA	_____	_____	_____	_____
0470	652.34 CONE	70.000 EA	_____	_____	_____	_____
0480	652.35 CONSTRUCTION SIGNS	435.000 SF	_____	_____	_____	_____
0490	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	_____
0500	652.38 FLAGGER	200.000 HR	_____	_____	_____	_____
0510	652.381 TRAFFIC OFFICER	40.000 HR	_____	_____	_____	_____
0520	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	7.000 EA	_____	_____	_____	_____
0530	652.55 TEMPORARY SOUND WALLS	LUMP SUM	LUMP SUM		_____	_____
0540	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____
0550	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____