

9/16/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 7

Proposal ID: 027158.00

Project(s): 027158.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.11 CLEARING	0.900 AC				
0020	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0030	202.202 REMOVING PAVEMENT SURFACE	2,820.000 SY				
0040	203.20 COMMON EXCAVATION	510.000 CY				
0050	203.25 GRANULAR BORROW	640.000 CY				
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	410.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	520.000 CY				
0080	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	232.000 T				
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	4.000 T				
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	160.000 T				
0110	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	100.000 T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	190.000 G				

9/16/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 7

Proposal ID: 027158.00

Project(s): 027158.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	461.131 TEMPORARY PAVEMENT	320.000 T	_____	_____	_____	_____
0140	501.2391 DYNAMIC LOADING TESTS - PROVIDING FOR	4.000 CD	_____	_____	_____	_____
0150	501.54 STEEL H-BEAM PILES 117 LBS/FT, DELIVERED	525.000 LF	_____	_____	_____	_____
0160	501.541 STEEL H-BEAM PILES 117 LBS/FT, IN PLACE	525.000 LF	_____	_____	_____	_____
0170	501.90 PILE TIPS	10.000 EA	_____	_____	_____	_____
0180	501.91 PILE SPLICES	10.000 EA	_____	_____	_____	_____
0190	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0200	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP SUM	_____	_____	_____
0210	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM	LUMP SUM	_____	_____	_____
0220	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP SUM	_____	_____	_____
0230	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP SUM	_____	_____	_____

9/16/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 7

Proposal ID: 027158.00

Project(s): 027158.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	16,900.000 LB	_____	_____	_____	_____
0250	503.13 REINFORCING STEEL, PLACING	16,900.000 LB	_____	_____	_____	_____
0260	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	25,400.000 LB	_____	_____	_____	_____
0270	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	25,400.000 LB	_____	_____	_____	_____
0280	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM	LUMP	SUM	_____	_____
0290	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM	LUMP	SUM	_____	_____
0300	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	SUM	_____	_____
0310	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	SUM	_____	_____
0320	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA	_____	_____	_____	_____
0330	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0340	510.10 SPECIAL DETOUR, VEHICULAR AND PEDESTRIAN TRAFFIC NOT SEPARATED	LUMP SUM	LUMP	SUM	_____	_____

9/16/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 7

Proposal ID: 027158.00

Project(s): 027158.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	511.07 COFFERDAM: ABUT NO.1	LUMP SUM	LUMP	SUM	_____	_____
0360	511.07 COFFERDAM: ABUT NO.2	LUMP SUM	LUMP	SUM	_____	_____
0370	512.081 FRENCH DRAINS	LUMP SUM	LUMP	SUM	_____	_____
0380	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0390	519.60 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	64.000 LF	_____	_____	_____	_____
0400	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0410	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	_____	_____	_____
0420	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	39,900.000 LF	_____	_____	_____	_____
0430	530.31 GFRP, REINFORCEMENT BARS, PLACING	39,900.000 LF	_____	_____	_____	_____
0440	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	525.000 LF	_____	_____	_____	_____
0450	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	50.000 LF	_____	_____	_____	_____

9/16/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 7

Proposal ID: 027158.00

Project(s): 027158.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	1.000 EA	_____	_____	_____	_____
0470	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	_____	_____	_____
0480	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA	_____	_____	_____	_____
0490	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA	_____	_____	_____	_____
0500	610.08 PLAIN RIPRAP	1,400.000 CY	_____	_____	_____	_____
0510	610.18 STONE DITCH PROTECTION	12.000 CY	_____	_____	_____	_____
0520	610.213 VOID FILLED RIPRAP	390.000 CY	_____	_____	_____	_____
0530	613.319 EROSION CONTROL BLANKET	640.000 SY	_____	_____	_____	_____
0540	615.07 LOAM	51.000 CY	_____	_____	_____	_____
0550	618.14 SEEDING METHOD NUMBER 2	9.000 UN	_____	_____	_____	_____
0560	619.12 MULCH	9.000 UN	_____	_____	_____	_____
0570	619.14 EROSION CONTROL MIX	110.000 CY	_____	_____	_____	_____

9/16/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 7

Proposal ID: 027158.00

Project(s): 027158.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	620.58 EROSION CONTROL GEOTEXTILE	2,200.000 SY	_____	_____	_____	_____
0590	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,700.000 LF	_____	_____	_____	_____
0600	627.77 REMOVING PAVEMENT MARKINGS	190.000 SF	_____	_____	_____	_____
0610	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	2,950.000 LF	_____	_____	_____	_____
0620	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	_____	_____	_____
0630	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0640	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0650	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0660	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0670	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	_____	_____	_____
0680	652.312 TYPE III BARRICADE	4.000 EA	_____	_____	_____	_____
0690	652.33 DRUM	50.000 EA	_____	_____	_____	_____

9/16/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 7

Proposal ID: 027158.00

Project(s): 027158.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0700	652.34 CONE	100.000 EA	_____	_____	_____	_____
0710	652.35 CONSTRUCTION SIGNS	400.000 SF	_____	_____	_____	_____
0720	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM	_____	_____	_____
0730	652.38 FLAGGER	520.000 HR	_____	_____	_____	_____
0740	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	_____	_____	_____
0750	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM	_____	_____	_____
0760	659.10 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0770	660.21 ON-THE-JOB TRAINING (BID)	1,000.000 HR	_____	_____	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____