

3/11/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 5

Proposal ID: 027526.00

Project(s): 027526.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	44,800.000 SY	_____	 _____	_____	 _____
0020	202.203 PAVEMENT BUTT JOINTS	80.000 SY	_____	 _____	_____	 _____
0030	205.412 RECONSTRUCTION OF EXISTING SHOULDER	21,000.000 SY	_____	 _____	_____	 _____
0040	304.103 AGGREGATE SUBBASE - GRAVEL (TRUCK MEASURE)	80.000 CY	_____	 _____	_____	 _____
0050	307.335 FULL DEPTH RECYCLED PAVEMENT(W EMULSIFIED ASPHALT STABILIZER) 5 IN. DEPTH	53,100.000 SY	_____	 _____	_____	 _____
0060	308.36 FULL DEPTH RECYCLED PAVEMENT WITH CEMENT	29,300.000 SY	_____	 _____	_____	 _____
0070	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	120.000 T	_____	 _____	_____	 _____
0080	403.2101 9.5 MM POLYMER MODIFIED HMA	7,300.000 T	_____	 _____	_____	 _____
0090	403.211 HOT MIX ASPHALT (SHIMMING)	60.000 T	_____	 _____	_____	 _____
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	12,000.000 T	_____	 _____	_____	 _____
0110	409.15 BITUMINOUS TACK COAT - APPLIED	6,600.000 G	_____	 _____	_____	 _____

3/11/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 5

Proposal ID: 027526.00

Project(s): 027526.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	340.000 CY	_____	_____	_____	_____
0130	603.179 18 INCH CULVERT PIPE OPTION III	388.000 LF	_____	_____	_____	_____
0140	603.199 24 INCH CULVERT PIPE OPTION III	120.000 LF	_____	_____	_____	_____
0150	603.219 36 INCH CULVERT PIPE OPTION III	67.000 LF	_____	_____	_____	_____
0160	603.55 CONCRETE PIPE TIES	2.000 GP	_____	_____	_____	_____
0170	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	950.000 LF	_____	_____	_____	_____
0180	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	12.500 LF	_____	_____	_____	_____
0190	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	12.500 LF	_____	_____	_____	_____
0200	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	11.000 EA	_____	_____	_____	_____
0210	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	1.000 EA	_____	_____	_____	_____
0220	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA	_____	_____	_____	_____

3/11/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 5

Proposal ID: 027526.00

Project(s): 027526.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	26.000 EA	_____	 _____	_____	 _____
0240	606.356 UNDERDRAIN DELINEATOR POST	35.000 EA	_____	 _____	_____	 _____
0250	609.31 CURB TYPE 3	610.000 LF	_____	 _____	_____	 _____
0260	610.08 PLAIN RIPRAP	70.000 CY	_____	 _____	_____	 _____
0270	610.18 STONE DITCH PROTECTION	1,200.000 CY	_____	 _____	_____	 _____
0280	613.319 EROSION CONTROL BLANKET	10,500.000 SY	_____	 _____	_____	 _____
0290	618.14 SEEDING METHOD NUMBER 2	430.000 UN	_____	 _____	_____	 _____
0300	619.12 MULCH	430.000 UN	_____	 _____	_____	 _____
0310	620.54 STABILIZATION/REINFORCEMENT GEOTEXTILE	1,780.000 SY	_____	 _____	_____	 _____
0320	620.58 EROSION CONTROL GEOTEXTILE	3,710.000 SY	_____	 _____	_____	 _____
0330	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	70,100.000 LF	_____	 _____	_____	 _____
0340	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	100.000 SF	_____	 _____	_____	 _____

3/11/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 5

Proposal ID: 027526.00

Project(s): 027526.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	70,100.000 LF	_____	_____	_____	_____
0360	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	_____	_____	_____
0370	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	270.000 HR	_____	_____	_____	_____
0380	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0390	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	540.000 HR	_____	_____	_____	_____
0400	631.22 FRONT END LOADER (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0410	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0420	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____
0430	652.33 DRUM	100.000 EA	_____	_____	_____	_____
0440	652.34 CONE	120.000 EA	_____	_____	_____	_____
0450	652.35 CONSTRUCTION SIGNS	1,650.000 SF	_____	_____	_____	_____

3/11/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 5

Proposal ID: 027526.00

Project(s): 027526.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	160.000 CD	_____	_____	_____	_____
0470	652.38 FLAGGER	4,000.000 HR	_____	_____	_____	_____
0480	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____
0490	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____