

8/5/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 4

Proposal ID: 027532.00

Project(s): 027532.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0020	202.202 REMOVING PAVEMENT SURFACE	910.000 SY				
0030	203.20 COMMON EXCAVATION	850.000 CY				
0040	203.24 COMMON BORROW	50.000 CY				
0050	203.25 GRANULAR BORROW	750.000 CY				
0060	203.33 SPECIAL FILL	180.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	720.000 CY				
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	170.000 T				
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	6.000 T				
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	160.000 T				
0110	409.15 BITUMINOUS TACK COAT - APPLIED	80.000 G				
0120	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM				

8/5/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 4

Proposal ID: 027532.00

Project(s): 027532.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0140	511.07 COFFERDAM: UPSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0150	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0160	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0170	534.71 PRECAST CONCRETE BOX CULVERT	LUMP SUM	LUMP	SUM	_____	_____
0180	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	387.500 LF	_____	_____	_____	_____
0190	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	4.000 EA	_____	_____	_____	_____
0200	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____
0210	610.18 STONE DITCH PROTECTION	10.000 CY	_____	_____	_____	_____
0220	610.212 STREAMBED ROCK FEATURES	12.000 CY	_____	_____	_____	_____
0230	610.213 VOID FILLED RIPRAP	620.000 CY	_____	_____	_____	_____
0240	613.319 EROSION CONTROL BLANKET	50.000 SY	_____	_____	_____	_____

8/5/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 4

Proposal ID: 027532.00

Project(s): 027532.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	615.07 LOAM	40.000 CY	_____	_____	_____	_____
0260	618.14 SEEDING METHOD NUMBER 2	7.000 UN	_____	_____	_____	_____
0270	619.12 MULCH	7.000 UN	_____	_____	_____	_____
0280	619.14 EROSION CONTROL MIX	80.000 CY	_____	_____	_____	_____
0290	620.58 EROSION CONTROL GEOTEXTILE	470.000 SY	_____	_____	_____	_____
0300	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,650.000 LF	_____	_____	_____	_____
0310	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	_____	_____	_____
0320	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0330	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0340	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____
0350	652.312 TYPE III BARRICADE	2.000 EA	_____	_____	_____	_____
0360	652.33 DRUM	50.000 EA	_____	_____	_____	_____

8/5/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 4

Proposal ID: 027532.00

Project(s): 027532.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	652.34 CONE	50.000 EA	_____	_____	_____	_____
0380	652.35 CONSTRUCTION SIGNS	500.000 SF	_____	_____	_____	_____
0390	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM	_____	_____	_____
0400	652.38 FLAGGER	240.000 HR	_____	_____	_____	_____
0410	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	_____	_____	_____
0420	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM	_____	_____	_____
0430	659.10 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
Section: 1			Total:	_____	_____	_____
			Total Bid:	_____	_____	_____