

8/25/2026

## Maine Department of Transportation

## Proposal Schedule of Items

Page 1 of 7

Proposal ID: 028262.00

Project(s): 028262.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal<br>Line<br>Number | Item ID<br>Description                                       | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|--------------------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |                                                              |                                      | Dollars    | Cents | Dollars    | Cents |
| 0010                       | 202.19<br>REMOVING EXISTING BRIDGE                           | LUMP SUM                             |            |       |            |       |
| 0020                       | 202.202<br>REMOVING PAVEMENT SURFACE                         | 130.000<br>SY                        |            |       |            |       |
| 0030                       | 203.20<br>COMMON EXCAVATION                                  | 900.000<br>CY                        |            |       |            |       |
| 0040                       | 203.25<br>GRANULAR BORROW                                    | 540.000<br>CY                        |            |       |            |       |
| 0050                       | 203.33<br>SPECIAL FILL                                       | 300.000<br>CY                        |            |       |            |       |
| 0060                       | 206.082<br>STRUCTURAL EARTH EXCAVATION -<br>MAJOR STRUCTURES | 890.000<br>CY                        |            |       |            |       |
| 0070                       | 304.10<br>AGGREGATE SUBBASE COURSE -<br>GRAVEL               | 970.000<br>CY                        |            |       |            |       |
| 0080                       | 403.208<br>HOT MIX ASPHALT 12.5 MM HMA<br>SURFACE            | 140.000<br>T                         |            |       |            |       |
| 0090                       | 403.213<br>HOT MIX ASPHALT 12.5 MM BASE                      | 220.000<br>T                         |            |       |            |       |
| 0100                       | 409.15<br>BITUMINOUS TACK COAT - APPLIED                     | 55.000<br>G                          |            |       |            |       |
| 0110                       | 461.131<br>TEMPORARY PAVEMENT                                | 160.000<br>T                         |            |       |            |       |
| 0120                       | 501.231<br>DYNAMIC LOADING TEST                              | 2.000<br>EA                          |            |       |            |       |

8/25/2026

## Maine Department of Transportation

## Proposal Schedule of Items

Page 2 of 7

Proposal ID: 028262.00

Project(s): 028262.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal<br>Line<br>Number | Item ID<br>Description                                                          | Approximate<br>Quantity and<br>Units | Unit Price |           | Bid Amount |           |
|----------------------------|---------------------------------------------------------------------------------|--------------------------------------|------------|-----------|------------|-----------|
|                            |                                                                                 |                                      | Dollars    | Cents     | Dollars    | Cents     |
| 0130                       | 501.50<br>STEEL H-BEAM PILES 89 LBS/FT,<br>DELIVERED                            | 525.000<br>LF                        | _____      | <br>_____ | _____      | <br>_____ |
| 0140                       | 501.501<br>STEEL H-BEAM PILES 89 LBS/FT, IN<br>PLACE                            | 525.000<br>LF                        | _____      | <br>_____ | _____      | <br>_____ |
| 0150                       | 501.90<br>PILE TIPS                                                             | 10.000<br>EA                         | _____      | <br>_____ | _____      | <br>_____ |
| 0160                       | 501.91<br>PILE SPLICES                                                          | 10.000<br>EA                         | _____      | <br>_____ | _____      | <br>_____ |
| 0170                       | 501.92<br>PILE DRIVING EQUIPMENT<br>MOBILIZATION                                | LUMP SUM                             |            | LUMP SUM  | _____      | <br>_____ |
| 0180                       | 502.219<br>STRUCTURAL CONCRETE,<br>ABUTMENTS AND RETAINING WALLS                | LUMP SUM                             |            | LUMP SUM  | _____      | <br>_____ |
| 0190                       | 502.26<br>STRUCTURAL CONCRETE ROADWAY<br>AND SIDEWALK SLABS ON STEEL<br>BRIDGES | LUMP SUM                             |            | LUMP SUM  | _____      | <br>_____ |
| 0200                       | 502.291<br>SAW CUT GROOVING                                                     | LUMP SUM                             |            | LUMP SUM  | _____      | <br>_____ |
| 0210                       | 502.31<br>STRUCTURAL CONCRETE<br>APPROACH SLABS                                 | LUMP SUM                             |            | LUMP SUM  | _____      | <br>_____ |
| 0220                       | 502.49<br>STRUCTURAL CONCRETE CURBS<br>AND SIDEWALKS                            | LUMP SUM                             |            | LUMP SUM  | _____      | <br>_____ |
| 0230                       | 503.12<br>REINFORCING STEEL, FABRICATED<br>AND DELIVERED                        | 21,800.000<br>LB                     | _____      | <br>_____ | _____      | <br>_____ |

8/25/2026

## Maine Department of Transportation

## Proposal Schedule of Items

Page 3 of 7

Proposal ID: 028262.00

Project(s): 028262.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal<br>Line<br>Number | Item ID<br>Description                                                         | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|--------------------------------------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |                                                                                |                                      | Dollars    | Cents | Dollars    | Cents |
| 0240                       | 503.13<br>REINFORCING STEEL, PLACING                                           | 21,800.000<br>LB                     | _____      | _____ | _____      | _____ |
| 0250                       | 503.19<br>LOW-CARBON, CHROMIUM<br>REINFORCEMENT - FABRICATED &<br>DELIVERED    | 5,700.000<br>LB                      | _____      | _____ | _____      | _____ |
| 0260                       | 503.20<br>LOW-CARBON, CHROMIUM<br>REINFORCEMENT - PLACING                      | 5,700.000<br>LB                      | _____      | _____ | _____      | _____ |
| 0270                       | 504.702<br>STRUCTURAL STEEL FABRICATED<br>AND DELIVERED, WELDED                | LUMP SUM                             | LUMP SUM   | _____ | _____      | _____ |
| 0280                       | 504.71<br>STRUCTURAL STEEL ERECTION                                            | LUMP SUM                             | LUMP SUM   | _____ | _____      | _____ |
| 0290                       | 505.08<br>SHEAR CONNECTORS                                                     | LUMP SUM                             | LUMP SUM   | _____ | _____      | _____ |
| 0300                       | 507.0821<br>STEEL BRIDGE RAILING, 3 BAR                                        | LUMP SUM                             | LUMP SUM   | _____ | _____      | _____ |
| 0310                       | 507.0822<br>STEEL APPROACH RAILING, 3-BAR                                      | 4.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0320                       | 510.10<br>SPECIAL DETOUR, VEHICULAR AND<br>PEDESTRIAN TRAFFIC NOT<br>SEPARATED | LUMP SUM                             | LUMP SUM   | _____ | _____      | _____ |
| 0330                       | 511.07<br>COFFERDAM: DOWNSTREAM                                                | LUMP SUM                             | LUMP SUM   | _____ | _____      | _____ |
| 0340                       | 511.07<br>COFFERDAM: UPSTREAM                                                  | LUMP SUM                             | LUMP SUM   | _____ | _____      | _____ |
| 0350                       | 512.081<br>FRENCH DRAINS                                                       | LUMP SUM                             | LUMP SUM   | _____ | _____      | _____ |

8/25/2026

## Maine Department of Transportation

## Proposal Schedule of Items

Page 4 of 7

Proposal ID: 028262.00

Project(s): 028262.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal<br>Line<br>Number | Item ID<br>Description                                        | Approximate<br>Quantity and<br>Units | Unit Price |          | Bid Amount |       |
|----------------------------|---------------------------------------------------------------|--------------------------------------|------------|----------|------------|-------|
|                            |                                                               |                                      | Dollars    | Cents    | Dollars    | Cents |
| 0360                       | 515.21<br>PROTECTIVE COATING FOR<br>CONCRETE SURFACES         | LUMP SUM                             |            | LUMP SUM |            |       |
| 0370                       | 526.301<br>PORTABLE CONCRETE BARRIER<br>TYPE I                | LUMP SUM                             |            | LUMP SUM |            |       |
| 0380                       | 527.34<br>WORK ZONE CRASH CUSHIONS                            | 4.000<br>UN                          |            |          |            |       |
| 0390                       | 530.30<br>GFRP, REINFORCEMENT BARS,<br>FABRICATED & DELIVERED | 23,300.000<br>LF                     |            |          |            |       |
| 0400                       | 530.31<br>GFRP, REINFORCEMENT BARS,<br>PLACING                | 23,300.000<br>LF                     |            |          |            |       |
| 0410                       | 606.1301<br>31" W-BM GR, MID-WAY SPLICE-SGL<br>FACED          | 200.000<br>LF                        |            |          |            |       |
| 0420                       | 606.1305<br>31" W-BM GR, MID-WAY SPLICE<br>FLARED TERMINAL    | 4.000<br>EA                          |            |          |            |       |
| 0430                       | 606.1721<br>BRIDGE TRANSITION - TYPE 1                        | 4.000<br>EA                          |            |          |            |       |
| 0440                       | 606.353<br>REFLECTORIZED FLEXIBLE<br>GUARDRAIL MARKER         | 8.000<br>EA                          |            |          |            |       |
| 0450                       | 610.08<br>PLAIN RIPRAP                                        | 5.000<br>CY                          |            |          |            |       |
| 0460                       | 610.16<br>HEAVY RIPRAP                                        | 760.000<br>CY                        |            |          |            |       |

8/25/2026

## Maine Department of Transportation

## Proposal Schedule of Items

Page 5 of 7

Proposal ID: 028262.00

Project(s): 028262.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal<br>Line<br>Number | Item ID<br>Description                                         | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|----------------------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |                                                                |                                      | Dollars    | Cents | Dollars    | Cents |
| 0470                       | 610.18<br>STONE DITCH PROTECTION                               | 10.000<br>CY                         | _____      | _____ | _____      | _____ |
| 0480                       | 610.212<br>STREAMBED ROCK FEATURES                             | 8.000<br>CY                          | _____      | _____ | _____      | _____ |
| 0490                       | 610.214<br>VOID-FILLED HEAVY RIPRAP                            | 990.000<br>CY                        | _____      | _____ | _____      | _____ |
| 0500                       | 613.319<br>EROSION CONTROL BLANKET                             | 50.000<br>SY                         | _____      | _____ | _____      | _____ |
| 0510                       | 615.07<br>LOAM                                                 | 64.000<br>CY                         | _____      | _____ | _____      | _____ |
| 0520                       | 618.14<br>SEEDING METHOD NUMBER 2                              | 11.000<br>UN                         | _____      | _____ | _____      | _____ |
| 0530                       | 619.12<br>MULCH                                                | 11.000<br>UN                         | _____      | _____ | _____      | _____ |
| 0540                       | 619.14<br>EROSION CONTROL MIX                                  | 64.000<br>CY                         | _____      | _____ | _____      | _____ |
| 0550                       | 620.58<br>EROSION CONTROL GEOTEXTILE                           | 1,550.000<br>SY                      | _____      | _____ | _____      | _____ |
| 0560                       | 627.18<br>12 " SOLID WHITE PAVEMENT<br>MARKING                 | 24.000<br>LF                         | _____      | _____ | _____      | _____ |
| 0570                       | 627.733<br>4" WHITE OR YELLOW PAINTED<br>PAVEMENT MARKING LINE | 550.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0580                       | 627.77<br>REMOVING PAVEMENT MARKINGS                           | 370.000<br>SF                        | _____      | _____ | _____      | _____ |

8/25/2026

## Maine Department of Transportation

## Proposal Schedule of Items

Page 6 of 7

Proposal ID: 028262.00

Project(s): 028262.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal<br>Line<br>Number | Item ID<br>Description                                                          | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|---------------------------------------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |                                                                                 |                                      | Dollars    | Cents | Dollars    | Cents |
| 0590                       | 627.78<br>TEMPORARY 4 INCH PAINTED<br>PAVEMENT MARKING LINE, WHITE<br>OR YELLOW | 1,050.000<br>LF                      | _____      | _____ | _____      | _____ |
| 0600                       | 629.05<br>HAND LABOR, STRAIGHT TIME                                             | 20.000<br>HR                         | _____      | _____ | _____      | _____ |
| 0610                       | 631.12<br>ALL PURPOSE EXCAVATOR<br>(INCLUDING OPERATOR)                         | 20.000<br>HR                         | _____      | _____ | _____      | _____ |
| 0620                       | 631.14<br>GRADER (INCLUDING OPERATOR)                                           | 10.000<br>HR                         | _____      | _____ | _____      | _____ |
| 0630                       | 631.15<br>ROLLER, EARTH AND BASE COURSE<br>(INCLUDING OPERATOR )                | 10.000<br>HR                         | _____      | _____ | _____      | _____ |
| 0640                       | 631.172<br>TRUCK - LARGE (INCLUDING<br>OPERATOR)                                | 20.000<br>HR                         | _____      | _____ | _____      | _____ |
| 0650                       | 631.22<br>FRONT END LOADER (INCLUDING<br>OPERATOR)                              | 20.000<br>HR                         | _____      | _____ | _____      | _____ |
| 0660                       | 639.19<br>FIELD OFFICE TYPE B                                                   | 1.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0670                       | 643.72<br>TEMPORARY TRAFFIC SIGNAL                                              | LUMP SUM                             | LUMP SUM   |       | _____      | _____ |
| 0680                       | 652.312<br>TYPE III BARRICADE                                                   | 4.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0690                       | 652.33<br>DRUM                                                                  | 25.000<br>EA                         | _____      | _____ | _____      | _____ |
| 0700                       | 652.34<br>CONE                                                                  | 50.000<br>EA                         | _____      | _____ | _____      | _____ |

8/25/2026

## Maine Department of Transportation

## Proposal Schedule of Items

Page 7 of 7

Proposal ID: 028262.00

Project(s): 028262.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal<br>Line<br>Number | Item ID<br>Description                                          | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|-----------------------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |                                                                 |                                      | Dollars    | Cents | Dollars    | Cents |
| 0710                       | 652.35<br>CONSTRUCTION SIGNS                                    | 400.000<br>SF                        |            |       |            |       |
| 0720                       | 652.361<br>MAINTENANCE OF TRAFFIC<br>CONTROL DEVICES            | LUMP SUM                             |            |       |            |       |
| 0730                       | 652.38<br>FLAGGER                                               | 400.000<br>HR                        |            |       |            |       |
| 0740                       | 656.75<br>TEMPORARY SOIL EROSION AND<br>WATER POLLUTION CONTROL | LUMP SUM                             |            |       |            |       |
| 0750                       | 659.10<br>MOBILIZATION                                          | LUMP SUM                             |            |       |            |       |
| Section: 1                 |                                                                 |                                      | Total:     |       |            |       |
|                            |                                                                 |                                      | Total Bid: |       |            |       |