

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 028850.00

Project(s): 028850.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	403.210 HOT MIX ASPHALT 9.5 MM	20.000 T	_____	 _____	_____	 _____
0020	409.15 BITUMINOUS TACK COAT - APPLIED	10.000 G	_____	 _____	_____	 _____
0030	604.169 CHANGE CATCH BASIN GRATE TO ADA COMPLIANT	1.000 EA	_____	 _____	_____	 _____
0040	608.26 CURB RAMP DETECTABLE WARNING FIELD	170.000 SF	_____	 _____	_____	 _____
0050	608.45 CONSTRUCT SIDEWALK	40.000 SY	_____	 _____	_____	 _____
0060	608.46 REGRAIDING SIDEWALK	100.000 SY	_____	 _____	_____	 _____
0070	609.11 VERTICAL CURB TYPE 1	10.000 LF	_____	 _____	_____	 _____
0080	609.221 TERMINAL CURB TYPE 1	50.000 LF	_____	 _____	_____	 _____
0090	609.31 CURB TYPE 3	80.000 LF	_____	 _____	_____	 _____
0100	609.38 RESET CURB TYPE 1	40.000 LF	_____	 _____	_____	 _____
0110	615.07 LOAM	8.000 CY	_____	 _____	_____	 _____
0120	618.13 SEEDING METHOD NUMBER 1	1.000 UN	_____	 _____	_____	 _____
0130	619.12 MULCH	1.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 028850.00

Project(s): 028850.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0140	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	920.000 SF	_____	 _____	_____	 _____
0150	629.05 HAND LABOR, STRAIGHT TIME	15.000 HR	_____	 _____	_____	 _____
0160	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	264.000 SF	_____	 _____	_____	 _____
0170	652.33 DRUM	20.000 EA	_____	 _____	_____	 _____
0180	652.34 CONE	100.000 EA	_____	 _____	_____	 _____
0190	652.35 CONSTRUCTION SIGNS	300.000 SF	_____	 _____	_____	 _____
0200	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		 LUMP SUM	_____	 _____
0210	652.38 FLAGGER	300.000 HR	_____	 _____	_____	 _____
0220	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0230	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____