

2/3/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 3

Proposal ID: 028864.00

Project(s): 028864.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.2023 REMOVING PAVEMENT SURFACE - MEDIUM CUT DRUM	64,380.000 SY	_____	_____	_____	_____
0020	202.203 PAVEMENT BUTT JOINTS	2,300.000 SY	_____	_____	_____	_____
0030	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	80.000 T	_____	_____	_____	_____
0040	403.2111 9.5 MM POLYMER MODIFIED HMA (SHIM)	4,790.000 T	_____	_____	_____	_____
0050	403.213 HOT MIX ASPHALT 12.5 MM BASE	135.000 T	_____	_____	_____	_____
0060	409.15 BITUMINOUS TACK COAT - APPLIED	2,300.000 G	_____	_____	_____	_____
0070	410.153 EMULSIFIED ASPHALT SEALCOAT WITH GRIT, APPLIED	32,970.000 SY	_____	_____	_____	_____
0080	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	20.000 CY	_____	_____	_____	_____
0090	424.22 ASPHALT RUBBER CRACK SEALER TYPE 2, APPLIED	35,700.000 LB	_____	_____	_____	_____
0100	424.38 CRACK REPAIR - HOT POUR MASTIC	4,200.000 LB	_____	_____	_____	_____
0110	462.301 POLYMER MODIFIED ULTRATHIN BONDED WEARING COURSE	130,800.000 SY	_____	_____	_____	_____

2/3/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 3

Proposal ID: 028864.00

Project(s): 028864.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	150.000 LF	_____	_____	_____	_____
0130	606.356 UNDERDRAIN DELINEATOR POST	4.000 EA	_____	_____	_____	_____
0140	609.31 CURB TYPE 3	1,251.000 LF	_____	_____	_____	_____
0150	613.319 EROSION CONTROL BLANKET	200.000 SY	_____	_____	_____	_____
0160	618.14 SEEDING METHOD NUMBER 2	200.000 UN	_____	_____	_____	_____
0170	619.12 MULCH	200.000 UN	_____	_____	_____	_____
0180	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	130,430.000 LF	_____	_____	_____	_____
0190	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	8.000 SF	_____	_____	_____	_____
0200	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	260,860.000 LF	_____	_____	_____	_____
0210	629.05 HAND LABOR, STRAIGHT TIME	50.000 HR	_____	_____	_____	_____
0220	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	200.000 HR	_____	_____	_____	_____
0230	631.133 SKID STEER (INCLUDING OPERATOR)	50.000 HR	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 3

Proposal ID: 028864.00

Project(s): 028864.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	400.000 HR	_____	_____	_____	_____
0250	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____
0260	652.33 DRUM	30.000 EA	_____	_____	_____	_____
0270	652.34 CONE	270.000 EA	_____	_____	_____	_____
0280	652.35 CONSTRUCTION SIGNS	2,400.000 SF	_____	_____	_____	_____
0290	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	71.000 CD	_____	_____	_____	_____
0300	652.38 FLAGGER	2,640.000 HR	_____	_____	_____	_____
0310	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____
0320	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____