

**APPENDIX A**  
**Description of Materials, Supplies, Equipment and Bid Price**

**Contractor** \_\_\_\_\_

**SCHEDULE OF ITEMS**

**Price**

Item Description	Approx. Quantity and Units	Unit Price	Bid Amount
<b>603.023 Polymer Precoated Galvanized Corrugated Steel Pipe (PPGCMP)</b>	<b>80 LF</b>	\$	\$
<b>96" Polymer Precoated, Galvanized Corrugated Steel Pipe and 3 Culvert Couplers</b>			
<b>TOTAL</b>			\$

Description: The Contractor shall furnish and deliver the materials listed in the Schedule of Items in this Appendix in accordance with the contract documents. The culvert pipe and associated pipe ties must meet the requirements of the State of Maine, Department of Transportation, Standard Specifications, Revision of December 2002 including, but not limited to Section 603 - Pipe Culverts and Storm Drains, Subsections 603.02 – Materials and 603.03 - Construction Requirements, Section 700 – Materials, Subsection 707.07 – Polymer Precoated, Galvanized Corrugated Steel Pipe, Standard Details Revision of December 2002, as updated through advertisement, Supplemental Specifications, Special Provisions, and Contract Agreement. Pipe of the different types and sizes, will be measured by the length in linear foot along the invert, delivered and accepted. The accepted quantities of pipe will be paid for at the contract unit price per linear foot, for the types and sizes specified.

Delivery: Delivery of finished product shall be on or before September 3, 2012. The Contractor shall notify MaineDOT, Travis Moore, Transportation Operations Manger of Region 1 at 207-885-7013 or cell phone 207- 215-3529 a minimum of 48 hours prior to delivery. Alternative contacts are: Steve Cady @ 592-3030 or Henry McFerren @ 615-6924. The Contractor shall deliver the materials only during the following times: Monday through Thursday, 6:00 AM through 4:30 PM except for they may not deliver on holidays. The Department will not off-load the materials at the delivery site. The materials are to be delivered to the project on Rt. 101 in the town of Berwick, Maine.