

APPENDIX A
Description of Materials, Supplies, Equipment and Bid Price

Contractor _____

SCHEDULE OF ITEMS

Item Description	Approx. Quantity and Units	Unit Price	Bid Amount
Structure # 1 3'x5' Polymer Coated Metal Squat Pipes Quantity 4 – 22 Foot pieces, Quantity - 2 Polymer Coated Bands, Route 5 in Albany	88 LF	\$	\$
Structure #2 3'x5' Polymer Coated Metal Squat Pipes Quantity 2 – 24 Foot pieces Quantity 2 – 20 Foot pieces Quantity 2 – Polymer Coated Bands Route 26 in Grafton	88 LF		
TOTAL			\$

Description The plate arch must meet the requirements of the Plans, State of Maine, Department of Transportation, Standard Specifications, Revision of December 2002 including, but not limited to Section 509 – Structural Plate Pipes, Pipe Arches, Arches, and Metal Box Culverts, Subsections 509.02 Materials and 509.03 Fabrication and Division 700 Materials as updated through advertisement, Supplemental Specifications, Special Provisions, and Contract Agreement.

Delivery Delivery of finished product shall be on or before July 5 , 2012. The Contractor shall notify MaineDOT, Paul Picard, Transportation Operations Manager of Region 3, 207-562-4228 or cell phone 207- 446-7765 a minimum of 48 hours prior to delivery. Alternative contacts are: Dan Bradbury @ 592-3600, Joe White @ 592-5603 The Contractor shall deliver the materials only during the following times: Monday through Thursday, 6:00 AM through 4:30 PM except they may not deliver on holidays, or government closure days. The Department will off-load the materials at the delivery site. The materials shall be delivered to the MaineDOT Maintenance Lot on Route 2 in the town of Bethel, Me.