

## NOTES:

*Refer to the MaineDOT Guidelines on Crosswalks for more information.*

- 1. All Crosswalks shall meet the criteria in the Americans with Disabilities Act (ADA), 49 CFR 37, Appendix A,*
- 2. All Crosswalks shall meet the criteria in the Manual on Uniform Traffic Control (MUTCD) Section 3B.18, including appropriate signage and signalization.*
- 3. No parking shall be allowed within 20 feet of any un-signalized crosswalk (includes midblock) and 30 feet of a signalized intersection.*
- 4. Crosswalks shall be located only where there is sufficient sight distance.*
- 5. Crosswalks shall be located where the speed limit is 40 mph or less, unless at a signalized intersection.*
- 6. Crosswalks should, to the maximum extent practicable, be perpendicular to the highway.*
- 7. Crosswalks should be located a minimum distance of 400 feet apart.*
- 8. Crosswalk bars shall cover the entire curb opening. Crosswalk bars shall be a minimum of six feet in width and shall not extend more than one foot beyond the curb opening on each side. See the MaineDOT Design Guidance Minimum ADA Requirements for Pedestrian Facilities and the MaineDOT Standard Details.*